

Provo City Airport Pump Station			
DESCRIPTION	SITE		TOTAL
LIGHTING			
F1A	5		5
F1B	5		5
GEAR			
UTILITY METER	1		1
CT ENCLOSURE; 600A / NEMA 3R / 480V	1		1
MAIN SERVICE DISCONNECT; 600A / 480 / 3P /NEMA3R	1		1
RVSS; 100HP / POWER FACTOR CORRECTION	2		2
DISCONNECTS 30A/480V/3P	2		2
TRANSFORMER L; / 3KVA / 480/240V-120V /NEMA 3R	1		1
POWER PANELS			
PANEL MDP; /600A/480/277/MLO/3P/4W/NEMA3R/22KAIC; SURGE PROTECTION	1		1
PANEL L; / 100A/ 240/120 / 40A MAIN /3P / 4W / NEMA3R / 10KAIC / SPD	1		1
PANEL CP-2; / 600A / 480 / MLO / 3P / 3W / NEMA3R	1		1
CONTROL PANELS			
CP-2 SMALL MOTOR CONTROL PANEL	1		1