

Santaquin WRF Phase 3

DESCRIPTION	TOTAL
CENTER STREET LIFT STATION	
LIGHTING	
L1	2
WALL PACK WITH EM BATTERY	2
LARGE LED FLOOD LIGHT	1
EXIT SIGN	2
GEAR	
UTILITY METER 277/480V/3O/150A/NEMA 3R/ 65KAIC	1
ATS 480V/3O/3P/NEMA 12/65KAIC	1
05-DP-C8 277/480V/3O/4W/150A/NEMA 12/ 65KAIC	1
LIGHTING TRASNFROMER 05-XFMR-CS 10KVA/277/480V/120/208 SECONDARY/1O/65KAIC	1
LIGHTING PANEL 05-LP-CS 120/208V/1O/42KAIC	1
30HP VFD	3
PROCESS BUILDINGS	
GEAR	
30A DISCONNECT 480V/4W/NEMA3R	7
JUNCTIONS BOXES 16X16X8/NEMA3R	3
RECLAIMED WATER PS	
GEAR	
75 HP VFD	2
200A DISCONNECT 480V/4W/NEMA3R	2
SOLID HANDLINGS	
LIGHTING	
LARGE LED FLOOD LIGHT	1
GEAR	
600A DISCONNECT 480V/4W/NEMA 4X	1
7.5 HP VFD	2
DP-SHB 600A/3P/4W/NEMA 12/ 65KAIC	1
XFMR-LP-SHB 10KVA 277/480/ & 120/240V SECONDARY	1
LP-SHB 120/240V/22KAIC	1
MINI POWER ZONE MPZ-DE 120/240V/100A/1P/3W/A 4X/42KAIC	1
DEWATERING	
LIGHTING	
LOW BAY WITH DIMMING AND EM BATTERY	6
EXIT SIGN	1
GEAR	
600A DISCONNECT 480V/4W/NEMA 4X	1
7.5 HP VFD	2
DP-SHB 600A/3P/4W/NEMA 12/ 65KAIC	1
XFMR-LP-SHB 10KVA 277/480/ & 120/240V SECONDARY	1
LP-SHB 120/240V/22KAIC	1
MINI POWER ZONE MPZ-DE 120/240V/100A/1P/3W/A 4X/42KAIC	1