

DOWNTOWN SEWER IMPROVEMENTS AND DOWNTOWN SEWER PUMPING STATION
ISSUED FOR BID


APRIL 2024



STATE OF UTAH



SALT LAKE COUNTY



DOWNTOWN SEWER TRUNK LINE AND PUMPING STATION

HANSEN, ALLEN & LUCE

859 W. SOUTH JORDAN PKWY. SUITE 200
SOUTH JORDAN, UTAH 84095
(801) 566-5599

HANSEN, ALLEN & LUCE DESIGN TEAM

GREG S. THOMAS, P.E. – PROJECT MANAGER

AARON C. SPENCER, P.E. – PROJECT ENGINEER

ROBERT CONDER, S.E., P.E. – STRUCTURAL ENGINEER
(CONDER ENGINEERING, LLC)

ROBERT J. HILLYER, P.E. – ELECTRICAL ENGINEER
(HEATH ENGINEERING)

ROBERT J. KESLER, P.E. – HVAC ENGINEER
(HEATH ENGINEERING)

CITY OF SOUTH SALT LAKE

DENNIS PAY – CITY ENGINEER 801-483-6038

CITY HALL – THE CITY OF SOUTH SALT LAKE
220 EAST MORRIS AVENUE
SOUTH SALT LAKE CITY, UT 84115

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\G-001 COVER.DWG
FILE DATE: 4.17.2024 11:44:27 (MAJ)
2/02

INDEX OF DRAWINGS

SHEET NO.	TITLE
	GENERAL
G–001	COVER SHEET
G–002	INDEX OF DRAWINGS
G–003	ABBREVIATIONS
G–004	SYMBOLS & LEGEND
G–005	GENERAL NOTES
G–101	SHEET LOCATION MAP & SURVEY CONTROL
G–102	TEST HOLE DATA
	ARCHITECTURAL
A–101	PUMPHOUSE ELEVATIONS
A–201	SCREEN BUILDING ELEVATIONS
A–501	ARCHITECTURAL SCHEDULES
A–502	DOOR DETAILS I
A–503	DOOR DETAILS II
	CIVIL
C–101	SITE AND DEMOLITION PLAN
C–102	YARD PIPING PLAN
C–103	GRADING PLAN I
C–104	GRADING PLAN II
C–105	PUMPHOUSE DRY & WET WELL PLAN
C–106	PUMPHOUSE BUILDING FLOOR PLAN
C–107	DRY WELL SECTIONS
C–108	WET WELL SECTIONS
C–109	PUMPHOUSE BUILDING SECTIONS I
C–110	PUMPHOUSE BUILDING SECTIONS II
C–111	PUMPHOUSE PIPE, FITTING & EQUIPMENT SCHEDULE
C–201	SCREEN BUILDING TRENCH PLAN
C–202	SCREEN BUILDING FLOOR PLAN
C–203	SCREEN BUILDING SECTIONS I
C–204	SCREEN BUILDING SECTIONS II
C–401	INTERCONNECT VAULT PLAN & SECTIONS
C–402	ODOR CONTROL UNITS PLAN & SECTIONS
C–403	EXISTING WET WELL PLAN & SECTION
C–501	MISCELLANEOUS DETAILS I
C–502	MISCELLANEOUS DETAILS II
C–503	CHAIN LINK FENCE DETAILS
C–504	CANTILEVER GATE DETAILS

SHEET NO.	TITLE
	CIVIL (CONT)
C–701	SOUTH SALT LAKE STANDARD DETAILS I
C–702	SOUTH SALT LAKE STANDARD DETAILS II
C–703	SOUTH SALT LAKE STANDARD DETAILS III
C–801	MANHOLE DETAILS
C–802	MANHOLE DETAILS
C–803	MANHOLE DETAILS
C–804	MISCELLANEOUS DETAILS I
C–805	MISCELLANEOUS DETAILS II
C–806	MISCELLANEOUS DETAILS III
C–901	BYPASS PUMPING PLAN
C–902	BYPASS PUMPING PLAN
C–903	BYPASS PUMPING PLAN
C–904	BYPASS PUMPING PLAN
C–905	BYPASS PUMPING PLAN
C–906	BYPASS PUMPING PLAN
C–907	BYPASS PUMPING PLAN
C–908	BYPASS PUMPING PLAN
C–909	BYPASS PUMPING PLAN
C–910	BYPASS PUMPING PLAN
	PLAN & PROFILE
PP–101	STA 1+00 TO STA 6+00
PP–102	STA 6+00 TO STA 11+00
PP–103	STA 11+00 TO STA 16+00
PP–104	STA 16+00 TO STA 21+00
PP–105	STA 21+00 TO STA 26+00
PP–106	STA 26+00 TO STA 30+07
PP–201	WEST TEMPLE STA 22+70 TO STA 27+00
PP–202	WEST TEMPLE STA 27+00 TO STA 32+00
PP–203	WEST TEMPLE STA 32+00 TO STA 37+00
PP–204	WEST TEMPLE STA 37+00 TO STA 41+58
PP–301	LIFT STATION STORM DRAIN I
PP–302	LIFT STATION STORM DRAIN II
PP–303	LIFT STATION STORM DRAIN III

SHEET NO.	TITLE
	STRUCTURAL
S–100	GENERAL STRUCTURAL NOTES
S–101	SPECIAL INSPECTIONS
S–102	PUMPHOUSE FOUNDATION SLAB PLAN
S–103	PUMPHOUSE FOUNDATION WALL PLAN
S–104	PUMPHOUSE FLOOR SLAB & STEM WALL PLAN
S–105	PUMPHOUSE CMU WALL PLAN
S–106	PUMPHOUSE DRY WELL SECTION
S–107	PUMPHOUSE DRY & WET WELL SECTION
S–108	PUMPHOUSE WET WELL SECTIONS & DETAILS
S–109	PUMPHOUSE ROOFING PLAN
S–151	PUMPHOUSE DRY WELL CRANE PLAN
S–152	PUMPHOUSE DRY WELL CRANE SECTION
S–201	SCREEN BUILDING FOOTING & SLAB PLAN
S–202	SCREEN BUILDING FOUNDATION WALL PLAN
S–203	SCREEN BUILDING GRATING & CAP SLAB PLAN
S–204	SCREEN BUILDING UPPER FLOOR SLAB PLAN
S–205	SCREEN BUILDING CMU WALL PLAN
S–206	SCREEN BUILDING SECTIONS I
S–207	SCREEN BUILDING SECTIONS II
S–208	SCREEN BUILDING ROOFING PLAN
S–501	TYPICAL MASONRY DETAILS
S–502	TYPICAL ROOFING DETAILS I
S–503	TYPICAL ROOFING DETAILS II
S–504	CONCRETE STAIR PLANS & SECTIONS
S–505	CONCRETE COLUMN PLAN & SECTIONS
S–506	TYPICAL GUARDRAIL DETAILS
S–507	MISCELLANEOUS STRUCTURAL DETAILS I
S–508	MISCELLANEOUS STRUCTURAL DETAILS II
S–509	MISCELLANEOUS STRUCTURAL DETAILS III
S–510	MISCELLANEOUS STRUCTURAL DETAILS IV
S–511	MISCELLANEOUS STRUCTURAL DETAILS V
	PLUMBING
P–001	SCHEDULES
P–101	PUMPHOUSE DRY & WET WELL PLAN
P–102	PUMPHOUSE BUILDING FLOOR PLAN
P–201	SCREEN BUILDING TRENCH PLAN
S–501	DETAILS I
S–502	DETAILS II

SHEET NO.	TITLE
	HVAC
H–001	SCHEDULES AND DETAILS
H–100	DRY PIT PLAN
H–101	TOP FLOOR PLAN
H–300	BUILDING SECTIONS
H–501	DETAILS
H–601	CONTROL DIAGRAMS
	ELECTRICAL
E–01	SYMBOL LEGEND
E–02	PANEL AND CONDUIT SCHEDULES
ES100	CLASSIFICATION PLANS
EP100	DRY PIT POWER PLAN
EP101	TOP FLOOR POWER PLAN
EP102	DRY PIT GROUNDING PLAN
EP103	TOP FLOOR GROUNDING PLAN
EP104	LIGHTING PROTECTION PLANS
EL100	LOWER LEVEL LIGHTING PLANS
EL101	UPPER FLOOR LIGHTING PLANS
E–501	DETAILS
E–502	DETAILS
E–503	DETAILS
E–504	DETAILS
E–505	DETAILS
E–506	DETAILS
E–507	DETAILS
E–508	DETAILS
E–601	ONE–LINE DIAGRAM
E–602	CONTROL DIAGRAMS
E–603	CONTROL DIAGRAMS
I–01	P & ID SYMBOL LEGEND
I–02	P & ID SYMBOL LEGEND
I–100	DRY PIT CONTROL PLAN
I–101	TOP FLOOR CONTROL PLAN
I–301	ELECTRICAL CONTROL SECTION
I–601	ONE–LINE DIAGRAM
I–602	ONE–LINE DIAGRAM

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
REGISTERED ENGINEER

HANSEN ALLEN & LUCE, Inc. ENGINEERS

DESIGNED ACS
DRAFTED MAJ
CHECKED GST
DATE APRIL 2024

NO.	DATE	REVISIONS	BY	APVD.
3				
2				
1				

SCALE: NONE

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
GENERAL
INDEX OF DRAWINGS

SHEET G–002
126.42.300

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\G–002 INDEX OF DRAWINGS.DWG
FILE DATE: 4.8.2024 17:59:27 (MAJ)

7/04

@	AT
A	AIR/AMPERE
A/C	AIR CONDITIONING
A/R	AIR RELEASE
AASHTO	AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS
AB	ANCHOR BOLT
ABAN	ABANDON
ABND	ABANDONED
ABBR	ABBREVIATION
AC	ASPHALTIC CONCRETE / ALTERNATING CURRENT
ACI	AMERICAN CONCRETE INTERNATIONAL
ACOUS	ACOUSTIC / ACOUSTICAL
ACP	ASBESTOS CEMENT PIPE / ASPHALTIC CONCRETE PAVEMENT
ADD	ADDITIONAL
ADH	ADHESIVE
ADJ	ADJUSTABLE / ADJACENT
AFF	ABOVE FINISHED FLOOR
AISC	AMERICAN INSTITUTE OF STEEL CONSTRUCTION
ALT	ALTERNATE
ALUM	ALUMINUM / ALUM
AMB	AMBIENT
ANSI	AMERICAN NATIONAL STANDARDS INSTITUTE
API	AMERICAN PETROLEUM INSTITUTE
APPD	APPROVED
APPROX	APPROXIMATE
APPURTS	APPURTENANCES
APWA	AMERICAN PUBLIC WORKS ASSOCIATION
ARV	AIR RELEASE VALVE
ARCH	ARCHITECTURE
ASME	AMERICAN SOCIETY OF MECHANICAL ENGINEERS
ASTM	AMERICAN SOCIETY FOR TESTING AND MATERIALS
AT	ACOUSTICAL TILE
ATM	ATMOSPHERE
AUTO	AUTOMATIC
AUX	AUXILIARY
AVAR	AIR VACUUM AND AIR RELEASE
AVE	AVENUE
AWG	AMERICAN WIRE GAGE
AWPA	AMERICAN WOOD PRESERVERS ASSOCIATION
AWS	AMERICAN WELDING SOCIETY
AWWA	AMERICAN WATER WORKS ASSOCIATION
B&S	BELL AND SPIGOT
B/W	BACK OF WALL / BACK OF WALK
BC	BEGIN CURVE / BOLT CIRCLE / BETWEEN CENTERS / BACK OF CURVE
BCR	BEGIN CURB RETURN
BDRY	BOUNDARY
BF	BLIND FLANGE
BFP	BACKFLOW PREVENTER
BFV	BUTTERFLY VALVE
BGS	BELOW GROUND SURFACE
BHP	BRAKE HORSEPOWER
BLDG	BUILDING
BLK	BLACK / BLOCK
BLKG	BLOCKING
BLVD	BOULEVARD
BM	BEAM / BENCHMARK
BOA	BLOW-OFF ASSEMBLY
BOO	BOTTOM OF OPENING
BOP	BOTTOM OF PIPE
BOT	BOTTOM
BPV	BACK PRESSURE VALVE
BRG	BEARING
BRK	BRICK / BREAK
BSMT	BASEMENT
BTU	BRITISH THERMAL UNIT
BV	BALL VALVE
BVC	BEGIN VERTICAL CURVE
BWV	BACK WATER VALVE
C	CENTIGRADE / CHANNEL / CEMENT
C&G	CURB AND GUTTER
CAB	CABINET / CRUSHED AGGREGATE BASE
CAP	CAPACITY
CATS	CASING TEST STATION
CB	CATCH BASIN / CHALKBOARD / CURB
CC	CENTER TO CENTER
CD	CEILING DIFFUSER
CEM	CEMENT
CF	CURB FACE / CUBIC FOOT
CFH	CUBIC FOOT PER HOUR
CFM	CUBIC FOOT PER MINUTE
CFS	CUBIC FOOT PER SECOND
CHEM	CHEMICAL
CHG	CHANGE
CHKD	CHECKERED
CI	CAST IRON
CIP	CAST IRON PIPE / CAST IN PLACE
CIPP	CAST IN PLACE PIPE
CISP	CAST IRON SOIL PIPE
CJ	CONSTRUCTION JOINT
CL	CHLORINE GAS / CHLORINATOR / CENTERLINE / CLASS
CLF	CHAIN LINK FENCE
CLG	CEILING
CLR	CLEAR / CLEARANCE
CLSM	CONTROLLED LOW STRENGTH MATERIAL
CMC	CEMENT MORTAR-COATED
CML	CEMENT MORTAR-LINED
CML&C	CEMENT MORTAR-LINED AND COATED
CMP	CORRUGATED METAL PIPE
CMU	CONCRETE MASONRY UNIT
CO	CLEANOUT
COTG	CLEANOUT TO GRADE
COL	COLUMN
COMM	COMMUNICATION CABLE
COMP	COMPRESSOR
CONC	CONCRETE / CONCENTRIC
COND	CONDENSER / CONDENSATE
CONN	CONNECTION
CONST	CONSTRUCT / CONSTRUCTION
CONT	CONTINUED / CONTINUOUS
CONTR	CONTRACTOR
COORD	COORDINATE
COR	CORNER
CP	COPPER PIPE
CPLG	COUPLING
CPVC	CHLORINATE POLYVINYL PIPE
CSP	CORRUGATED STEEL PIPE
CSTS	CURRENT SPAN TEST STATION
CT	CERAMIC TILE
CTR	CENTER
CTS	CORROSION TEST STATION
CTSK	COUNTERSINK
CU	COPEER / CUBIC
CV	CHECK VALVE
CY	CUBIC YARD
CYL	CYLINDER
d	PENNY
DAD	DOUBLE ACTING DOOR
DB	DIRECT BURY
DBL	DOUBLE
DC	DIRECT CURRENT
DEG	DEGREE
DET	DETAIL
DF	DRINKING FOUNTAIN / DOUGLAS FIR
DG	DOOR GRILL
DH	DOUBLE HUNG
DI	DUCTILE IRON
DIP	DUCTILE IRON PIPE
DIA	DIAMETER
DIAG	DIAGONAL
DIAPH	DIAPHRAGM
DIM	DIMENSION
DIR	DIRECTION
DISCH	DISCHARGE
DIST	DISTANCE
DL	DEAD LOAD
DMH	DROP MANHOLE
DMJ	DISMANTLING JOINT
DN	DOWN
DO	DISSOLVED OXYGEN
DR	DOOR / DRAIN
DT	DRAIN TILE
DWG	DRAWING
DWLS	DOWELS
DWY	DRIVEWAY
E/O	EAST OF
EA	EACH
EB	EXPANSION BOLT OR ANCHOR
EC	END OF CURVE
ECC	ECCENTRIC
ECR	END CURB RETURN
EF	EACH FACE / EXHAUST FAN
EFF	EFFLUENT
EG	EXISTING GRADE / EDGE OF GUTTER / EXHAUST GRILLE / EXHAUST GAS
EGL	ENERGY GRADE LINE
EL	ELEVATION
ELEC	ELECTRIC / ELECTRONIC
EN	EDGE NAILING
ENCL	ENCLOSURE
ENG	ENGINE
ENGR	ENGINEER
ENT	ENTRANCE
EO	EDGE OF OIL / EMERGENCY OVERFLOW
EOP	EDGE OF PAVEMENT
EQ	EQUAL
EQUIP	EQUIPMENT
ES	EACH SIDE
ESEW	EMERGENCY SHOWER / EYE WASH
ESMT	EASEMENT
ETB	EMULSION TREATED BASE
ETC	ET CETERA
EUH	ELECTRIC UNIT HEATER
EVAP	EVAPORATOR
EVC	END VERTICAL CURVE
EW	EACH WAY / EYE WASH
EX	EXISTING
EXC	EXCAVATION / EXCAVATE
EXH	EXHAUST
EX-HY	EXTRA HEAVY
EXIST	EXISTING
EXP	EXPANSION / EXPOSED
EXT	EXTERIOR / EXTENSION
EXTR	EXTRUDED
F	FAHRENHEIT / FINISH
F TO F	FACE TO FACE
F&C	FRAME AND COVER
F&I	FURNISH AND INSTALL
FAB	FABRICATE / FABRICATION / FABRICATED
FAI	FRESH AIR INTAKE
FB	FLAT BAR / FLOOR BEAM / FIELD BLOCK
FC	FLEXIBLE COUPLING
FCA	FLANGE COUPLING ADAPTER
FCO	FLOOR CLEANOUT
FD	FLOOR DRAIN
FDR	FEEDER
FE	FIRE EXTINGUISHER
FEM	FEMALE (PIPE THREAD)
FF	FLAT FACE / FAR FACE / FINISH FLOOR
FG	FINISH GRADE
FH	FIRE HYDRANT / FLAT HEAD
FIG	FIGURE
FIN	FINISHED
FIX	FIXTURE
FL	FLOWLINE
FLEX	FLEXIBLE
FLG	FLANGE / FLOORING
FLGD	FLANGED
FLR	FLOOR
FLSG	FLASHING
FM	FACTORY MUTUAL (LAB APPROVED) / FORCE MAIN
FMH	FLEXIBLE METAL HOSE
FN	FIELD NAIL
FND	FOUNDATION
FOC	FACE OF CONCRETE / FIBER OPTIC CABLE
FOM	FACE OF MASONRY
FOS	FACE OF STUDS
FOW	FACE OF WALL
FPC	FLEXIBLE PIPE COUPLING
FPM	FEET PER MINUTE
FPS	FEET PER SECOND
FPTS	FOREIGN PIPE TEST STATION
FR	FRAME
FRP	FIBERGLASS REINFORCED PLASTIC
FS	FINISHD SURFACE / FAR SIDE / FLOOR SINK / FORGED STEEL
FT	FEET / FOOT
FTG	FOOTING
FUR	FURRING
FUT	FUTURE
FV	FIELD VERIFY
FW	FINISH WATER
FWD	FORWARD
G	GAS
GA	GAGE / GAUGE
GAL	GALLON
GALV	GALVANIZED
GANC	GUT ANCHOR
GB	GRADE BREAK
GC	GROOVED COUPLING
GE	GROOVED END
GEN	GENERAL / GENERATOR
GFA	GROOVED FLANGE ADAPTOR
GI	GALVANIZED IRON
GIP	GALVANIZED IRON PIPE
GL	GLASS / GROUND LINE / GRADE LINE
GLB	GLUE LAMINATED BEAM / GLULAM
GLV	GLOBE VALVE
GM	GAS METER
GP	GUY POLE
GPD	GALLONS PER DAY
GPH	GALLONS PER HOUR
GPM	GALLONS PER MINUTE
GR	GRADE / GUARDRAIL
GRD	GROUND
GRTG	GRATING
GSP	GALVANIZED STEEL PIPE
GV	GATE VALVE
GVL	GRAVEL
GYP	GYPSUM
H	HIGH / HEIGHT
H&V	HEATING AND VENTILATING
H/B	HOSE BIBB
HC	HOUSE CONNECTION
HD	HUB DRAIN
HDPE	HIGH-DENSITY POLYETHYLENE PIPE
HDR	HEADER
HDW	HARDWARE
HDWL	HEADWALL
HEX	HEXAGONAL
HG	MERCURY
HGL	HYDRAULIC GRADE LINE
HGR	HANGER
HM	HOLLOW METAL
HORIZ	HORIZONTAL
HP	HIGH POINT / HORSEPOWER / HIGH PRESSURE / HIGH PERFORMANCE
HPG	HIGH PRESSURE GAS
HR	HEAT RETURN / HOUR / HANDRAIL
HSL	HORIZONTALLY SLOTTED
HSS	HOLLOW STRUCTURAL SECTION
HTG	HEATING
HTR	HEATER
HV	HORIZONTAL AND VERTICAL CONTROL POINT
HVAC	HEATING, VENTILATION AND AIR CONDITIONING
HW	HOT WATER / HEADWORK
HWD	HARDWOOD
HWL	HIGH WATER LEVEL
HWO	HANDWHEEL OPERATED
HYD	HYDRAULIC / HYDRANT
I/O	INPUT/OUTPUT
I&C	INSTRUMENTATION & CONTROL
I&O	INSIDE AND OUTSIDE
IBC	INTERNATIONAL BUILDING CODE
ID	INSIDE DIAMETER
IE	INVERT ELEVATION
IF	INSIDE FACE
IJTS	INSULATING JOINT TEST STATION
IN	INCH
INCL	INCLUDE / INCLUDING
INF	INFLUENT
INSL	INSULATION / INSULATING / INSULATED
INSP	INSPECTION
INST	INSTRUMENT
INT	INTERIOR
INV	INVERT
IP	IRON PIPE
IPS	IRON PIPE SIZE
IRRIG	IRRIGATION
JAN	JANITOR
JC	JUNCTION CHAMBER
JCT	JUNCTION
JS	JUNCTION STRUCTURE
JSTS	JOISTS
JT	JOINT
k	KILO
K	KELVIN / KARAT
kg	KILOGRAM
KIP	THOUSAND POUNDS
km	KILOMETER
kV	KILOVOLT
KVA	KILOVOLT AMPHERE
kW	KILOWATT
kWh	KILOWATT HOUR
L	LETTER / LENGTH / ANGLE
LAB	LABORATORY
LAM	LAMINATED
LAT	LATERAL
LAV	LAVATORY
LB	POUND
LCP	LOCAL CONTROL PANEL
LCS	LOCAL CONTROL STATION
LD	LOCAL DEPRESSION
LDG	LANDING
LF	LINEAR FOOT
LG	LENGTH / LONG
LH	LAMP HOLE / LEFT HAND
LL	LIVE LOAD
LLH	LONG LEG HORIZONTAL
LLV	LONG LEG VERTICAL
LOC	LOCATION
LOL	LAYOUT LINE
LONG	LONGITUDINAL
LP	LOW POINT / LOW PRESSURE / LAMP POST
LPG	LIQUID PETROLEUM GAS
LT	LEFT / LIGHT
LW	LOW WATER
LWL	LOW WATER LEVEL
LWR	LOWER
m	METER
M	MALE (PIPE THREAD)
mA	MILLIAMPS
MACH	MACHINE
MAG	MAGNETIC
MAINT	MAINTENANCE
MAN	MANUAL
MAS	MASONRY
MAT	MATERIAL
MAX	MAXIMUM
MB	MAILBOX / MACHINE BOLT
MCC	MOTOR CONTROL CENTER
MCJ	MASONRY CONTROL JOINT
MCR	MIDDLE OF CURB RETURN
MEAS	MEASURE
MECH	MECHANICAL
MED	MEDIUM
MEM	MEMBER
MFR	MANUFACTURER
MFRD	MANUFACTURED
MG	MILLION GALLON
MGD	MILLION GALLON PER DAY
MH	MANHOLE / MAINTENANCE HOLE
MHW	MEAN HIGH WATER
MI	MALLEABLE IRON / MILE
MICRON	1/1,000,000 METER
MIL	MILITARY / 1/1,000TH INCH
MIN	MINIMUM / MINUTE
MIR	MIRROR
MISC	MISCELLANEOUS
MJ	MECHANICAL JOINT
MK	MARK
MLW	MEAN LOW WATER
mm	MILLIMETER
MO	MOTOR OPERATED / MASONRY OPENING
MOD	MODEL
MON	MONUMENT
MOR	MORTAR
MSL	MEAN SEA LEVEL
MTC	MECHANICAL-TYPE COUPLING
MTD	MOUNTED
MTG	MOUNTING
MTL	METAL / MATERIAL
MTR	MOTOR
MWS	MAXIMUM WATER SURFACE
N	NORTH
NaOCL	SODIUM HYPOCHLORITE
NaOH	SODIUM HYDROXIDE (CAUSTIC SODA)
NC	NORMALLY CLOSED
NEC	NATIONAL ELECTRIC CODE
NEMA	NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION
NF	NEAR FACE
NFPA	NATIONAL FIRE PROTECTION ASSOCIATION
NG	NATURAL GRADE / NATURAL GAS
NIC	NOT IN CONTRACT
NO	NUMBER / NORMALLY OPEN
NOM	NOMINAL
NPS	NOMINAL PIPE SIZE
NPT	NATIONAL PIPE THREAD
NPW	NON-POTABLE WATER
NRCP	NON-REINFORCED CONCRETE PIPE
NRS	NON-RISING STEM
NS	NEAR SIDE
NTS	NOT TO SCALE
NW	NORTHWEST
OBJ	OBJECT
OC	ON CENTER / OVER-CROSSING
OD	OUTSIDE DIAMETER / OVERALL DIMENSION
OE	OUTER EDGE
OF	OVERFLOW / OUTSIDE FACE
OFD	OVERFLOW DRAIN
OG	ORIGINAL GROUND
OH	OVERHEAD
OHP	OVERHEAD POWER LINE
OHW	OVERHEAD POWER WIRE
OPER	OPERATOR / OPERATING
OPNG	OPENING
OPP	OPPOSITE
ORIG	ORIGINAL
OS&Y	OUTSIDE SCREW AND YOKE
OSA	OUTSIDE AIR
OSHA	OCCUPATIONAL SAFETY AND HEALT ADMINISTRATION
OWG	OIL, WATER, GAS
OZ	OUNCE
P	POLE / PAGE / PIPE
P/S	POLE AND SHELF
PA	PLANTING AREA
PART	PARTITION
PAVMT	PAVEMENT
PB	POLYBUTYLENE / PULL BOX
PC	POINT OF CURVATURE / PORTLAND CEMENT
PCC	PORTLAND CEMENT CONCRETE / POINT OF COMPOUND CURVE
PCOTG	PRESSURE CLEANOUT TO GRADE
PCVC	POINT OF COMPOUND VERTICAL CURVE
PE	POLYETHYLENE / PLAIN END / PLANT EFFLUENT
PG	PRESSURE GAGE
pH	HYDROGEN ION CONCENTRATION
PI	PLANT INFLUENT / POINT OF INTERSECTION
PK	PARKING
PL	PLATE / PROPERTY LINE /PLACE
PLAS	PLASTER / PLASTIC
PLT	PLANT
PLWD	PLYWOOD
PM	PRESSED METAL
PNEU	PNEUMATIC
PNL	PANEL
POB	POINT OF BEGINNING
POC	POINT OF CONNECTION
POT	POINT OF TANGENT
PP	POWER POLE / POLYPROPYLENE
PPD	POUNDS PER DAY
PPH	POUNDS PER HOUR
PPM	POUNDS PER MINUTE / PARTS PER MILLION
PR	PAIR
PRC	POINT OF REVERSE CURVE
PRCT	PRECAST
PREFAB	PREFABRICATED
PRESS	PRESSURE
PROF	PROFILE
PROP	PROPERTY
PRV	PRESSURE REGULATING, RELIEF, OR REDUCING VALVE
PRVC	POINT OF REVERSE VERTICAL CURVE
PS	PRESSURE SWITCH / PUMP STATION
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
PSIA	POUNDS PER SQUARE INCH ABSOLUTE
PSIG	POUNDS PER SQUARE INCH GAUGE
PSV	PRESSURE SUSTAINING VALVE
PT	POINT OF TANGENCY / PAINT
PTFE	POLYTETRAFLUOROETHYLENE (TEFLON)
PV	PLUG VALVE
PVC	POLYVINYL CHLORIDE
PVDF	POLYVINYLIDENE FLUORIDE (KYNAR)
PW	POTABLE WATER
QTY	QUANTITY
QUAD	QUADRANGLE / QUADRANT
R	RADIUS / RISER / RATE OF SLOPE
R/W	RIGHT-OF-WAY
RAC	RECYCLED ASPHALT CONCRETE
RAG	RETURN AIR GRILLE
RAP	RECYLCED ASPHALT PAVEMENT
RC	REINFORCED CONCRETE
RCP	REINFORCED CONCRETE PIPE
RD	ROAD / ROOF DRAIN / ROUND
RED	REDUCER / REDUCING
REF	REFERENCE / REFER / REFRIGERATOR
REG	REGULATING
REINF	REINFORCE / REINFORCED
REQD	REQUIRED
RESIL	RESILIENT
RET	RETAINING / RETURN
REV	REVISION
REW	RECLAIMED WATER
RF	ROOF / RAISED FOUNDATION / ROUGH FACE
RFG	ROOFING
RGE	REGISTERED GEOTECHNICAL ENGINEER
RH	REDHEAD / RIGHT HAND
RL	RIDGE LINE
RM	ROOM
RMP	ROCKY MOUNTAIN POWER
RO	ROUGH OPENING / REVERSE OSMOSIS
RP	RADIUS POINT
RPM	REVOLUTIONS PER MINUTE
RR	RAILROAD
R/R	REMOVE AND REPLACE
RS	RISING STEM
RT	RIGHT
RTU	REMOTE TERMINAL UNIT
RW	REDWOOD
RWL	RAINWATER LEADER
S	SOUTH / SINK / SECOND / SLOPE / SLIP / SOCKET
S/O	SOUTH OF
SA	SAMPLE
SAN	SANITARY
SBR	STYRENE BUTADIENE (RUBBER)
SCCP	STEEL CYLINDER CONCRETE PIPE
SCR	SCREWED
SCFM	STANDARD CUBIC FEET PER MINUTE
SCH	SCHEDULE
SD	SANITARY DRAIN AND VENT / SMOKE DETECTOR
SDR	STANDARD THERMOPLASTIC PIPE DIMENSION RATIO / STORM DRAIN
SEC	SECONDARY / SECTION
SF	SQUARE FOOT (FEET)
SH	SHOWER
SHT	SHEET
SHTG	SHEATHING
SIM	SIMILAR
SLDG	SLIDING
SLG	SLUICE GATE
SOG	SLAB ON GRADE
SOL	SOLUTION
SP	STATIC PRESSURE
SPD	SUMP PUMP DRAIN
SPEC	SPECIFICATION
SQ	SQUARE
SQ IN	SQUARE INCH
SS	STAINLESS STEEL / SANITARY SEWER / SERVICE SINK
SSB	SELECT SUB-BASE
SSPWC	STANDARD SPECIFICATION FOR PUBLIC WORKS CONSTRUCTION
ST	STREET / STATE
STA	STATION
STC	SLEEVE-TYPE COUPLING
STD	STANDARD
STK	STAKE
STL	STEEL
STM	STEAM
STN	STAINLESS
STR	STRAIGHT / STRUCTURAL
STRUCT	STRUCTURE
SUBFL	SUB-FLOOR
SUCT	SUCTION
SUSP	SUSPEND / SUSPENDED
SV	SOLENOID VALVE
SW	SIDEWALK / SOUTHWEST
SWGR	SWITCHGEAR
SWR	SIDEWALL REGISTER
SY	SQUARE YARD
SYM	SYMMETRICAL / SYMBOL
T	THERMOSTAT / TREAD OF STAIR / TANGENT
T&B	TOP AND BOTTOM
T&G	TONGUE AND GROOVE
TAN	TANGENT
TBC	TOP BACK OF CURB
TBE	THREAD BOTH ENDS
TBG	TUBING
TBM	TEMPORARY BENCH MARK
TCE	TEMPORARY CONSTRUCTION EASEMENT
TCV	TEMPERATURE CONTROL VALVE
TDH	TOTAL DYNAMIC HEAD
TECH	TECHNICAL
TEL	TELEPHONE
TEMP	TEMPERATURE / TEMPORARY
TF	TOP OF FOOTING
TH	TEST HOLE
THK	THICK / THICKNESS
THR	THRESHOLD
THRD	THREADED
TK	TANK / TACK
TL	TRAVERSE LINE
TOB	TOP OF BAFFLE
TOC	TOP OF CONCRETE
TOE	THREAD ONE END
TOG	TOP OF GRATING / TOP OF GATE
TOM	TOP OF MASONRY
TOP	TOP OF PIPE
TOPO	TOPOGRAPHIC
TOS	TOP OF STEEL / TOP OF SLAB
TOW	TOP OF WALL
TP	TELEPHONE POLE / TURNING POINT / TEST PIT
TRANS	TRANSMITTER / TRANSITION / TRANSMISSION
TS	TRAFFIC SIGNAL
TV	THERMOSTATIC VALVE
TW	THERMOMETER WELL / TRAVELED WAY
TWS	TRACER WIRE STATION
TYP	TYPICAL
UB	UNION BONNET
UBC	UNIFORM BUILDING CODE / UNTREATED BASE COURSE
UC	UNDER-CROSSING
UCE	UTILITY CORRIDOR EASEMENT
UDOT	UTAH DEPARTMENT OF TRANSPORTATION
UG	UNDERGROUND
UGC	UNDERGROUND CONDUIT
UH	UNIT HEATER
UL	UNDERWRITERS LABORATORIES
UNID	UNIDENTIFIED
UNK	UNKNOWN
UNO	UNLESS NOTED OTHERWISE
UOI	UNLESS OTHERWISE INDICATED
UPS	UNINTERRUPTABLE POWER SUPPLY
USA	UNDERGROUND SERVICE ALERT
USGS	UNITED STATES GEOLOGICAL SURVEY
UW	UTILITY WATER
V	VALVE / VERTICAL / VENT / VOLT
VAC	VACUUM
VAR	VARIES / VARIABLE
VB	VALVE BOX
VC	VERTICAL CURVE
VCP	VITRIFIED CLAY PIPE
VERT	VERTICAL
VOL	VOLUME
VPI	VERTICAL POINT OF INTERSECTION
VSL	VERTICALLY SLOTTED
VTR	VENT THRU ROOF
VWM	VERIFY WITH MANUFACTURER
W	WEST / WASTE / WIDTH / WIDE FLANGE / WATER
W/	WITH
W/O	WEST OF / WITHOUT
WC	WATER COLUMN / WATER CLOSET
WCO	WALL CLEANOUT
WD	WOOD
WDW	WINDOW
WH	WATER HEATER
WI	WROUGHT IRON
WM	WATER METER
WOG	WATER, OIL, OR GAS
WP	WATERPROOFING / WORKING PRESSURE
WPJ	WEAKEN PLANE JOINT
WS	WATER SURFACE
WSP	WELDED STEEL PIPE
WSTP	WATERSTOP
WT	WEIGHT / WATER TIGHT
WWF	WELDED WIRE FABRIC
WWP	WORKING WATER PRESSURE
XCONN	CROSS CONNECTION
XS	EXTRA STRONG
XSEC	CROSS SECTION
XXS	DOUBLE EXTRA STRONG
YD	YARD
YR	YEAR
Z	ZERO / ZONE

PROJECT ABBREVIATIONS

CPP	CORRUGATED PLASTIC PIPE
GFRP	GLASS FIBER REINFORCED PIPE

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\G-003 ABBREVIATIONS.DWG
FILE DATE: 3.6.2024 11:55:32 (MAJ)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE inc
ENGINEERS

DESIGNED	ACS	3			
DRAFTED	MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY / APVD.

SCALE: NONE

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
GENERAL
ABBREVIATIONS

SHEET G-003
126.42.300

7/04


DETAIL, SECTION & ELEVATION IDENTIFICATION

NOTES:


1. IF SECTION CUT AND SECTION OR DETAIL CALL–OUT AND DETAIL ARE SHOWN ON SAME DRAWING, DRAWING NUMBER IS REPLACED BY A LINE.
2. DETAIL LETTERS "I" AND "O" NOT USED.

DETAIL IDENTIFICATION

DETAIL CALL–OUT ON SHEET C–1:




ON SHEET C–4, THIS DETAIL IS IDENTIFIED AS:




SECTION IDENTIFICATION

SECTION CUT ON SHEET C–1:




ON SHEET C–4, THIS SECTION IS IDENTIFIED AS:




ELEVATION IDENTIFICATION

ELEVATION CALL–OUT ON SHEET C–6:



ON SHEET A–1, THIS ELEVATION IS IDENTIFIED AS:



LEGEND

EXISTING

- 4-G — EXISTING GAS LINE W/ SIZE
- GS — GS — GS — EXISTING GAS SERVICE
- 10-W — EXISTING WATER LINE W/ SIZE
- WS — WS — WS — EXISTING WATER SERVICE
- 15-SS — EXISTING SANITARY SEWER W/ SIZE
- SL — SL — SL — EXISTING SANITARY SEWER LATERAL
- 24-SD — EXISTING STORM DRAIN W/ SIZE
- 12-IRR — EXISTING IRRIGATION W/ SIZE
- FO-UG — EXISTING FIBER OPTIC LINE
- T-UG — EXISTING UNDERGROUND TELEPHONE
- EXISTING CABLE TV
- P-UG — EXISTING UNDERGROUND POWER LINE
- P-OH — EXISTING OVERHEAD POWER LINE
- X — EXISTING FENCE LINE
- EXISTING RAILROAD TRACKS
- EXISTING PROPERTY LINE
- R O W — EXISTING RIGHT–OF–WAY
- EXISTING ASPHALT
- 4200 — EXISTING MAJOR CONTOUR
- EXISTING MINOR CONTOUR

- EXISTING FIRE HYDRANT
- EXISTING POWER POLE
- EXISTING POWER / LIGHT POLE COMBO
- EXISTING LIGHT POLE
- EXISTING GUY WIRE
- P — EXISTING POWER BOX
- EM — EXISTING POWER METER
- T — EXISTING TELEPHONE
- F — EXISTING FIBER OPTIC
- EXISTING CABLE
- EXISTING SIGNAL POLE
- EXISTING SIGNAL / LIGHT POLE COMBO
- EXISTING SIGNAL BOX
- EXISTING TRAFFIC LOOP
- EXISTING TRAFFIC BOX
- EXISTING IRRIGATION BOX
- EXISTING SIGN
- EXISTING TREE

- SS — EXISTING SANITARY SEWER MANHOLE
- SD — EXISTING STORM DRAIN MANHOLE
- W — EXISTING WATER MANHOLE
- G — EXISTING GAS MANHOLE
- P — EXISTING POWER MANHOLE
- T — EXISTING TELEPHONE MANHOLE
- F — EXISTING FIBER OPTICS MANHOLE
- IRR — EXISTING IRRIGATION MANHOLE
- WM — EXISTING WATER METER
- EXISTING VALVES
- EXISTING REDUCERS
- EXISTING SD CATCH BASIN
- EXISTING SD CATCH BASIN / JUNCTION BOX
- EXISTING SD JUNCTION BOX
- SD — EXISTING SD CLEANOUT BOX
- SD — EXISTING SD COMBO CATCH BASIN / CLEANOUT BOX

NEW

- 4200 — PROPOSED MAJOR CONTOUR
- PROPOSED MINOR CONTOUR
- NEW PROPERTY LINE
- NEW UTILITY LINE
- P/E — PERMANENT EASEMENT
- C/E — CONSTRUCTION EASEMENT
- R — RIDGE LINE
- GB — GRADE BREAK
- FLOW LINE
- RETAINING WALL
- NEW FENCE

- NEW INLET BOX
- NEW CAP
- NEW FIRE HYDRANT
- NEW WATER VALVE
- NEW GATE VALVE
- NEW BUTTERFLY VALVE
- NEW PLUG VALVE
- NEW LIGHT POLE

HATCHING

- CONCRETE (PLAN)
- CONCRETE (SECTION)
- GROUT
- BRICK (PLAN)
- CMU (PLAN)
- CMU (SECTION)
- STEEL (SECTION)
- DEMOLITION
- GRATING
- EARTH
- AGGREGATE
- GRAVEL
- RIPRAP
- SAND
- ASPHALT

CONTROL SYMBOLS

- BM–## — EXISTING BENCH MARK
- EXISTING HORIZONTAL CONTROL POINT
- EXISTING VERTICAL CONTROL POINT
- EXISTING HORIZONTAL & VERTICAL CONTROL POINT
- EXISTING SURVEY MONUMENT
- EXISTING SECTION MONUMENT

NOTE:
SURVEY OF EXISTING RING & COVER IS FROM CENTER OF THE COVER.

MISCELLANEOUS

- 104 — ROOM NUMBER
- 101 — DOOR NUMBER
- W1 — WINDOW NUMBER
- M–1 — METER SCHEDULE
- P–1 — PUMP SCHEDULE
- V–1 — VALVE SCHEDULE
- FE–X — NEW FIRE EXTINGUISHER TYPE (1, 2, 3, OR 4)
- CTS–1 — CATHODIC TEST STATION
- 4 — FITTING SCHEDULE
- 6 — KEY NOTES
- A — COORDINATE POINT
- ø — DIAMETER
- ∠ — ANGLE
- ℄ — CENTERLINE

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TWEEDY
STATE OF UTAH

DESIGNED	ACS	3					
DRAFTED	MAJ	2					
CHECKED	GST	1					
DATE	APRIL 2024	NO.	DATE	REVISIONS		BY	APVD.

SCALE: NONE

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
GENERAL
SYMBOLS & LEGEND

SHEET G–004
126.42.300

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\G–004 SYMBOLS & LEGEND.DWG
FILE DATE: 3.6.2024 11:54:36 (MAJ)

7/04

GENERAL NOTES

1. THESE DRAWINGS REFERENCE THE APWA STANDARD 2017 SPECIFICATIONS AND PLANS AS PUBLISHED BY UTAH T2 CENTER (435) 797–2931. WHEN REFERENCE IS MADE TO THE "STANDARD SPECIFICATIONS" THEY REFER TO THE APWA MANUAL OF STANDARD SPECIFICATIONS 2017 EDITION, WITH THE EXCEPTIONS PUBLISHED BY THE CITY OF SOUTH SALT LAKE, OR AS MODIFIED HEREIN. THE SPECIFICATIONS IN THE PROJECT MANUAL WILL GOVERN EXCEPT WHERE APWA STANDARDS ARE SPECIFIED. CONTRACTOR SHALL BE REQUIRED TO PURCHASE SUFFICIENT COPIES OF THE STANDARD SPECIFICATIONS TO BE UTILIZED AND REFERENCED FOR CONSTRUCTION. SAID STANDARD SPECIFICATIONS SHALL BE CONSIDERED PART OF THE PROJECT CONTRACT DOCUMENTS.
2. CONTRACTOR SHALL MEET ALL UTAH STATE DEPARTMENT OF ENVIRONMENTAL QUALITY AND U.S. EPA REQUIREMENTS WITH RESPECT TO THEIR RULES AND REGULATIONS.
3. STATIONING, CURVE DATA, AND STRAIGHT SECTIONS LISTED ARE GROUND DISTANCES. HORIZONTAL AND VERTICAL CONTROL IS BASED ON NAD 83, STATE PLANE, UTAH CENTRAL COORDINATE SYSTEM.
4. CONSTRUCTION OPERATIONS SHALL BE CONDUCTED, AND SIGNS, BARRICADES, AND FLASHERS SHALL BE PLACED, SO AS TO COMPLY WITH OSHA, UTAH STATE INDUSTRIAL COMMISSION, LOCAL SAFETY STANDARDS, AND MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.
5. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL UNDERGROUND UTILITIES, INCLUDING WATER LINES, STORM DRAIN LINES, TELEPHONE CABLES, GAS LINES, AND ANY OTHER OBSTRUCTION DURING THE COURSE OF CONSTRUCTION AND INSTALLATION OF THE PIPELINES. SAID UTILITIES SHALL BE RESTORED TO A CONDITION AT LEAST EQUAL TO THEIR ORIGINAL CONDITION.
6. CONTRACTOR SHALL BE RESPONSIBLE TO OBTAIN RIGHT OF INGRESS AND EGRESS SHOULD THEY VENTURE ONTO PRIVATE PROPERTY WHICH IS NOT INCLUDED IN CITY ACQUIRED RIGHTS–OF–WAY AND EASEMENTS.
7. UNLESS DETAILED, SPECIFIED, OR INDICATED OTHERWISE, CONSTRUCTION SHALL BE AS INDICATED IN THE APPLICABLE TYPICAL DETAILS AND GENERAL NOTES. TYPICAL DETAILS ARE MEANT TO APPLY EVEN THOUGH NOT REFERENCED AT SPECIFIC LOCATIONS OR IN SPECIFIC DRAWINGS.
8. CONTRACTOR SHALL BE RESPONSIBLE TO PROTECT ALL EXISTING IMPROVEMENTS DURING CONSTRUCTION AND SHALL REPLACE OR RESTORE ANY IMPROVEMENTS DAMAGED AS A RESULT OF THE CONSTRUCTION ACTIVITY AS DIRECTED BY THE ENGINEER.
9. THIS PROJECT IS LOCATED WITHIN CITY OF SOUTH SALT LAKE LIMITS AND UTA ROW. CONTRACTOR SHALL OBTAIN ALL APPLICABLE PERMITS AND APPROVALS FROM UTA AND SOUTH SALT LAKE AND SHALL COMPLY WITH SOUTH SALT LAKE AND UTA REGULATIONS FOR TRAFFIC CONTROL, SAFETY, EXCAVATION AND BACKFILL IN CITY AND UTA RIGHTS–OF–WAY, ETC.
10. RIGHT–OF–WAY LINES SHOWN ARE OBTAINED FROM MAPS FROM SALT LAKE COUNTY GIS PORTAL.
11. NO TITLE WORK WAS PERFORMED FOR USE IN THE PREPARATION OF THIS SURVEY. FOR BUILDING LINES, EASEMENTS OR RESTRICTIONS NOT SHOWN HEREON, REFER TO DEEDS, ABSTRACTS, TITLE POLICIES, SEARCHES OR COMMITMENTS, CONTRACTS AND LOCAL BUILDING AND ZONING ORDINANCES.

PROPERTY OWNER PROJECT NOTES

1. TRUCO SERVICES, 2225 S 400 W, SOUTH SALT LAKE, UT 84115, BRIAN BORLACE, 801–376–5509: CONTRACTOR SHALL INSTALL TEMPORARY CONSTRUCTION FENCING ALONG NORTHERN LIMITS OF TEMPORARY CONSTRUCTION EASEMENT. TEMPORARY CONSTRUCTION FENCING SHALL BE PERMANENT IN NATURE AS PER APWA PLAN 831. TEMPORARY CONSTRUCTION FENCING SHALL BE REMOVED AND SURFACE RESTORED ONCE CONSTRUCTION IS COMPLETE AND PERMANENT FENCING IS RESTORED.
2. MIDWEST MOTOR EXPRESS, 2200 SOUTH 400 WEST, SOUTH SALT LAKE, UT 84115, 801–485–1444: CONTRACTOR SHALL INSTALL TEMPORARY CONSTRUCTION FENCING ALONG NORTHERN LIMITS OF TEMPORARY CONSTRUCTION EASEMENT. TEMPORARY CONSTRUCTION FENCING SHALL BE PERMANENT IN NATURE AS PER APWA PLAN 831. TEMPORARY CONSTRUCTION FENCING SHALL BE REMOVED AND SURFACE RESTORED ONCE CONSTRUCTION IS COMPLETE AND PERMANENT FENCING IS RESTORED.

SOUTH SALT LAKE CITY TRAFFIC CONTROL PROJECT NOTES

1. PRIOR TO CONSTRUCTION, CONTRACTOR SHALL SUBMIT TO SOUTH SALT LAKE TRAFFIC CONTROL PLANS WHEN SUBMITTING RIGHT–OF–WAY ENCROACHMENT PERMIT. TRAFFIC CONTROL PLANS SHALL DETAIL LANE CLOSURES, FLAGGING OPERATIONS, AND REROUTING TRAFFIC INCLUDING BICYCLE AND PEDESTRIAN TRAFFIC.
2. ACCESS TO RESIDENTIAL STREETS, DRIVEWAYS, AND BUSINESS ACCESS IS TO BE MAINTAINED THROUGHOUT CONSTRUCTION UNLESS NOTED OTHERWISE.
3. WEST TEMPLE, UTOPIA AVENUE, 300 WEST, AND 600 WEST: CONTRACTOR SHALL MAINTAIN A MINIMUM OF TWO LANES OF TRAFFIC, ONE IN EACH DIRECTION AT ALL TIMES. IN THE EVENT THAT TWO LANES OF TRAFFIC CANNOT BE MAINTAINED, ONE LANE OF TRAFFIC WITH FLAGGING OPERATIONS IS ACCEPTABLE DURING ACTIVE CONSTRUCTION BUT SHALL BE RESTORED TO A MINIMUM OF TWO LANES OF TRAFFIC WHEN CONSTRUCTION IS NOT OCCURRING. CONTRACTOR SHALL PROVIDE A MINIMUM OF 72 HOURS NOTICE PRIOR TO CLOSURES.
4. ANDY AVENUE – 300 WEST TO 400 WEST: CONTRACTOR IS ALLOWED TO CLOSE ANDY AVENUE BETWEEN 300 WEST AND 400 WEST TO ALL TRAFFIC DURING CONSTRUCTION FOR A TIME PERIOD NOT TO EXCEED 7 CALENDAR DAYS. NIGHT WORK ALONG ANDY AVENUE BETWEEN 300 WEST AND 400 WEST IS ACCEPTABLE WITH PROPER SALT LAKE COUNTY APPROVALS. CONTRACTOR SHALL COORDINATE WITH HILTI (2180 SOUTH 300 WEST #105, AMBER HICKS, 480–259–1458) FOR DELIVERIES DURING ROADWAY CLOSURE.

SANITARY SEWER PROJECT NOTES

1. LOCATION OF EXISTING SANITARY SEWER LATERALS ARE APPROXIMATE. CONTRACTOR SHALL FIELD VERIFY LOCATION AND ELEVATION PRIOR TO CONSTRUCTION. LATERALS SHALL BE EXTENDED TO THE NEW SEWER LINE MAINTAINING LINE AND GRADE. CONTRACTOR SHALL IMMEDIATELY NOTIFY CITY IF LATERALS ARE FOUND THAT CANNOT BE CONNECTED TO THE NEW SEWER MAINTAINING EXISTING LINE AND GRADE.
2. RECORDS INDICATE THAT MORE THAN ONE SANITARY SEWER LATERAL MAY BE PRESENT AT SOME SEWER CONNECTIONS. CONTRACTOR SHALL FIELD VERIFY SANITARY SEWER LATERAL IS ACTIVE PRIOR TO RECONNECTING TO NEW SANITARY SEWER TRUNK LINE. COORDINATE WITH CITY PERSONNEL WHEN LATERALS ARE FOUND THAT ARE NOT ACTIVE.
3. SANITARY SEWER MANHOLES SHALL BE ABANDONED BY REMOVING THE GRATE, FRAME, RISERS, CONE, AND RISER SECTIONS TO THE BOTTOM SECTION.
4. SANITARY SEWER PIPES TO BE ABANDONED SHALL BE REMOVED A MINIMUM OF 5 FEET FROM NEW SEWER PIPELINE AND FILLED WITH CONCRETE SLURRY OR SAND SLURRY AND CAP OPEN ENDS WITH CONCRETE AT LEAST 24 INCHES.
5. MAXIMUM MEASURED SANITARY SEWER FLOWS ARE:
   a. DOWNTOWN; UTOPIA AVE TO MAIN WASTEWATER LIFT STATION: 3,900 GPM
6. FLOW CONTROL
   a. CONTRACTOR SHALL PROVIDE BYPASS OF FLOW OF SEWAGE AROUND SECTIONS OF PIPE TO BE INSTALLED OR REMOVED.
   b. CONTRACTOR SHALL PROVIDE MEANS AND EQUIPMENT (BYPASS PUMPING PLAN) FOR FLOW CONTROL OR PUMPING DURING CONSTRUCTION. BYPASS PUMPING PLAN SHALL BE SUBMITTED AT LEAST 14 CALENDAR DAYS PRIOR TO BYPASS PUMPING OPERATIONS. BYPASS PUMPING PLAN SHALL INCLUDE SEQUENCE OF DIVERSION OPERATIONS, TEMPORARY PLUGS, SILENCED BYPASS PUMPING SYSTEM, TEMPORARY VEHICLE AND PEDESTRIAN BYPASS, AND SITE REINSTATEMENT AFTER DIVERSION.
   c. CONTRACTOR SHALL BE RESPONSIBLE FOR WRITTEN NOTIFICATION TO PROPERTY OWNERS AFFECTED BY SEWER INSTALLATION AND SEWER BYPASS PUMPING.
   d. CONTRACTOR SHALL BE RESPONSIBLE FOR DAMAGES TO PROPERTY DUE TO SEWER BACKUP WHILE CONTROLLING SEWAGE FLOW.
   e. CONTRACTOR SHALL FURNISH PUMPING EQUIPMENT, CONDUITS, ETC. UNDER NO CIRCUMSTANCES SHALL BYPASSING OF UNTREATED WASTEWATER TO STORM DRAINAGE FACILITY OR SURFACE WATER COURSE BE ALLOWED.
   f. SEWER FLOW CONTROL OPERATIONS SHALL NOT CAUSE FLOODING OR DAMAGE TO PUBLIC OR PRIVATE PROPERTY. SEWAGE FLOW DIVERTED SHALL BE DISCHARGED BACK INTO SANITARY SEWER SYSTEM.
   g. CONTRACTOR SHALL PROVIDE FOR BYPASSING PIPE FLOWS AND LATERAL FLOWS. STANDBY PUMPING CAPACITY FOR 125% AT ALL TIMES.
7. ALL NEW SANITARY SEWER MANHOLES, THE WET WELL AND THE SCREEN TROUGH SHALL INCLUDE INSIDE COATING OF QUADEX® STRUCTURE GUARD® LINING SYSTEM (NO SUBSTITUTION PERMITTED) WITH A MINIMUM THICKNESS OF 150 MILS. MANHOLE BASES SHALL BE COATED PRIOR TO INSTALLATION. MANHOLE SECTIONS MAY BE FIELD COATED PRIOR TO INSTALLATION OR AFTER INSTALLATION. ALL INTERIOR SURFACES OF MANHOLES SHALL BE COATED. WET WELL AND SCREEN TROUGH SHALL BE COATED PRIOR TO THE INTRODUCTION OF SANITARY SEWER FLOWS. WET WELL, SCREEN TROUGH, AND ALL MANHOLE COATING SHALL BE AS PER MANUFACTURER RECOMMENDATIONS INCLUDING SURFACE PREPARATION. CONTRACTOR SHALL PROVIDE THIRD PARTY TESTING OF INSTALLED COATING AS PER MANUFACTURER RECOMMENDATIONS INCLUDING HIGH VOLTAGE SPARK TESTING (HOLIDAY TESTING) AND ADHESION TESTING.

PUMP STATION PROJECT NOTES

1. EXISTING PUMP STATION SHALL REMAIN IN SERVICE DURING CONSTRUCTION.
2. EXISTING PUMP STATION SHALL REMAIN AS BACKUP FOR THE NEW PUMPING STATION.
3. CONTRACTOR SHALL COORDINATE SITE ACCESS WITH SOUTH SALT LAKE.
4. CONTRACTOR SHALL MAINTAIN ACCESS TO THE EXISTING PUMP STATION FOR CITY PERSONNEL AND VEHICLES.
5. MINIMUM COVER FOR FORCEMAIN SHALL BE 4'.
6. COORDINATE WITH SOUTH SALT LAKE FOR OPERATION OF EXISTING VALVES WHEN CONNECTING NEW PIPING TO EXISTING PIPING.
7. FIELD VERIFY ALL EXISTING PIPE ELEVATIONS AND CONDITIONS PRIOR TO CONSTRUCTION.
8. ALL DISTURBANCE TO THE SITE SHALL BE RESTORED AFTER CONSTRUCTION PER SOUTH SALT LAKE STANDARDS AND AS SHOWN ON DRAWINGS.
9. WHERE NEW PIPING IS TO BE CONNECTED TO EXISTING PIPING:
   a. THE CONTRACTOR SHALL EXCAVATE A TEST PIT TO VERIFY LOCATION, ELEVATION, ORIENTATION, AND MATERIAL OF CONSTRUCTION.
   b. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL ADAPTERS, FITTINGS, AND ADDITIONAL PIPE AS REQUIRED TO COMPLETE THE CONNECTION.

UTAH DEPARTMENT OF TRANSPORTATION (UDOT) PROJECT NOTES

1. CONTRACTOR SHALL COORDINATE WITH UDOT PRIOR TO THE REMOVAL AND REPLACEMENT OF THE EXISTING UTILITY CONFLICT BOX IN ANDY AVE AS SHOWN ON THE DRAWINGS.
2. CONTRACTOR SHALL PROTECT FLOWS THROUGH THE EXISTING UDOT STORM DRAIN TRUNK LINE DURING THE REPLACEMENT OF THE UTILITY CONFLICT BOX.
3. CONTRACTOR IS RESPONSIBLE FOR THE RECONNECTION OF THE UDOT STORM DRAIN TRUNK LINE ONCE THE EXISTING UTILITY CONFLICT BOX IS REMOVED AND REPLACED PER DETAIL C ON SHEET CD–6.

UTAH TRANSIT AUTHORITY (UTA) PROJECT NOTES

1. CONTRACTOR SHALL APPLY FOR AND OBTAIN A TRAX TRACK ACCESS PERMIT FROM UTA BEFORE ANY ACCESS WILL BE ALLOWED ON UTA PROPERTY. THE CURRENT CONTACT PERSON FOR OBTAINING A TRAX TRACK ACCESS PERMIT IS JEFF WOODHEAD 385–218–8190, OR SUCH OTHER CONTACT AS SHALL BE IDENTIFIED ON UTA'S WEBSITE LOCATION NOTED BELOW. A COPY OF THE PERMIT THAT WILL NEED TO BE FILLED OUT AND SUBMITTED CAN BE FOUND ON UTA'S WEBSITE, UNDER THE TRACK ACCESS PERMIT TAB. HTTP://WWW.RIDEUTA.COM/PROPERTYMANAGEMENT
2. UTA ACCESS PERMITS WILL NOT BE ISSUED WITHOUT FIRST HAVING AN EXECUTED CONTRACTOR'S RIGHT OF ENTRY AGREEMENT, UTA HAVING RECEIVED PROOF OF INSURANCE AS PROVIDED IN THE RIGHT OF ENTRY AGREEMENT, AND VERIFICATION THAT THE CONTRACTOR AND ALL OF THE CONTRACTOR'S EMPLOYEES HAVE GONE THROUGH UTA'S ROADWAY WORKER TRAINING, IF APPLICABLE.
3. CONTRACTOR SHALL PROVIDE A RAIL MONITORING PLAN TO BE REVIEWED AND APPROVED BY UTA PRIOR TO COMMENCEMENT OF WORK. THE TOP OF RAIL SHALL NOT DEFLECT MORE THAN 1/4" VERTICALLY OR HORIZONTALLY. CONTRACTOR SHALL ALSO PROVIDE AN ESTABLISHED CONTINGENCY PLAN IN THE EVENT OF GROUND LOSS AND/OR THE RAIL DEVIATES 1/4" VERTICAL OR HORIZONTAL, THE CONTINGENCY PLAN MUST BE REVIEWED AND APPROVED BY UTA PRIOR TO COMMENCING THE WORK. IN THE EVENT THAT THE TOP OF RAIL DEFLECTS MORE THAN 1/4", OPERATIONS SHALL STOP IMMEDIATELY AND THE UTA ONSITE REPRESENTATIVE NOTIFIED. WORK SHALL NOT CONTINUE UNTIL UTA'S ENGINEER HAS DETERMINED THE APPROPRIATE ACTION REQUIRED TO PROTECT THE SAFETY, INTEGRITY, AND FUNCTIONALITY OF THE RAILROAD ELEMENTS.
4. CONTRACTOR SHALL PREPARE AND SUBMIT A RAIL MONITORING PLAN TO BE REVIEWED AND APPROVED BY UTA ENGINEERS PRIOR TO INSTALLATION FOR CONSTRUCTION UNDER THE UTA BRIDGE AT 600 WEST.
5. UTA APPLICATION FEE IS WAIVED.
6. WORK WILL BE REQUIRED TO BE PERFORMED DURING UTA NON–REVENUE HOURS (MIDNIGHT TO 4 AM).
7. UTA WILL REQUIRE/PROVIDE RWIC TO BE PRESENT DURING THE PUSH UNDER THE RAIL (MINIMUM $788 PER 8 HOUR SHIFT). THIS WILL BE COLLECTED THROUGH THE WRITTEN AGREEMENT FROM CONTRACTOR.
8. ABANDONED IN PLACE PIPE WILL BE REQUIRED TO BE FLOW FILLED AND CAPPED.
9. SEPARATE RAILROAD PROTECTIVE LIABILITY POLICY IS REQUIRED IN ADDITION TO THE GENERAL LIABILITY INSURANCE REQUIREMENTS.
10. ALL WORKERS, CONTRACTORS, SUBCONTRACTORS AND INVITEES TO THE PROJECT ARE REQUIRED TO OBTAIN UTA ROADWAY WORKER SAFETY CERTIFICATION. INFORMATION RELATED TO THE TRAINING IS AVAILABLE ON THE UTA WEBSITE HTTPS://www.rideuta.com/doing–business/property–management

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\G–005 GENERAL NOTES.DWG
FILE DATE: 3.6.2024 11:46:27 (MAJ)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TUCKETT
STATE OF UTAH
REGISTERED PROFESSIONAL ENGINEER

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3					
DRAFTED	MAJ	2					
CHECKED	GST	1					
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.	


SCALE: NONE

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
GENERAL
GENERAL NOTES

SHEET G–005
126.42.300

7/04



SURVEY CONTROL

THE PROJECT CONTROL WAS COMPILED USING G.P.S. (RTK) REAL TIME KINEMATIC METHODS AVERAGED AT A MINIMUM OF 180 TIMES. MEASUREMENTS ARE STATE PLANE COORDINATES (GRID).

THE BASE PROJECT COORDINATE, LATITUDE, LONGITUDE AND STATE PLANE COORDINATE (UT–CENTRAL, NAD 83 W/GEOID 2012B) WAS ESTABLISHED ON THE SLCO CONTROL POINT MONUMENT 1S1W243A AS FOLLOWS:

BASE PROJECT COORDINATE: N = 7428592.613 E = 1527603.499
STATE PLANE COORDINATE: Y = 2264239.557 X = 465614.478 (NAD83–METRIC)
GEODETIC POSITION: (N) LAT = 40°42'45.56" (W) LONG = –111°54'24.94"
BASE PROJECT ELEVATION: 4237.56 (NAVD 88)

GPS SCALE FACTORS ARE AS FOLLOWS:

SCALE FACTOR: 1.00001619
COMBINED SCALE FACTOR: N/A

PRIMARY HORIZONTAL CONTROL WAS ESTABLISHED USING THE OBSERVED SLCO CONTROL POINT MONUMENT 1S1W243A AS THE BASE POINT.

BENCHMARKS

DESCRIPTION	POINT NO.	NORTHING	EASTING	ELEVATION
SLCO MON 1S1W243A	100	7,428,592.685	1,527,603.539	4,237.56
SLCO MON 16183001	102	7,434,427.208	1,533,553.903	4,260.02
SLCO MON 1S1W1401	103	7,433,431.619	1,526,670.689	4,231.51
SLCO MON 16193001	104	7,428,557.797	1,534,341.831	4,261.54

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
REGISTERED PROFESSIONAL ENGINEER

HANSEN ALLEN & LUCE inc
ENGINEERS

DESIGNED ACS
DRAFTED TPB, MAJ
CHECKED GST
DATE APRIL 2024

NO.	DATE	REVISIONS	BY	APVD.
3				
2				
1				

SCALE AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION GENERAL
SHEET LOCATION MAP & SURVEY CONTROL

SHEET G–101
126.42.300

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\G–101 SHEET LOCATION MAP & SURVEY CONTROL.DWG
FILE DATE: 3.6.2024 11:44:50 (MAJ)

7/04

TEST HOLE NO.	DATE	SIZE	TYPE	MATERIAL	OWNER	POINT	NORTHING	EASTING	GROUND ELEVATION	DEPTH (FEET)	TOP ELEVATION	SURFACE TYPE	PAVEMENT DEPTH	SHEET	STATION	COMMENTS
201	5/21/2020	2"	Fiber Optic	Plastic	Comcast	2357	7432221.85	1527696.40	4234.76	2.20	4232.56	Asphalt	6"	PP-101	2+48	
202	5/21/2020	24" / 4"	Fiber Optic	Conrete / Plastic	Syringa	2239	7432275.50	1527718.57	4235.01	2.43	4232.58	Natural	N/A	PP-101	3+03	Apparent bottom of utilities at 4.29'. Utility bottom noted as apparent bottom unless noted as actual bottom. Additional material and/or utilities may exist below apparent bottom or actual bottom.
204	5/21/2020	2"	Telephone	Plastic	Century Link	2239	7432275.50	1527718.57	4235.01	4.90	4230.11	Natural	N/A	PP-101	3+03	Test hole called for water line but water line is not impacted. Telephone line dug at this location.
205	7/2/2020	(2) 2"	Gas	Plastic	Dominion Energy	3124	7432181.33	1527922.44	4234.06	2.52	4231.54	Natural	N/A	PP-101	5+15	Apparent bottom of utilities at 3.15'. Utility bottom noted as apparent bottom unless noted as actual bottom. Additional material and/or utilities may exist below apparent bottom or actual bottom.
208	7/2/2020	10"	Water	Metal	South Salt Lake City	3131	7432141.43	1528227.97	4233.46	4.53	4228.93	Natural	N/A	PP-102	8+24	
209	7/2/2020	2"	Gas	Plastic	Dominion Energy	3136	7432151.80	1528663.01	4233.61	3.80	4229.81	Natural	N/A	PP-103	12+61	
211	5/20/2020	10"	Water	Plastic	South Salt Lake City	2318	7432163.85	1528995.67	4233.91	3.07	4230.84	Asphalt	4"	PP-103	15+97	
214	5/19/2020	24" wide	Fiber Optic/Telephone	Concrete	CenturyLink	2322	7432161.94	1529595.28	4236.62	3.12	4233.50	Concrete	6"	PP-105	21+97	Apparent bottom of utilities at 3.59'. Utility bottom noted as apparent bottom unless noted as actual bottom. Additional material and/or utilities may exist below apparent bottom or actual bottom.
215	5/19/2020	4"	Gas	Plastic	Dominion Energy	2321	7432161.55	1529601.52	4236.73	3.75	4232.98	Asphalt	6"	PP-105	22+03	
217	5/19/2020	2"	Fiber Optic	Plastic	CenturyLink	2319	7432207.80	1529651.42	4235.74	2.67	4233.07	Asphalt	3"	NOT SHOWN	22+88	
219	5/19/2020	2"	Fiber Optic	Plastic	CenturyLink	2323	7432599.03	1529644.80	4235.17	3.45	4231.72	Asphalt	4"	PP-106	26+99	
221	5/19/2020	8" per plan	Water	Plastic	South Salt Lake City	2324	7432605.25	1529655.10	4234.48	4.18	4230.30	Asphalt	4"	PP-106	27+09	
223 & 224	5/19/2020	(2) 2"	Cable TV/Fiber Optic	Plastic	Comcast	2325	7432604.57	1529667.98	4234.27	2.55	4231.72	Asphalt	4"	PP-106	27+22	
225	5/20/2020	1"/2.5"	Water/Unknown	Metal/Plastic	South Salt Lake City/Unknown	2362	7432606.02	1529728.84	4234.86	4.21	4230.65	Asphalt	5"	PP-106	27+83	Depth to top of unknown at 3.87'.
226	5/18/2020	2"	Fiber Optic	Plastic	CenturyLink	2363	7432597.42	1529932.00	4236.10	1.93	4234.17	Natural	N/A	PP-106	29+86	
250	5/18/2020	6"	Water	Plastic	South Salt Lake City	2327	7432633.92	1531244.69	4241.69	3.66	4238.03	Asphalt	3"	PP-204	41+48	
254	5/18/2020	8"	Water	Plastic	South Salt Lake City	2328	7432225.33	1531239.52	4242.52	4.72	4237.80	Asphalt	8"	PP-204	37+39	
259	5/18/2020	8"	Water	Plastic	South Salt Lake City	2331	7431850.06	1531239.68	4242.24	3.79	4238.45	Asphalt	5"	PP-203	33+60	
263	5/14/2020	6"	Water	Plastic	South Salt Lake City	2333	7431345.24	1531236.43	4242.11	3.67	4238.44	Asphalt	5"	PP-202	28+56	
265	5/14/2020	2"	Fiber Optic	Plastic	Utopia	2332	7431304.83	1531230.43	4241.84	3.36	4238.48	Concrete	7"	PP-202	28+15	
267	5/14/2020	6"	Water	Plastic	South Salt Lake City	2334	7431036.58	1531240.49	4242.84	3.99	4238.85	Asphalt	5"	PP-201	25+47	
270	5/14/2020	6"	Water	Plastic	South Salt Lake City	2335	7430770.68	1531225.01	4242.98	4.60	4238.38	Concrete	13"	PP-201	22+81	
271A	5/20/2020	18"	Sewer	Concrete	South Salt Lake City	2364	7432115.52	1531229.42	4243.22	11.45	4231.77	Concrete	12"	PP-203	36+28	Encountered ~1' of concrete. Moved south within the test hole around the concrete. Line possibly encased with concrete.
271B	7/6/2020	18"	Sewer	Concrete	South Salt Lake City	2365	7432111.51	1531229.35	4243.26	11.49	4231.77	Concrete	12"	PP-203	36+24	Unable to locate casing at this location.
272A	5/19/2020	10"	Unknown	Metal	Unknown	2366	7432031.41	1531224.08	4243.01	3.88	4239.13	Concrete	10"	PP-203	35+44	Unable to locate casing at this location.
272B	7/6/2020	18"	Sewer	Concrete	South Salt Lake City	2367	7432059.42	1531228.85	4243.07	11.24	4231.83	Concrete	12"	PP-203	35+72	Unable to locate casing at this location.
272C	7/6/2020	10"	Unknown	Metal	Unknown	2368	7432055.52	1531227.82	4243.02	3.64	4239.38	Concrete	12"	PP-203	35+68	Located unknown line while looking for the steel casing.

CONTACT INFORMATION TABLE

AGENCY	UTILITY	CONTACT NAME	PHONE	EMAIL
BEEHIVE BROADBAND	FIBER & PHONE	BEEHIVE ENGINEERING	435-837-6141	engineering@beehive.net
CENTRACOM INTERACTIVE	CATV & PHONE	ALISA FAATZ	435-427-3331	alisa@centracom.com
CENTRAL VALLEY WATER RECLAMATION	SEWER	BRANDON HEIDELBERGER	801-973-9100	heidelbergerb@cvwrf.org
CENTURYLINK LOCAL NETWORK	FIBER & PHONE	DAVID SLOAN	801-974-8232	David.Sloan2@centurylink.com
COMCAST	CATV & FIBER	JEFF HOUSTON	435-224-2356	jeff.houston@telecon.com
DOMINION ENERGY UTAH	GAS	JOHN STAPLES	435-324-3765	john.staples@dominionenergy.com
EMERY TELCOM	PHONE	SCOTT WILLIAMS	435-748-3126	SWilliams@emerytelcom.com
FIRSTDIGITAL TELECOM	FIBER	BRANDON BALMFORTH	801-456-1095	bbalmforth@firstdigital.com
ROCKY MOUNTAIN POWER	ELECTRIC	JOEL SIMMONS	503-813-6993	GISDept@PacifiCorp.com
SALT LAKE CITY PUBLIC UTILITIES	STORM DRAIN, SEWER, WATER	NICK KRYGER	801-483-6834	nick.kryger@slcgov.com
SOUTH SALT LAKE CITY	STORM DRAIN, SEWER, WATER	ED RUFENER	801-412-3210	erufener@sslc.net
UDOT REGION II	FIBER & TRAFFIC SIGNALS	GOLDEN HOLT	801-887-3403	r2permits@utah.gov
ZAYO FIBER SOLUTIONS	FIBER	SYLVAN STEWART	801-808-7365	sylvan.stewart@zayo.com

NOTES:

1. THE LEVEL OF SUBSURFACE UTILITY ENGINEERING (SUE) FOR EXISTING UTILITIES IS DEPICTED ON THE DRAWINGS. THE LEVELS ARE IN ACCORDANCE WITH THE AMERICAN SOCIETY OF CIVIL ENGINEERING STANDARD GUIDELINE 39–02 TITLED "STANDARD GUIDELINE FOR THE COLLECTION AND DEPICTION OF SUBSURFACE DATA." THE LEVELS ARE GENERALLY DESCRIBED BELOW:
   - 1.1. SUE D – RECORDS RESEARCH/DATA COLLECTION
   - 1.2. SUE C – ABOVE GROUND SURVEY
   - 1.3. SUE B – UTILITY DESIGNATION
   - 1.4. SUE A – TEST HOLE/POT HOLING

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3			
DRAFTED	TPB, MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY APVD.

SCALE: NONE

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
GENERAL
TEST HOLE DATA

SHEET G–102

126.42.300


FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\G–102 TEST HOLE DATA DOWNTOWN.DWG
FILE DATE: 3.6.2024 11:41:41 (MAJ)

7/04




NORTH ELEVATION 1 C-106

SCALE IN FEET




EAST ELEVATION 2 C-106

SCALE IN FEET



SOUTH ELEVATION 3 C-106

SCALE IN FEET



WEST ELEVATION 4 C-106

SCALE IN FEET

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3			
DRAFTED	BKC, MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY / APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ARCHITECTURAL
PUMPHOUSE ELEVATIONS

SHEET A-101

126.42.300


FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\A-101 PUMPHOUSE ELEVATIONS.DWG
FILE DATE: 4.17.2024 15:40:06 (MAJ)

7/04




NORTH ELEVATION 1
C-202

0 4 8
SCALE IN FEET




EAST ELEVATION 2
C-202

0 4 8
SCALE IN FEET



SOUTH ELEVATION 3
C-202

0 4 8
SCALE IN FEET



WEST ELEVATION 4
C-202

0 4 8
SCALE IN FEET

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\A-201 SCREEN BUILDING ELEVATIONS.DWG
FILE DATE: 4.17.2024 15.47.99 (MAJ)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THORNE
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3				
DRAFTED	MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE
AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ARCHITECTURAL
SCREEN BUILDING ELEVATIONS

SHEET
A-201
126.42.300

7/04

DOOR SCHEDULE

TAG NO.	DOOR						FRAME					DETAILS			HARDWARE	REMARKS
	WIDTH	HEIGHT	THICK	TYPE	MATERIAL	FINISH	WIDTH	HEIGHT	THICK	FRAME MAT	FRAME FINISH	HEAD	JAMB	THRESHOLD		
101	3'–0"	7'–0"	1 3/4"	SINGLE	HM	NOTE 1	3'–4"	7'–4"	5 3/4"	HM (GROUTED)	NOTE 1	A/A–502	B/A–502	C/A–502	SEE SPEC	ACOUSTIC DOOR
102	3'–0"	7'–0"	1 3/4"	SINGLE	HM	NOTE 1	3'–4"	7'–4"	7 1/4"	STEEL (WRAP)	NOTE 1	A/A–503	B/A–503	C/A–502	SEE SPEC	ACOUSTIC DOOR, WRAP AROUND FRAME FOR STEEL STUD FRAMING
103	12'–0"	12'–8"	SEE SPEC	COILING	SEE SPEC	NOTE 2	SEE SPEC	SEE SPEC	–	STEEL	NOTE 2	E/A–502	F/A–502	G/A–502	SEE SPEC	MOTOR OPERATED OVERHEAD COILING DOOR – PUMPHOUSE
201	3'–0"	7'–0"	1 3/4"	SINGLE	HM	NOTE 1	3'–4"	7'–4"	7 1/4"	STEEL (WRAP)	NOTE 1	A/A–503	B/A–503	C/A–502	SEE SPEC	ACOUSTIC DOOR, WRAP AROUND FRAME FOR STEEL STUD FRAMING
202	12'–0"	14'–0"	SEE SPEC	COILING	SEE SPEC	NOTE 2	SEE SPEC	SEE SPEC	–	STEEL	NOTE 2	E/A–502	F/A–502	G/A–502	SEE SPEC	MOTOR OPERATED OVERHEAD COILING DOOR – MECH SCREEN BLDG

INTERIOR PAINTING SCHEDULE

LOCATION	MATERIAL	COLOR	REMARKS
PUMP STATION DRY WELL FLOOR	CONCRETE	GRAY	SYSTEM #10 – CLEAN AND PREPARE FLOOR, SIKAFLEX CONCRETE FLOOR EDGE, COAT FLOOR AND CONCRETE STEM WALL (ADD FINE AGGREGATE TO FLOOR)
PUMP STATION UPPER LEVEL FLOOR	CONCRETE	GRAY	SYSTEM #10 – CLEAN AND PREPARE FLOOR, SIKAFLEX CONCRETE FLOOR EDGE, COAT FLOOR AND CONCRETE STEM WALL
SCREEN BUILDING FLOORS	CONCRETE	GRAY	SYSTEM #10 – CLEAN AND PREPARE FLOOR, SIKAFLEX CONCRETE FLOOR EDGE, COAT FLOOR AND CONCRETE STEM WALL (ADD FINE AGGREGATE TO FLOOR)
PUMP STATION WALLS	CONCRETE	GRAY	SYSTEM #13
SCREEN BUILDING WALLS	CONCRETE	GRAY	SYSTEM #13
WET WELL AND SCREEN TROUGH	CONCRETE	STANDARD (LIGHT BLUE)	RAVEN 405 LINING SYSTEM – PREPARE SURFACE AND APPLY PER MANUFACTURER'S RECOMMENDATIONS WITH A MINIMUM THICKNESS OF 150 MILS. PROVIDE THIRD PARTY TESTING INCLUDING HIGH VOLTAGE SPARK TESTING (HOLIDAY TESTING) AND ADHESION TESTING
CEILING	PLYWOOD	WHITE	WITH BATTEN BOARDS
PIPING	METAL	GREEN	EXPOSED PIPE, VALVES & FITTINGS TO BE PAINTED

EXTERIOR COLOR SCHEDULE

MARK	MATERIAL	MANUFACTURER	FINISH	COLOR	REMARKS
EX–1	CONCRETE	GEN. CONTR.	STONE RUB	NATURAL	
EX–2	CMU	SUN–ROC	SPLIT	OWNER	8"W X 8"H X 16"L COAT OUTSIDE WALLS W/ GRAFFITI COAT
EX–3	CMU	SUN–ROC	SPLIT	OWNER	8"W X 8"H X 16"L COAT OUTSIDE WALLS W/ GRAFFITI COAT
EX–4	MORTAR	SPEC–MIX	SMOOTH	OWNER	CONCAVE JOINTS
EX–5	METAL ROOF	FABRAL	GALVALUME	OWNER	2" STANDING SEAM
EX–6	FACIA	FABRAL	GALVALUME	OWNER	
EX–7	SOFFIT	FABRAL	GALVALUME	OWNER	VENTED
EX–8	GUTTER/DOWN SPOUT	FABRAL	GALVALUME	OWNER	4" DEEP, 4" WIDE, DOWN SPOUT 6" X 6" GUTTER
EX–9	DOORS	–	SMOOTH	OWNER	FACTORY PRIMED
EX–10	STEEL DOORFRAME	GENERAL CONTRACTOR	MATTE EPOXY	OWNER	
EX–11	METAL SIDING	FABRAL	GALVALUME	OWNER	2" REVEAL; 2" PENCIL RIBS

NOTES:

1. SEE SPECIFICATIONS SECTION 09 90 00 PAINTING AND FINISHES FOR TYPICAL FINISH.
2. SEE SPECIFICATIONS SECTION 08 33 23 OVERHEAD COILING DOORS FOR FACTORY FINISH.
3. ALL HOLLOW METAL DOORS AND FRAMES SHALL BE GALVANIZED.
4. OWNER TO SELECT ARCHITERCTURAL COLORS.

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
REGISTERED PROFESSIONAL ENGINEER

HANSEN ALLEN & LUCE, Inc. ENGINEERS

DESIGNED ACS
DRAFTED MAJ
CHECKED GST
DATE APRIL 2024

NO.	DATE	REVISIONS	BY	APVD.
3				
2				
1				

SCALE NONE

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ARCHITECTURAL
ARCHITECTURAL SCHEDULES

SHEET A–501


126.42.300

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – FILE DATE: 4/17/2024 16:15:59 (MAJ)


7/04




DOOR HEAD NTS | A | A–501



DOOR JAMB NTS | B | A–501



DOOR SILL NTS | C | A–501 | C | C–109




DIMENSIONS G, M AND D*
F265 SLAT

DIMENSIONS	Max. Door Opening Widths		
	9'0"	15'0"	20'0"
G	3"	3 1/2"	4"
M	5 1/4"	5 3/4"	6 3/4"
D	4 1/2"	5"	5"


NOTE:
BOLT COILING DOOR TO STEEL CHANNEL. WELDING NOT PERMITTED. BOLT SIZE PER DOOR MANUFACTURER.

COILING DOOR GUIDE NTS | D | — | D | C–109



NOTE:
BOLT COILING DOOR TO STEEL CHANNEL. WELDING NOT PERMITTED. BOLT SIZE PER DOOR MANUFACTURER.


COILING DOOR HEAD NTS | E | A–501 | E | C–106 | E | C–109 | E | S–105 | E | S–205



NOTE:

BOLT COILING DOOR TO STEEL CHANNEL. WELDING NOT PERMITTED. BOLT SIZE PER DOOR MANUFACTURER.

COILING DOOR – JAMB NTS | F | — | F | A–501 | F | S–105 | F | S–205



NOTE:
HOT DIP GALVANIZED THRESHOLD ASSEMBLY AFTER FABRICATION.

COILING DOOR – THRESHOLD NTS | G | — | G | A–501 | G | C–109 | G | S–204

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\A–502 DOOR DETAILS 1.DWG
FILE DATE: 4.17.2024 16:17:06 (MAJ)

HANSEN ALLEN & LUCE inc ENGINEERS

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

DESIGNED	ACS
DRAFTED	MAJ
CHECKED	GST
DATE	APRIL 2024

NO.	DATE	REVISIONS	BY	APVD.
3				
2				
1				


SCALE
NOT TO SCALE

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ARCHITECTURAL
DOOR DETAILS 1

SHEET
A–502
126.42.300


7/04



DETAIL NOTES:

1. DOOR OPENING SIZE TO BE ADJUSTED AS NECESSARY TO MEET FRAME MANUFACTURER'S REQUIREMENTS.

WRAP DOOR HEAD W/ STEEL FRAMING — A / A-501
NTS



DETAIL NOTES:

1. DOOR OPENING SIZE TO BE ADJUSTED AS NECESSARY TO MEET FRAME MANUFACTURER'S REQUIREMENTS.

WRAP DOOR JAMB W/ STEEL FRAMING — B / A-501
NTS

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\A-503 DOOR DETAILS II.DWG
FILE DATE: 4.17.2024 16:18:13 (MAJ)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3			
DRAFTED	MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY / APVD.


SCALE: NOT TO SCALE

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ARCHITECTURAL
DOOR DETAILS II

SHEET: A-503
126.42.300

7/04



KEY NOTES:

- (A) REMOVE EXISTING 2' WIDE CONCRETE VALLEY GUTTER.
- (B) REMOVE EXISTING CONCRETE GENERATOR PAD AND CURB WALL.
- (C) REMOVE EXISTING STORAGE SHEDS. CITY PERSONNEL TO REMOVE EQUIPMENT PRIOR TO DEMOLITION. COORDINATE REMOVAL OF EQUIPMENT WITH CITY PERSONNEL.
- (D) REMOVE EXISTING DRAIN BOX AND PIPE.
- (E) REMOVE EXISTING 12" SD PIPING.
- (F) REMOVE EXISTING CHAIN LINK FENCE.
- (G) REMOVE EXISTING CURB. SAWCUT AS REQUIRED FOR A CLEAN EDGE. TACK COAT EDGE.
- (H) REMOVE EXISTING 18" CPP NORTH OF NEW INLET BOX. BACKFILL WITH STRUCTURAL FILL.
- (J) INSTALL 4' WIDE SIDEWALK PER SOSL STANDARD DETAILS (SEE SHEET C-702).
- (K) INSTALL ASPHALT PAVEMENT (4" ASPHALT OVER 8" UBC, MIN). SEE SHEETS C-103 & C-104 FOR EXTENTS.
- (L) SAWCUT ASPHALT. TACK COAT EDGE.
- (M) INSTALL GENERATOR AND PAD (SEE DETAIL E/C-501).
- (N) INSTALL SD MANHOLE OR INLET, TYP (SEE SHEETS PP-301 TO PP-303).
- (P) PROTECT IN PLACE EXISTING CHAIN LINK FENCE.
- (Q) RELOCATE OR REPLACE WATER METER (SEE SHEET C-102 FOR FURTHER DETAILS).
- (R) PROVIDE 18" MIN WIDE x 6" THICK MIN CONCRETE APRON AROUND BOX. FORM TO MATCH WATERWAY AND DESIGN GRADE OF ASPHALT. DRAIN TO INLET BOX. PROVIDE #4 BAR @ 12" OC EW, MIN
- (S) REMOVE EXISTING ROLLING CHAIN LINK GATE.
- (T) REMOVE EXISTING PAVEMENT AND PLACE 3" NEW ASPHALT. PROOF ROLL SUBGRADE AND REPLACE SOFT SPOTS WITH 8" MIN UBC (SEE SHEET C-103 FOR EXTENTS).
- (U) SLIDING GATE OPENER WITH BATTERY BACKUP COMPATIBLE WITH CANTILEVER GATE.
- (V) POLE MOUNTED KEYPAD COMPATIBLE WITH CANTILEVER GATE OPENER.
- (W) INSTALL 6" CONCRETE SLAB PER DETAIL D/C-501.
- (X) INSTALL TRANSFORMER AND TRANSFORMER VAULT. SEE ELECTRICAL PLANS.
- (Y) INSTALL FREE-STANDING ELECTRICAL PANEL WITH METER, DISCONNECT & CT PANEL. SEE ELECTRICAL PLANS.

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-101 SITE & DEMO PLAN.DWG
FILE DATE: 4.16.2024, 12:56:28 (MAJ)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

DESIGNED	ACS	3				
DRAFTED	TPB, MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

HANSEN ALLEN & LUCE inc ENGINEERS

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
SITE AND DEMOLITION PLAN

SHEET C-101

126.42.300

7/04



KEY NOTES:

(A) FIELD VERIFY LOCATION AND ELEVATION PRIOR TO CONSTRUCTION.

(B) PROVIDE FITTINGS AS NECESSARY TO FACILITATE INSTALLATION.

(C) ELECTRICAL CONDUIT(S), TYPICAL. LOCATION IS APPROXIMATE. SEE ELECTRICAL DRAWINGS FOR QUANTITY, SIZE AND CONNECTION POINTS. CONTRACTOR IS RESPONSIBLE FOR FINAL LAYOUT OF CONDUIT AS REQUIRED TO MEET REQUIREMENTS OF ELECTRICAL DRAWINGS.

GENERAL SHEET NOTES:

1. ALL FITTINGS AND PIPE JOINTS TO BE MECHANICALLY RESTRAINED.
2. ALL DIP PIPING AND FITTINGS SHALL BE CL 53 AND PROTECTO 401 CERAMIC EPOXY LINED BY U.S. PIPE FABRICATION OR APPROVED EQUAL.

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH
PROJECT ENGINEER

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3			
DRAFTED	TPB, MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
YARD PIPING PLAN

SHEET C-102

126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-102 YARD PIPING PLAN.DWG
FILE DATE: 4.16.2024, 13:02:57 (MAJ)

7/04



POINT ID	NORTHING	EASTING	ELEVATION	DESCRIPTION
A	7,432,215.06	1,527,565.03	4236.53	EOP
B	7,432,193.82	1,527,564.45	4236.68	TBC
C	7,432,193.83	1,527,565.12	4235.92	EOP
D	7,432,176.75	1,527,564.47	4236.68	TBC
E	7,432,176.75	1,527,565.15	4235.51	FG
F	7,432,179.42	1,527,565.15	4235.51	FG
H	7,432,109.91	1,527,564.57	4236.68	TBC
J	7,432,109.91	1,527,565.25	4236.50	EOP
K	7,432,109.91	1,527,565.97	4236.51	EOP
L	7,432,060.08	1,527,566.00	4236.50	EOP
M	7,432,060.08	1,527,593.13	4236.99	EOP
N	7,432,060.08	1,527,607.28	4237.34	EOP
P	7,432,086.19	1,527,615.92	4237.08	EOP
Q	7,432,106.26	1,527,621.76	4237.04	EOP
R	7,432,105.56	1,527,624.54	4237.03	EOP
S	7,432,096.18	1,527,651.27	4237.33	EOP
T	7,432,099.00	1,527,671.18	4236.65	EOP
U	7,432,118.54	1,527,670.33	4236.71	MATCH EX
V	7,432,130.24	1,527,653.70	4236.64	EOP
W	7,432,134.56	1,527,653.28	4236.69	EOP
X	7,432,111.77	1,527,698.31	4236.42	MATCH EX
Y	7,432,147.30	1,527,687.84	4236.49	EOP
Z	7,432,134.57	1,527,691.60	4236.62	EOP
AA	7,432,182.18	1,527,677.56	4236.61	EOP
AB	7,432,186.20	1,527,667.86	4236.63	EOP
AC	7,432,189.29	1,527,660.59	4236.60	EOP
AD	7,432,196.09	1,527,644.62	4236.17	EOP
AE	7,432,204.03	1,527,618.04	4236.11	EOP
AF	7,432,208.20	1,527,599.37	4235.79	EOP
AG	7,432,211.48	1,527,583.43	4235.76	EOP
AH	7,432,157.40	1,527,565.18	4235.61	EOP
AJ	7,432,203.42	1,527,583.37	4235.84	EOP/TOC
AK	7,432,203.42	1,527,599.32	4235.84	EOP/TOC
AL	7,432,195.42	1,527,599.32	4236.00	TOC
AM	7,432,195.42	1,527,583.37	4236.00	EOP/TOC
AN	7,432,179.42	1,527,583.37	4235.97	EOP/TOC
AP	7,432,179.42	1,527,574.50	4235.79	EOP/TOC
AQ	7,432,165.91	1,527,574.50	4235.79	EOP/TOC
AR	7,432,165.91	1,527,578.50	4235.87	TOC

POINT ID	NORTHING	EASTING	ELEVATION	DESCRIPTION
AS	7,432,157.41	1,527,574.50	4235.79	EOP/TOC
AT	7,432,157.41	1,527,578.50	4235.87	EOP/TOC
AU	7,432,119.91	1,527,578.50	4236.94	EOP/TOC
AV	7,432,115.91	1,527,578.50	4236.86	EOP/TOC
AW	7,432,115.91	1,527,601.83	4236.86	EOP/TOC
AX	7,432,119.91	1,527,601.83	4236.94	TOC
AY	7,432,109.91	1,527,578.50	4236.69	FG
AZ	7,432,109.91	1,527,601.81	4236.83	FG
BA	7,432,129.58	1,527,601.83	4236.94	EOP
BB	7,432,149.19	1,527,610.91	4236.70	EOP
BC	7,432,165.58	1,527,610.91	4235.92	EOP
BD	7,432,165.58	1,527,606.00	4236.42	TOC
BE	7,432,165.58	1,527,606.08	4236.02	EOP
BF	7,432,175.42	1,527,606.08	4236.02	EOP/TOC
BG	7,432,175.42	1,527,606.00	4236.42	TOC
BH	7,432,179.42	1,527,606.08	4236.10	TOC
BJ	7,432,175.42	1,527,618.04	4235.90	EOP/TOC
BK	7,432,179.42	1,527,618.04	4236.00	EOP/TOC
BL	7,432,175.72	1,527,634.27	4236.12	EOP
BM	7,432,175.73	1,527,653.27	4236.50	EOP
BN	7,432,164.23	1,527,653.28	4236.69	EOP
BP	7,432,164.24	1,527,634.27	4236.13	EOP
BQ	7,432,123.68	1,527,615.91	4236.41	EOP/TOC
BR	7,432,123.68	1,527,621.91	4236.42	EOP/TOC
BS	7,432,122.37	1,527,621.91	4236.39	EOP/TOC
BT	7,432,120.32	1,527,621.91	4236.36	FL
BU	7,432,118.26	1,527,621.91	4236.44	EOP/TOC
BV	7,432,117.68	1,527,621.91	4236.47	EOP/TOC
BW	7,432,117.68	1,527,615.91	4236.44	EOP/TOC
BX	7,432,110.89	1,527,670.19	4236.60	EOP/TOC
BY	7,432,108.94	1,527,669.72	4236.52	FL
BZ	7,432,106.99	1,527,669.26	4236.60	EOP/TOC
CA	7,432,149.19	1,527,627.24	4236.70	EOP
CB	7,432,164.21	1,527,627.30	4235.99	EOP
CC	7,432,129.58	1,527,610.91	4236.58	EOP
CD	7,432,130.21	1,527,627.16	4236.64	MATCH EX
CE	7,432,144.75	1,527,670.72	4236.32	FG
CF	7,432,161.51	1,527,670.72	4236.15	FG
CG	7,432,215.39	1,527,564.36	4236.68	TBC
CH	7,432,179.42	1,527,606.00	4236.42	TOC

LEGEND:

REMOVE AND REPLACE ASPHALT (4" ASPHALT OVER 8" UBC MIN)

PLACE NEW ASPHALT (4" ASPHALT OVER 8" UBC MIN)

KEY NOTES:

(A) GRADE ASPHALT TO MATCH BOX RIM ELEVATION (SEE SHEETS PP-201 & PP-202).

(B) SET MANHOLE LID TO MATCH FINISH ELEVATION OF ASPHALT.

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-103 GRADING PLAN 1.DWG
FILE DATE: 4.16.2024 13:10:13 (MAJ)

7/04

HANSEN ALLEN & LUCE Inc. ENGINEERS

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TUCKER
REGISTERED ENGINEER

DESIGNED	ACS	3			
DRAFTED	MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY / APVD.


SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
GRADING PLAN 1

SHEET C-103

126.42.300



POINT ID	NORTHING	EASTING	ELEVATION	DESCRIPTION
A	7,432,215.06	1,527,565.03	4236.53	EOP
B	7,432,239.90	1,527,570.30	4235.47	EOP
C	7,432,267.08	1,527,570.30	4235.21	EOP
D	7,432,267.08	1,527,590.51	4234.85	EOP
E	7,432,267.08	1,527,610.72	4234.55	EOP
F	7,432,264.24	1,527,607.89	4234.55	EOP
G	7,432,251.07	1,527,632.69	4234.72	EOP
H	7,432,235.06	1,527,654.66	4234.90	EOP
J	7,432,217.19	1,527,682.05	4235.11	EOP
K	7,432,217.19	1,527,684.60	4235.06	EOP
L	7,432,198.05	1,527,690.42	4235.20	EOP
M	7,432,194.15	1,527,677.56	4235.81	EOP/GB
N	7,432,208.20	1,527,618.04	4235.79	FG/GB
P	7,432,218.64	1,527,689.38	4234.64	TBC
Q	7,432,199.50	1,527,695.18	4234.78	TBC
AA	7,432,182.18	1,527,677.56	4236.61	EOP
AB	7,432,186.20	1,527,667.86	4236.63	EOP
AC	7,432,189.29	1,527,660.59	4236.60	EOP
AD	7,432,196.09	1,527,644.62	4236.17	EOP
AE	7,432,204.03	1,527,618.04	4236.11	EOP
AF	7,432,208.20	1,527,599.37	4235.79	EOP/GB
AG	7,432,211.48	1,527,583.43	4235.76	EOP

LEGEND:

PLACE NEW ASPHALT
(4" ASPHALT OVER 8" UBC MIN)

KEY NOTES:

(A) GRADE ASPHALT TO MATCH BOX RIM ELEVATION (SEE SHEET PP-203).

(B) SET MANHOLE LID TO MATCH FINISH ELEVATION OF ASPHALT.

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-104 GRADING PLAN II.DWG
FILE DATE: 4.17.2024 | 16:56:37 (MAJ)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE, Inc. ENGINEERS

DESIGNED	ACS	3				
DRAFTED	MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
GRADING PLAN II

SHEET C-104

126.42.300

7/04



PLAN

LEGEND:

- ▲ – PIPE SUPPORT (13X) ANVIL TYPE (TYP) SEE DETAIL F/C-501
- △ – PIPE SUPPORT (16X) FLANGE TYPE (TYP) SEE DETAIL F/C-501
- ◉ – PRESSURE GUAGE AND PRESSURE SWITCH (TYP) SEE DETAIL 2/E-506

GENERAL SHEET NOTES:

1. SEE SHEET C-111 FOR PUMPHOUSE PIPE, FITTING AND EQUIPMENT SCHEDULE.
2. ALL DIP PIPING AND FITTINGS SHALL BE CL 53 AND PROTECTO 401 CERAMIC EPOXY LINED BY U.S. PIPE FABRICATION OR APPROVED EQUAL.
3. INTERIOR SURFACE OF WET WELL, INCLUDING PIPING SHALL BE COATED WITH RAVEN 405 LINING SYSTEM (NO SUBSTITUTION PERMITTED) WITH A MINIMUM THICKNESS OF 150 MILS. COATING SHALL BE FIELD APPLIED PRIOR TO THE INTRODUCTION OF SANITARY SEWER FLOWS. COATING SHALL BE AS PER MANUFACTURER RECOMMENDATIONS INCLUDING SURFACE PREPARATION. CONTRACTOR SHALL PROVIDE THIRD PARTY TESTING OF INSTALLED COATING AS PER MANUFACTURER RECOMMENDATIONS INCLUDING HIGH VOLTAGE SPARK TESTING (HOLIDAY TESTING) AND ADHESION TESTING.

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TWELVES
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3				
DRAFTED	BKC, MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
PUMPHOUSE DRY & WET WELL PLAN

SHEET C-105

126.42.300

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\C-105 PUMPHOUSE DRY & WET WELL PLAN.DWG
FILE DATE: 4.12.2024 11:33:57 (MAJ)
7/04



PLAN

GENERAL SHEET NOTES:
1. SEE SHEET S-105 FOR DIMENSIONS OF HOUSEKEEPING PADS.

FILE NAME:PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-106 PUMPHOUSE BLDG FLOOR PLAN.DWG
FILE DATE: 4.17.2024 17:16:28 (MAJ)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. [illegible]
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3			
DRAFTED	BKC, MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY APVD.


SCALE: AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
PUMPHOUSE BUILDING FLOOR PLAN

SHEET C-106
126.42.300


7/04




SECTION 2 C-105
0 2 4
SCALE IN FEET



SECTION 4 C-105
0 2 4
SCALE IN FEET



SECTION 3 C-105
0 2 4
SCALE IN FEET



SECTION 5 C-105
0 2 4
SCALE IN FEET

GENERAL SHEET NOTES:
1. SEE SHEET C-111 FOR PUMPHOUSE PIPE, FITTING AND EQUIPMENT SCHEDULE.
2. SEE SHEET C-105 FOR THE LOCATION AND QUANTITY OF ALL PIPE SUPPORTS IN THE DRY WELL.

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THURGOOD
STATE OF UTAH

HANSEN ALLEN & LUCE Inc ENGINEERS

DESIGNED	ACS	3				
DRAFTED	BKC, MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.


SCALE AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
DRY WELL SECTIONS


SHEET C-107
126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-107 DRY WELL SECTIONS.DWG
FILE DATE: 4/17/2024 17:18:36 (MAJ)
7/04




DETAIL NOTE:
1. SEE SHEET C-111 FOR EQUIPMENT, PIPE AND FITTING SCHEDULE.
2. PROVIDE MAXIMUM FEASIBLE CLEARANCE WHILE NOT RAISING THE TOP OF THE MOTOR HOUSING ABOVE THE NORMAL LOW WATER LEVEL.

SECTION 6
SCALE IN FEET 0 2 4
C-105



SECTION 7
NTS
—



SECTION 8
NTS
—

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED ACS	3					
DRAFTED BKC, MAJ	2					
CHECKED GST	1					
DATE APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.	

SCALE AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
WET WELL SECTIONS

SHEET C-108
126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-108 WET WELL SECTIONS.DWG
FILE DATE: 3.15.2024 14:26:13 (MAJ)

7/04



SECTION 1 C-105 | 1 C-106

0 1 2
SCALE IN FEET

FILE NAME:PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-109 PUMPHOUSE BLDG SECTIONS 1.DWG
FILE DATE: 3.5.2024 14:28:11 (MAJ)

7/04

HANSEN ALLEN & LUCE inc ENGINEERS

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. [illegible]
STATE OF UTAH

DESIGNED	ACS	3				
DRAFTED	BKC, MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.


SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
PUMPHOUSE BUILDING SECTIONS 1

SHEET C-109

126.42.300



SECTION 7
C-106

0 1 2
SCALE IN FEET

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-110 PUMPHOUSE BLDG SECTIONS II.DWG
FILE DATE: 3.5.2024 14:29:15 (MAJ)

7/04

HANSEN ALLEN & LUCE inc ENGINEERS

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
REGISTERED ENGINEER

DESIGNED	ACS	3				
DRAFTED	BKC, MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE
AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
PUMPHOUSE BUILDING SECTIONS II

SHEET
C-110
126.42.300

PIPE, FITTING & EQUIPMENT SCHEDULE

NO	DESCRIPTION	SIZE	JOINT	NOTE
1	FLYGT NT 3171 MT 3–436	10" SUCTION, 6" DISCHARGE	FLG	ROTATE DISCHARGE 45 DEG FROM SUCTION; NO SUBSTITUTION PERMITTED
2	FLYGT NT 3315 MT 3–635	12" SUCTION, 10" DISCHARGE	FLG	ROTATE DISCHARGE 45 DEG FROM SUCTION; NO SUBSTITUTION PERMITTED
3	SUCTION BELL	14"X21"	FLG	AMERICAN DUCTILE IRON SPECIALS FLARE CASTINGS
4	SUCTION BELL	12"X19"	FLG	AMERICAN DUCTILE IRON SPECIALS FLARE CASTINGS
5	SUCTION BELL	10"X16"	FLG	AMERICAN DUCTILE IRON SPECIALS FLARE CASTINGS
6	90 DEG BEND	14"	FLG	3" THD TAP FOR AIR VENT WHERE SHOWN ON PLANS
7	90 DEG BEND	12"	FLG	
8	90 DEG BEND	10"	FLG	
9	90 DEG BEND	6"	FLG	
10	45 DEG BEND	10"	FLG	
11	45 DEG BEND	6"	FLG	
12	REDUCER	12"X14"	FLG	ECCENTRIC
13	REDUCER	10"X12"	FLG	ECCENTRIC
14	REDUCER	8"X10"	FLG	CONCENTRIC
15	REDUCER	8"X6"	FLG	CONCENTRIC
16	NOT USED			
17	TEE	12"X10"	FLG	
18	TEE	10"	FLG	
19	TEE	8"X6"	FLG	
20	DIP SPOOL (CL 53)	14"	FLG	FIELD VERIFY LENGTH PRIOR TO FABRICATION
21	DIP SPOOL (CL 53)	12"	FLG	FIELD VERIFY LENGTH PRIOR TO FABRICATION
22	DIP SPOOL (CL 53)	10"	FLG	FIELD VERIFY LENGTH PRIOR TO FABRICATION
23	DIP SPOOL (CL 53)	8"	FLG	FIELD VERIFY LENGTH PRIOR TO FABRICATION
24	DIP SPOOL (CL 53)	6"	FLG	FIELD VERIFY LENGTH PRIOR TO FABRICATION
25	DIP THRUST COLLAR (CL 53)	12"	FLG	FIELD VERIFY LENGTH PRIOR TO FABRICATION
26	DIP THRUST COLLAR (CL 53)	10"	FLG	FIELD VERIFY LENGTH PRIOR TO FABRICATION
27	PLUG VALVE	14"	FLG	
28	PLUG VALVE	12"	FLG	
29	PLUG VALVE	10"	FLG	
30	PLUG VALVE	6"	FLG	
31	NOT USED			
32	CHECK VALVE	10"	FLG	
33	CHECK VALVE	6"	FLG	
34	DISMANTLING JOINT	14"	FLG	ROMAC DJ400 W/ SS TIE RODS
35	DISMANTLING JOINT	12"	FLG	ROMAC DJ400 W/ SS TIE RODS
36	DISMANTLING JOINT	10"	FLG	ROMAC DJ400 W/ SS TIE RODS
37	NOT USED			
38	DISMANTLING JOINT	6"	FLG	ROMAC DJ400 W/ SS TIE RODS
39	FLOW METER	14"	FLG	SIEMANS SITRANS MAG 5100W; NO SUBSTITUTION PERMITTED
40	AIR/VAC VALVE	NA	THD	APCO SERIES 447 SCAV (3")
41	DIP THRUST COLLAR (CL 53)	14"	FLG X PE	FIELD VERIFY LENGTH PRIOR TO FABRICATION
42	NOT USED			
43	TEE W/ 14" SIDE OUTLET	14" X 10" X 14"	FLG	
44	NOT USED			
45	CHECK VALVE	3"	FLG	VALMATIC SWING–FLEX
46	LANDIA AERIGATOR DG–I 105	–	–	ROTATE DISCHARGE ±15° FROM CENTERLINE OF WET WELL
47	AERIGATOR GUIDE	–	–	GUIDE TO BE SUPPLIED BY MANUFACTURER OF AERIGATOR
48	DIP THRUST COLLAR (CL 53)	14"	FLG	FIELD VERIFY LENGTH PRIOR TO FABRICATION

GENERAL SHEET NOTES:

1. CONTRACTOR SHALL PROVIDE (1) "FLYGT BASIC REPAIR KIT" FOR THE FLYGT NT 3171 MT 3–436 PUMPS AND (1) "FLYGT BASIC REPAIR KIT " FOR THE FLYGT NT 3315 MT 3–635 PUMPS (PART NO 6571701).

2. CONTRACTOR SHALL PROVIDE (1) COMPLETE SPARE PARTS KIT FOR THE LANDIA AERIGATOR DG–I 105 UNITS. EACH SPARE PARTS KIT SHALL INCLUDE ONE IMPELLER, ONE COMPLETE CHOPPING SYSTEM, INCLUDING ALL ROTATING AND STATIONARY MEMBERS, ONE OUTER MECHANICAL SEAL, ONE SET OF O–RINGS, AND A SET OF SEALING WASHERS.

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\C–111 PUMPHOUSE PIPE, FITTING_EQUIPMENT SCHEDULE.DWG
FILE DATE: 3.5.2024 14:30:22 (MAJ)

HANSEN ALLEN & LUCE inc ENGINEERS

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. T. CIVIL
STATE OF UTAH

DESIGNED	ACS	3			
DRAFTED	BKC, MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY APVD.

SCALE: NONE


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
PUMPHOUSE PIPE, FITTING & EQUIPMENT SCHEDULE

SHEET C–111

126.42.300

7/04



GENERAL SHEET NOTES:

1. CONTRACTOR SHALL PROVIDE AND INSTALL JWC CMF3618-2.ME (CHANNEL MONSTER FLEX). AFTER START UP, TESTING AND ACCEPTANCE, CONTRACTOR SHALL REMOVE THE EQUIPMENT FROM THE CHANNEL AND PROVIDE TO OWNER FOR STORAGE.
2. CONTRACTOR SHALL PROVIDE (3) ADDITIONAL CUTTERS AND SPACERS FOR THE JWC CMF3618-2.ME (CHANNEL MONSTER FLEX).

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-201 SCREEN BUILDING TRENCH PLAN.DWG
FILE DATE: 3.5.2024 14:52:40 (MAJ)

7/04

HANSEN ALLEN & LUCE INC ENGINEERS

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

DESIGNED	ACS
DRAFTED	MAJ
CHECKED	GST
DATE	APRIL 2024

NO.	DATE	REVISIONS	BY	APVD.
3				
2				
1				

SCALE
AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
SCREEN BUILDING TRENCH PLAN

SHEET
C-201
126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-202 SCREEN BUILDING FLOOR PLAN.DWG
FILE DATE: 4.17.2024 17:38:14 (MAJ)

N

0 2 4
SCALE IN FEET

8'-0"
6" SLAB ON GRADE (SEE SHEET C-103 FOR ELEVATIONS) D C-501
16'-0"
3"
1 A-201
BOLLARD C C-501
4'-9"
1'-6"
36" INTERIOR DOOR (SEE SHEET A-501 FOR DOOR SCHEDULE) D-5
CONCRETE STAIRS B S-504
3'-4" TRENCH AREA ACCESS
DOWN TO TRENCH AREA
8'-0"
14'H X 12'W INSULATED COILING DOOR
1'-9"
(2) BOLLARD C C-501
1'-9"
STAIR RAIL TERMINATION E S-506
GUARDRAIL C S-506
2'-0"
1'-6"
202
7'-4"
2'-2"
2'-0"
3'-8"
3"
GANTRY CRANE BEAM
REMOVEABLE BOLLARD C S-511 (TYP OF 3)
3'-8"
3'-8"
3'-8"
7'-2"
2 A-201
4 A-201
GRATING, TYP (SEE SHEET S-203)
11'-8"
LOUVER (SEE SHEET H-101)
DUMPSTER (BY OTHERS)
DISCHARGE CHUTE AS SUPPLIED BY SCREEN MANUFACTURER
JWC CRM2 (CHAIN & RAKE MONSTER) SCREEN AND JWC MWP3018 WASH PRESS
1 C-203
UPPER HOSE BIBB D P-501
CONCRETE PAD FOR ODOR CONTROL UNITS (SEE SHEET C-103 FOR ELEVATIONS) A C-402
1'-11"
11'-0"
1'-6" (TYP)
6'-6"
6'-0"
2'-8"
1'-6"
11"
7"
201
DUMPSTER BARRIER (TYP) C S-507
36" STEEL PERSONNEL DOOR
3'-8"
4'-0"
12'-1"
3 A-201
2 C-204
4' CONCRETE SIDEWALK PER SOSL STANDARD DETAILS (SEE SHEET C-702) (SEE SHEET C-103 FOR ELEVATIONS)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TWEEDY
STATE OF UTAH

HANSEN ALLEN & LUCE INC ENGINEERS

DESIGNED	ACS		
DRAFTED	MAJ		
CHECKED	GST		
DATE	APRIL 2024		

NO.	DATE	REVISIONS	BY	APVD.
3				
2				
1				


SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
SCREEN BUILDING FLOOR PLAN

SHEET C-202
126.42.300

7/04



SECTION 1 C-201 / 1 C-202

0 2 4
SCALE IN FEET

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-203 SCREEN BUILDING SECTIONS 1.DWG
FILE DATE: 4.15.2024 16:08:58 (MAJ)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TOBIAS
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED ACS	3					
DRAFTED MAJ	2					
CHECKED GST	1					
DATE APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.	


SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
SCREEN BUILDING SECTIONS 1

SHEET C-203
126.42.300

7/04



SECTION 2 C-201 | 2 C-202

0 2 4
SCALE IN FEET

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-204 SCREEN BUILDING SECTIONS II.DWG
FILE DATE: 3.5.2024 15:15:22 (MAJ)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TUCKETT
STATE OF UTAH

HANSEN ALLEN & LUCE INC ENGINEERS

DESIGNED	ACS	3			
DRAFTED	MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY / APVD.


SCALE: AS SHOWN


SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
SCREEN BUILDING SECTIONS II


SHEET C-204
126.42.300

7/04









GENERAL SHEET NOTES:

1. ALL DIP PIPING AND FITTINGS SHALL BE CL 53 AND PROTECTO 401 CERAMIC EPOXY LINED BY U.S. PIPE FABRICATION OR APPROVED EQUAL.
2. ALL FITTINGS AND APPURTENANCES SHALL BE MECHANICALLY RESTRAINED.

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. [illegible]
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3			
DRAFTED	BKC, MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
INTERCONNECT VAULT PLAN & SECTIONS

SHEET C-401


126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-401 INTERCONNECT VAULT PLAN & SECTIONS.DWG
FILE DATE: 3.5.2024 - 15:46:56 (MAJ)


7/04




PLAN | A C-101 | A C-106 | A C-202



SECTION 3 — SCALE IN FEET



SECTION 1 — SCALE IN FEET



GENERAL SHEET NOTES:
1. CONTRACTOR TO VERIFY ALL DIMENSIONS AND FITTING SPACING REQUIREMENTS PRIOR TO INSTALLING SCH 80 PVC PIPE FOR DUCTING.

SECTION 2 — SCALE IN FEET

LICENSED PROFESSIONAL ENGINEER 4/19/24 No. 5052482 GREGORY S. THOMAS STATE OF UTAH

DESIGNED	ACS	3					
DRAFTED	MAJ	2					
CHECKED	GST	1					
DATE	APRIL 2024	NO.	DATE	REVISIONS		BY	APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
ODOR CONTROL UNITS PLAN & SECTIONS

SHEET C-402

126.42.300


FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-402 ODOR CONTROL UNITS PLAN & SECTIONS.DWG
FILE DATE: 3.20.2024 08:58:36 (MAJ)

7/04



DETAIL NOTES:
1. ALL DIP PIPING AND FITTINGS SHALL BE CL 53 AND PROTECTO 401 CERAMIC EPOXY LINED BY U.S. PIPE FABRICATION OR APPROVED EQUAL.
2. ALL FITTINGS AND APPURTENANCES SHALL BE MECHANICALLY RESTRAINED.

EXISTING WET WELL CONNECTION — A / C-102



DETAIL NOTES:
1. ALL DIP PIPING AND FITTINGS SHALL BE CL 53 AND PROTECTO 401 CERAMIC EPOXY LINED BY U.S. PIPE FABRICATION OR APPROVED EQUAL.
2. ALL FITTINGS AND APPURTENANCES SHALL BE MECHANICALLY RESTRAINED.

SECTION — 1 / —

0 2 4
SCALE IN FEET

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-403 EXIST WET WELL PLAN & SECTION.DWG
FILE DATE: 3.5.2024 17:54:23 (MAJ)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE, INC. ENGINEERS

DESIGNED	ACS	3				
DRAFTED	BKC, MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.


SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
EXISTING WET WELL PLAN & SECTION

SHEET C-403
126.42.300

7/04




DETAIL NOTES:

1. SEE SHEET C-111 FOR PUMPHOUSE FITTING SCHEDULE.

AIR VAC VALVE — NTS

A	A
C-105	C-107




DETAIL NOTES:

1. ALL COMPONENTS TO BE TYPE 304 STAINLESS STEEL.
2. WALL PIECE TO BE PLACED PRIOR TO CONCRETE PLACEMENT.

WALL PIECE — NTS

B
C-107




BOLLARD — NTS

C	C	C	C	C
A-101	A-102	C-101	C-106	C-202

C	C
PP-104	PP-105


REBAR SCHEDULE (UNO)	
SLAB THICKNESS	SPACING
6" & LESS	#4 @ 18" OC
8"	#4 @ 12" OC
10"	#4 @ 10" OC



NOTE:
1. DEPTH OF SLAB PER PLAN.


SLAB ON GRADE — NTS

D	D	D	D
–	C-101	C-202	C-402



GENERATOR CONCRETE FOUNDATION PLAN — NTS

E
C-101




DETAIL NOTES:

1. DETAIL IS PROVIDED FOR GENERAC SD400 12.5 L 400KW 480 V (136.02"x53.00"). ANCHOR GENERATOR TO PAD WITH (10) 3/4"x6" SIMPSON TITEN HD BOLTS (STAINLESS STEEL).
2. IF DIFFERENT GENERATOR IS USED, THEN CONTRACTOR IS TO PROVIDE AND VERIFY PAD DIMENSIONS AND THICKNESS WITH GENERATOR MANUFACTURER. ANCHOR BOLTS DIMENSIONS, COVER AND EDGE DISTANCES TO BE DESIGNED PER THE CRACKED-CONCRETE (SEISMIC) REQUIREMENTS OF THE CURRENT ACI 318 AND ACI 351.3R-18 CODE.
3. PROVIDE SEISMIC ISOLATORS AT THE BASE OF THE GENERATOR SLED IF RECOMMENDED BY MANUFACTURER.


SECTION — NTS

1
–



DIMENSIONS IN INCHES					
PIPE SIZE	A	B	C (SQ)	D	E
6	3	5.50	9	2.50	4.75
8	3	6.87	9	2.50	4.75
10	3	8.50	9	2.50	4.75
12	3	9.93	9	2.50	4.75
14	4	10.93	11	3	4.50
16	4	12.37	11	3	4.50

"A" = SCHEDULE 40 PIPE DIAMETER. LENGTH CUT ON SITE
"B" = BASE OF SADDLE TO CENTER OF PIPE
"C" = BASE PLATE (SQUARE) (DRILLED AND SLOTTED FROM PT&P)
"D" = THREADED PIPE ADJUSTER DIAMETER
"E" = TOTAL ALLOWABLE ADJUSTMENT



PIPE SUPPORTS — NTS

F	F	F
C-105	C-107	C-401

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

DESIGNED	ACS	3					
DRAFTED	TPB, MAJ	2					
CHECKED	GST	1					
DATE	APRIL 2024	NO.	DATE	REVISIONS		BY	APVD.


SCALE: AS SHOWN

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
MISCELLANEOUS DETAILS I


SHEET C-501

126.42.300

FILE NAME:PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-501 MISC DETAILS I.DWG
FILE DATE: 3.5.2024 17:55:34 (MAJ)
7/04



PLAN




SECTION 1 / NTS — —

KEY NOTES:

- (A) PROVIDE 2'-0" SQ X 6" HIGH CONCRETE CURB AT ROOF SLAB PENETRATION (SEE DETAIL H/S-507 FOR STRUCTURAL REQUIREMENTS)
- (B) 1/2" STAINLESS STEEL, 18 GAUGE MESH BIRD SCREEN SECURED BY FLANGE FITTING
- (C) TERMINATE MINIMUM 36" ABOVE TOP OF CONCRETE
- (D) 14" DIA SCH 40 GALVANIZED PIPE
- (E) (2) GALVANIZED STEEL PIPE ELBOWS TO FORM A GOOSENECK
- (F) 16" DIA GALV STEEL SLEEVE W/ 2" SEEP RING
- (G) PIPE CLAMP
- (H) LINK SEAL (MODEL S-316)
- (J) GROUT ANNULAR SPACE
- (K) FLEXIBLE COUPLING EQUAL TO FERNCO SERIES 1056 COUPLING
- (L) 14" DIA SCH 40 PVC BALANCING HAND DAMPER WITH LOCKING QUADRANT EQUAL TO RUSKIN MODEL PVC12
- (M) JOINT SEALANT PER SECTION 03 25 00

GOOSENECK AIR VENT — NTS — A C-106 | A C-108 | A S-507



DETAIL NOTES:

1. PROVIDE CONTROL JOINTS AT 15' OC MAX ALONG LENGTH OF CURB.

10" CURB — NTS — B C-101

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-502 MISC DETAILS II.DWG
FILE DATE: 4.17.2024 08:51:46 (MAJ)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TWEEDY
STATE OF UTAH

HANSEN ALLEN & LUCE, inc. ENGINEERS

DESIGNED	ACS	3				
DRAFTED	TPB, MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
MISCELLANEOUS DETAILS II


SHEET C-502

126.42.300


7/04




DROP ROD ASSEMBLY




TOP GATE HINGE




GATE KEEPER




GATE KEEPER POST




BOTTOM GATE HINGE AND GATE DETAIL




PIPE POST TIE



TWISTED & BARBED SELVAGE
TYPE II



BRACE AND TRUSS CONNECTIONS



CENTER GATE STOP AND GATE DETAIL

GENERAL SHEET NOTES:

1. MATERIALS, CONSTRUCTION, AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH PROJECT STANDARD SPECIFICATIONS.
2. USE TYPE II TOP SUPPORT (TWISTED & BARBED SELVAGE).
3. BARB WIRE SHALL BE USED ONLY WHEN DESIGNATED ON THE PLANS OR IN THE SPECIFICATIONS.
4. TWISTED AND BARBED SELVAGE TOP AND BOTTOM SHALL BE USED ON FENCES 5-FEET HIGH OR GREATER.
5. KNUCKLED SELVAGE ON TOP AND TWISTED AND BARBED ON BOTTOM SHALL BE USED ON FENCES LESS THAN 5-FEET.
6. ALL STEEL PIPE MEMBERS SHALL CONFORM TO THE REQUIREMENTS OF ASTM DESIGNATION F1083 SCHEDULE 40 HOT DIPPED ZINC COATED HIGH TENSILE STEEL PIPE OR TRIPLE COATED PIPE MADE FROM STEEL CONFORMING TO ASTM F1043.
7. POSTS SHALL BE STEEL SCHEDULE 40 PIPE OR TRIPLE COATED HIGH TENSILE STEEL PIPE OF THE SIZE SHOWN IN THE CHART. WEIGHT IN POUNDS PER FOOT WITH A TOLERANCE OF 5%.
8. LINE POSTS SHALL BE LOCATED AT EQUAL SPACING FOR EACH SEGMENT WITH A MAXIMUM SPACING AS FOLLOWS:
   A. TANGENT SECTIONS TO 500-FOOT RADIUS NOT MORE THAN 10-FEET.
   B. UNDER 500-FOOT RADIUS TO 200-FOOT RADIUS NOT MORE THAN 8-FEET.
   C. UNDER 200-FOOT RADIUS TO 100-FOOT RADIUS NOT MORE THAN 6-FEET.
   D. UNDER 100-FOOT RADIUS NOT MORE THAN 5-FEET.
9. TRUSS RODS AND BRACES SHALL NOT BE REQUIRED FOR FABRIC HEIGHT LESS THAN 5-FEET.
10. TENSION WIRE SHALL BE 7 GAUGE ZINC COIL SPRING STEEL TENSION WIRE.
11. PROVIDE PRIVACY SLATS IN ALL FENCES. PRIVACY SLATS SHALL NOT BE INSTALLED IN GATES. COORDINATE COLOR WITH OWNER. SLATS SHALL MEET REQUIREMENTS OF SECTION 32 31 13.

HEIGHT	GATE OPENING	GATE POST	GATE FRAME
UNDER 6 FEET	SINGLE TO 6' OR DOUBLE TO 12'	2"	1"
	SINGLE OVER 6' TO 8' OR DOUBLE OVER 12' TO 16'	2 1/2"	1 1/2"
	SINGLE OVER 8' TO 12' OR DOUBLE 16' TO 24'	3 1/2"	
6 FEET AND OVER	SINGLE OVER 6' OR DOUBLE TO 12'	2 1/2"	1 1/2"
	SINGLE OVER 6' TO 12' OR DOUBLE OVER 12' TO 24'	3 1/2"	
	SINGLE OVER 12' TO 18' OR DOUBLE OVER 24' TO 36'	6"	
	SINGLE OVER 18' OR DOUBLE OVER 36'	8"	

HEIGHT OF FABRIC	DEPTH OF POSTS	LENGTH OF END, CORNER OR PULL POST	LENGTH OF LINE POST HOLES	SIZE OF POSTS						
				END, CORNER, & PULL POSTS				LINE POST MIN. SIZE			
				NOM. SIZE	OUTSIDE DIA.	PIPE WEIGHT ASTM F1083	PIPE WEIGHT TRIPLE COATED	NOM. SIZE	OUTSIDE DIA.	PIPE WEIGHT ASTM F1083	PIPE WEIGHT TRIPLE COATED
8'	3'	11'	10'-8"	2 1/2"	2.875"	5.79	4.64	2"	2.375"	3.65	3.11
7'	3'	10'	9'-8"	2 1/2"	2.875"	5.79	4.64	2"	2.375"	3.65	3.11
6'	3'	9'	8'-8"	2 1/2"	2.875"	5.79	4.64	2"	2.375"	3.65	3.11
5'	3'	8'	7'-8"	2"	2.375"	3.65	3.11	1 1/2"	1.900"	2.72	2.23
4'	3'	6'	5'-8"	2"	2.375"	3.65	3.11	1 1/2"	1.900"	2.72	2.23
3'	3'	5'	4'-8"	2"	2.375"	3.65	3.11	1 1/2"	1.900"	2.72	2.23

TYPICAL CHAIN LINK FENCE DETAILS
NTS

A	A
C-101	PP-103

LICENSED PROFESSIONAL ENGINEER
GREGORY S. TWEEDIE
No. 5052482
4/18/24
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3			
DRAFTED	TPB	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY APVD.

SCALE AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
CHAIN LINK FENCE DETAILS

SHEET C-503
126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-503 CHAIN LINK FENCE DETAILS.DWG
FILE DATE: 3.5.2024 17:57:33 (MAJ)


7/04




DETAIL NOTES:

1. DESIGN OF CANTILEVER GATE TO BE BY MANUFACTURER.
2. ALL DIMENSIONS SHOWN ARE MINIMUMS AND SHALL BE ENLARGED AS REQUIRED BY MANUFACTURER.

20' WIDE CANTILEVER GATE — A / C–101
NTS



POST FOUNDATION — C / –
NTS



SLIDE GATE ASSEMBLY
(LOOKING DOWN TRACK) — B / –
NTS

GENERAL SHEET NOTES:

1. CRITICAL DIMENSIONS

MINIMUM GATE CLEAR OPENING:	20'–0"
TOP OF GATE HEIGHT:	8'–0"
POST HEIGHT:	8'–0"
ADJOINING FENCE HEIGHT:	8'–0"
BARB ARMS REQUIRED:	NO
GATE STORAGE IN OPEN POSITION (OUTSIDE LOOKING IN – RIGHT SHOWN)	RIGHT

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

DESIGNED	ACS	3					
DRAFTED	TPB	2					
CHECKED	GST	1					
DATE	APRIL 2024	NO.	DATE	REVISIONS		BY	APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
CANTILEVER GATE DETAILS

SHEET C–504
126.42.300

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\C–504 CANTILEVER GATE DETAILS.DWG
FILE DATE: 3.5.2024 17:58:31 (MAJ)
7/04

DETAIL NOTES:


1. VARIANCE FROM SPECIFIED DIMENSIONS AND SLOPES MUST BE ACCEPTABLE TO ENGINEER. SYSTEM CONFIGURATION MAY BE CHANGED AT ENGINEER'S DISCRETION.
2. BASE COURSE: UNTREATED BASE COURSE, SECTION 32 11 13.
3. EXPANSION JOINT FILLER: 1/2–INCH THICK TYPE F1 FULL DEPTH, SECTION 03 25 00.
4. CONCRETE: CLASS 4000, SECTION 03 30 00. HIGH EARLY STRENGTH CONCRETE MIXES MUST BE APPROVED BY ENGINEER. USE OF HIGH EARLY STRENGTH CONCRETE MAY RESULT IN CONCRETE CRAZING (SPIDER CRACKS) IF AIR TEMPERATURE EXCEEDS 90 DEGREES F.
5. CONCRETE CURING AGENT: CLEAR MEMBRANE FORMING COMPOUND WITH FUGITIVE DYE (TYPE ID CLASS A). INSTALL PER SECTION 03 30 00.
6. BASE COURSE PLACEMENT: THICKNESS IF 6–INCH IF FLOW LINE GRADE IS 0.5 PERCENT (S=0.005) OR GREATER. IF SLOPE IS LESS, PROVIDE 8–INCHES. MAXIMUM LIFT THICKNESS BEFORE COMPACTION IS 8–INCHES WHEN USING RIDING EQUIPMENT OR 6–INCHES WHEN USING HAND HELD EQUIPMENT. COMPACTION IS 95 PERCENT OR GREATER RELATIVE TO A MODIFIED PROCTOR DENSITY (ASTM D–1557).
7. CONCRETE PLACEMENT: SECTIONS 03 10 00 AND 03 30 00.
   A. INSTALL EXPANSION JOINTS VERTICAL, FULL DEPTH, WITH TOP FILLER SET FLUSH WITH CONCRETE SURFACE. INSTALL AT THE START OF END OF THE STREET INTERSECTION CURB RETURN. EXPANSION JOINTS ARE NOT REQUIRED IN CONCRETE PLACEMENT USING SLIP–FORM CONSTRUCTION.
   B. INSTALL CONTRACTION JOINTS VERTICAL, 1/8–INCH WIDE OR 1/4 SLAB THICKNESS IF THE SLAB IS GREATER THAN 8–INCHES THICK. MATCH JOINT LOCATION IN ADJACENT PORTLAND–CEMENT CONCRETE ROADWAY PAVEMENT.
   C. PROVIDE 1/2–INCH RADIUS EDGES. APPLY A BROOM FINISH. APPLY A CURING AGENT.
8. PROTECTION AND REPAIR: PROTECT CONCRETE FROM DEICING CHEMICALS DURING CURE. REPAIR CONSTRUCTION THAT DOES NOT DRAIN. IF NECESSARY, FILL FLOW–LINE WITH WATER TO VERIFY.



CURB AND GUTTER | A | —
NTS

DETAIL NOTES:


1. VARIANCE FROM SPECIFIED DIMENSIONS AND SLOPES MUST BE ACCEPTABLE TO ENGINEER. SYSTEM CONFIGURATION MAY BE CHANGED AT ENGINEER'S DISCRETION.
2. BASE COURSE: UNTREATED BASE COURSE, SECTION 32 11 13.
3. EXPANSION JOINT FILLER: 1/2–INCH THICK TYPE F1 FULL DEPTH, SECTION 03 25 00.
4. CONCRETE: CLASS 4000, SECTION 03 30 00. HIGH EARLY STRENGTH CONCRETE MIXES MUST BE APPROVED BY ENGINEER. USE OF HIGH EARLY STRENGTH CONCRETE MAY RESULT IN CONCRETE CRAZING (SPIDER CRACKS) IF AIR TEMPERATURE EXCEEDS 90 DEGREES F.
5. REINFORCEMENT: GALVANIZED OR EPOXY COASTED, DEFORMED, 60 KSI YIELD GRADE STEEL, ASTM A615.
6. CONCRETE CURING AGENT: CLEAR MEMBRANE FORMING COMPOUND WITH FUGITIVE DYE (TYPE ID CLASS A). INSTALL PER SECTION 03 30 00.
7. BASE COURSE PLACEMENT: THICKNESS IF 6–INCH IF FLOW LINE GRADE IS 0.5 PERCENT (S=0.005) OR GREATER. IF SLOPE IS LESS, PROVIDE 8–INCHES. MAXIMUM LIFT THICKNESS BEFORE COMPACTION IS 8–INCHES WHEN USING RIDING EQUIPMENT OR 6–INCHES WHEN USING HAND HELD EQUIPMENT. COMPACTION IS 95 PERCENT OR GREATER RELATIVE TO A MODIFIED PROCTOR DENSITY (ASTM D–1557).
8. CONCRETE PLACEMENT: SECTIONS 03 10 00 AND 03 30 00.
   A. INSTALL EXPANSION JOINTS VERTICAL, FULL DEPTH, WITH TOP FILLER SET FLUSH WITH CONCRETE SURFACE. INSTALL AT THE START OF END OF THE STREET INTERSECTION CURB RETURN. EXPANSION JOINTS ARE NOT REQUIRED IN CONCRETE PLACEMENT USING SLIP–FORM CONSTRUCTION.
   B. INSTALL CONTRACTION JOINTS VERTICAL, 1/8–INCH WIDE OR 1/4 SLAB THICKNESS IF THE SLAB IS GREATER THAN 8–INCHES THICK. MATCH JOINT LOCATION IN ADJACENT PORTLAND–CEMENT CONCRETE ROADWAY PAVEMENT.
   C. PROVIDE 1/2–INCH RADIUS EDGES. APPLY A BROOM FINISH. APPLY A CURING AGENT.
9. PROTECTION AND REPAIR: PROTECT CONCRETE FROM DEICING CHEMICALS DURING CURE. REPAIR CONSTRUCTION THAT DOES NOT DRAIN. IF NECESSARY, FILL FLOW–LINE WITH WATER TO VERIFY.



WATERWAY | B | B
NTS | — | C–101

DETAIL NOTES:

1. CASTINGS: GREY IRON CLASS 35 MINIMUM, ASTM A48, COATED WITH ASPHALT BASED PAINT OR BETTER (EXCEPT ON MACHINED SURFACES).
   A. CAST THE HEAD NUMBER ON THE FRAME AND COVER.
   B. GIVE THE FRAME AND COVER A MACHINE FINISH SO THE COVER WILL NOT ROCK.
   C. √ DESIGNATES MACHINED SURFACE.
   D. CAST THE WORDS "SEWER" ON THE COVER IN UPPER CASE FLUSH WITH THE SURFACE FINISH.
2. EXCEPT IN PAVED STREETS, PROVIDE LOCKING MANHOLE COVERED IN EASEMENTS, ALLEYS, PARKING LOTS, AND ALL OTHER PLACES. DRILL AND TAP TWO HOLES TO THE DEPTH OF 1–INCH AT 90 DEGREES TO PRY HOLE AND INSTALL 3/4 X 3/4–INCH ALLEN SOCKET SET SCREWS.



30" FRAME AND COVER | C | C | C
NTS | — | C–801 | C–802
C | C
C–803 | C–805

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\C–701 SSL DETAILS 1.DWG
FILE DATE: 3.5.2024 18:00:27 (MAJ)

HANSEN ALLEN & LUCE, Inc. ENGINEERS
LICENSED PROFESSIONAL ENGINEER 4/19/24 No. 5052482 GREGORY S. THOMAS STATE OF UTAH

DESIGNED	ACS	3				
DRAFTED	TPB, SWM	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
SOUTH SALT LAKE STANDARD DETAILS I


SHEET C–701
126.42.300

7/04

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-702 SSL DETAILS II.DWG
FILE DATE: 3.5.2024 18:31:43 (MAJ)

DETAIL NOTES:

1. VARIANCE FROM SPECIFIED DIMENSIONS AND SLOPES MUST BE ACCEPTABLE TO ENGINEER. SYSTEM CONFIGURATION MAY BE CHANGED AT ENGINEER'S DISCRETION.
2. BASE COURSE: UNTREATED BASE COURSE, SECTION 32 11 13.
3. EXPANSION JOINT FILLER: 1/2–INCH THICK TYPE F1 FULL DEPTH, SECTION 03 25 00.
4. CONCRETE: CLASS 4000, SECTION 03 30 00. HIGH EARLY STRENGTH CONCRETE MIXES MUST BE APPROVED BY ENGINEER. USE OF HIGH EARLY STRENGTH CONCRETE MAY RESULT IN CONCRETE CRAZING (SPIDER CRACKS) IF AIR TEMPERATURE EXCEEDS 90 DEGREES F.
5. CONCRETE CURING AGENT: CLEAR MEMBRANE FORMING COMPOUND WITH FUGITIVE DYE (TYPE ID CLASS A). INSTALL PER SECTION 03 30 00.
6. BASE COURSE PLACEMENT: MAXIMUM LIFT THICKNESS BEFORE COMPACTION IS 8–INCHES WHEN USING RIDING EQUIPMENT OR 6–INCHES WHEN USING HAND HELD EQUIPMENT. COMPACTION IS 95 PERCENT OR GREATER RELATIVE TO A MODIFIED PROCTOR DENSITY (ASTM D–1557).
7. CONCRETE PLACEMENT: SECTIONS 03 10 00 AND 03 30 00.
   A. INSTALL EXPANSION JOINTS VERTICAL, FULL DEPTH, WITH TOP FILLER SET FLUSH WITH CONCRETE SURFACE.
   B. INSTALL CONTRACTION JOINTS VERTICAL, 1/8–INCH WIDE OR 1/4 SLAB THICKNESS IF THE SLAB IS GREATER THAN 8–INCHES THICK. MAXIMUM LENGTH TO WIDTH RATIO FOR NON–SQUARE PANELS IS 1.5 TO 1. MAXIMUM PANEL LENGTH (IN FEET) IS 1.5 TIMES THE SLAB THICKNESS (IN INCHES).
   C. PROVIDE 1/2–INCH RADIUS EDGES. APPLY A BROOM FINISH. APPLY A CURING AGENT.




Sidewalk

This drawing replaces APWA Plan231
August 2018

SIDEWALK | A
NTS | —

DETAIL NOTES:

1. DECK IS MADE FOR ROUND MANHOLE RISER GRADE RINGS.
2. CONCRETE: CLASS 4000, SECTION 03 30 00.
3. REINFORCEMENT: DEFORMED, 60 KSI YIELD GRADE STEEL, ASTM A615.
4. CONCRETE PLACEMENT: SECTIONS 03 10 00 AND 03 30 00. APPLY A CURING AGENT.
5. REINFORCEMENT: PLACEMENT SECTION 03 20 00.




Concrete deck

This drawing replaces APWA Plan 345
August 2018

CONCRETE DECK | B | B
NTS | — | C–804

DETAIL NOTES:

1. IN A PAVEMENT SURFACE, THE CONCRETE WILL SUPPORT THE FRAME UNDER TRAFFIC LOADINGS.
2. CONCRETE: CLASS 4000, SECTION 03 30 00.
3. CONCRETE CURING AGENT: CLEAR MEMBRANE FORMING COMPOUNT WITH FUIGITIVE DYE (TYPE ID CLASS A), SECTION 03 30 00.
4. PAVEMENT PREPARATION: PROVIDE A NEAT VERTICAL AND CONCENTRIC JOINT BETWEEN CONCRETE AND EXISTING BITUMINOUS CONCRETE SURFACES. CLEAN EDGES OF ALL DIRT, OIL, AND LOOSE DEBRIS.
5. CONCRETE PLACEMENT: SECTIONS 03 10 00 AND 03 30 00. FILL THE ANNULAR SPACE AROUND THE FRAME AND COVER CASTING WITH CONCRETE. APPLY A BROOM FINISH. APPLY A CURING AGENT.



Cover collar for storm drains

This drawing replaces APWA Plan 362
August 2018

CONCRETE COLLAR FOR STORM DRAINS | C | C | C | C | C
NTS | — | C–801 | C–802 | C–803 | C–804 | C–805

HANSEN ALLEN & LUCE inc ENGINEERS

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TWEEDY
STATE OF UTAH

DESIGNED	ACS	3				
DRAFTED	TPB	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
SOUTH SALT LAKE STANDARD DETAILS II

SHEET C–702
126.42.300


7/04

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-703 SSL DETAILS III.DWG
FILE DATE: 3.5.2024 18:33:00 (MAJ)

BACKFILL AND PANEL TIE-IN




BACKFILL



BAR TYPE	BAR TYPE TABLE
⟷	30" LONG No. 5 TIE BARS AT 30" O.C.
⟷	30" LONG No. 5 TIE BARS AT 15" O.C.
—	18" LONG DOWEL BARS - SEE TABLE 1

TABLE 1	
PAVEMENT THICKNESS	DOWEL DIAMETER
LESS THAN 9"	1"
≥ 9" AND < 11"	1.25"
11" OR GREATER	1.5"



PANEL TIE-IN

Notes:
1. Notes for APWA Standard Plan 256.2 shall apply to this drawing.

Concrete pavement patch

This drawing replaces
APWA Plan 256.2
August 2018

SHEET 256.2
DATE SEPTEMBER, 2018

CONCRETE PAVEMENT PATCH

CITY OF SOUTH SALT LAKE
STANDARD DRAWINGS

SOUTH SALT LAKE PUBLIC WORKS DEPARTMENT
220 EAST MORRIS AVENUE, SUITE 200
SOUTH SALT LAKE, UTAH 84115

DRAWN | CHECKED | DATE | DESIGN

DETAIL NOTES:

1. REPRODUCE EXISTING PAVEMENT JOINT LAYOUT EVEN IF REPAIRS STRADDLE AN EXISTING JOINT. DETERMINE EXTENT AND DIMENSIONS OF REMOVAL FROM DRAWINGS, OR ACCEPTABLE TO ENGINEER. FORM ANY SIDE THAT DOES NOT HAVE AN ADJACENT PANEL. FORM TO MATCH EXISTING PANELS PROVIDING A VERTICAL EDGE.
2. BASE COURSE: UNTREATED BASE COURSE, SECTION 32 11 13.
3. REINFORCEMENT: 60 KSI YIELD GRADE STEEL, ASTM A615 EPOXY COATED OR GALVANIZED DEFORMED OR SMOOTH WITH DIAMETER AND LENGTH INDICATED.
   A. DOWEL BAR: SMOOTH
   B. TIE BAR: DEFORMED
   C. MAT: DEFORMED
4. DOWEL BAR END CAP: NON-METALLIC THAT ALLOWS 1/4 INCH LONGITUDINAL MOVEMENT OF BAR.
5. EXPANSION JOINT FILLER (IF REQUIRED): F-1: BITUMINOUS (ASPHALT OR TAR) MASTIC, ASTM D994. FORMED AND ENCASED BETWEEN TWO (2) LAYERS OF BITUMINOUS SATURATED FELT OR TWO (2) LAYERS OF GLASS-FIBER FELT.
6. CONTRACTION JOINT FILLER (BACKER ROD) (IF REQUIRED): ASPHALT BASE TYPE, ASTM D3405, OR ELASTOMERIC TYPE, ASTM D3406. ONE COMPONENT, FOR PORTLAND CEMENT CONCRETE PAVEMENTS.
7. TACKIFIER: EPOXY GEL TYPE II,
8. ADHESIVE: EPOXY ADHESIVE GROUT, SECTION 03 60 00 FOR GLUING BARS IN DRILLING HOLES IN CONCRETE.
9. BOND BREAKER (GREASE): PARAFFIN WAX, LITHIUM GREASE, OR OTHER SEMI-SOLID, INERT LUBRICANT.
10. CONCRETE: CLASS 4000, SECTION 03 30 00.
11. CONCRETE CURING AGENT: WHITE PIGMENTED MEMBRANE FORMING COMPOUND (TYPE II CLASS A OR B), SECTION 03 30 00.
12. WATER REPELLANT: PENETRATING COMPOUND, SECTION 07 19 00.
13. BASE COURSE PLACEMENT: SECTION 32 11 23. MAXIMUM LIFT THICKNESS BEFORE COMPACTION IS 8-INCHES WHEN USING RIDING EQUIPMENT OR 6-INCHES WHEN USING HAND HELD EQUIPMENT. COMPACTION IS 95 PERCENT OR GREATER RELATIVE TO A MODIFIED PROCTOR DENSITY (ASTM D-1557).
14. PREPARATION: MAKE FULL DEPTH SAW CUTS AROUND PERIMETER OF THE RECTANGULAR SECTION TO BE REMOVED. DO NOT OVER CUT. MAKE FULL DEPTH RECUTS ALONG ANY EDGE THAT IS DAMAGED DURING REPAIRS, INCLUDING FAILURES ON THE UNDERNEATH OF THE SLAB CAUSED BY INSUFFICIENT SAWCUT DEPTHS.
15. JOINT PREPARATION: USE A RIGID DRILL FRAME TO DRILL HOLES IN THE VERTICAL CENTER OF THE ADJACENT CONCRETE PANEL. DRILL HOLES PARALLEL TO THE PANEL SURFACE. DRILL HOLES AT MID-DEPTH OF SLAB. PROVIDE THE SPECIFIED SPACE BETWEEN DRILL HOLES. FOR DOWEL BARS, DRILL THE HOLES PARALLEL TO THE THOROUGHFARE CENTERLINE. LIMIT DEVIATION FROM PARALLEL TO 1/4-INCH IN THE LENGTH OF THE DOWEL BAR. CLEAN VERTICAL SURFACE OF THE ADJACENT CONCRETE. REMOVE CONTAMINANTS FROM HOLES.
   A. TACKIFIER REQUIRED ON VERTICAL SURFACE OF COLD JOINT, BOTH TRANSVERSE AND HORIZONTAL. DO NOT APPLY BOND BREAKER TO COLD JOINTS.
16. REINFORCEMENT: REMOVE DIRT, DUST, AND RUST FROM BARS. DO NOT INSTALL TIE BARS THAT INTERFERE WITH DOWEL BARS.
   A. FOR TIE BARS, PLACE ADHESIVE AT THE BACK OF EACH HOLE SO ADHESIVE FLOWS OUT, AROUND, AND FULLY ENCASES EACH INSERTED BAR. DO NOT COAT ONE END OF THE BAR AND THEN INSERT THE BAR INTO THE HOLE. PREVENT LOSS OF ADHESIVE UPON INSERTION.
   B. FOR DOWEL BARS, PLACE GREASE AT THE BACK OF EACH HOLE SO GREASE FLOWS OUT, AROUND, AND FULLY ENCASES EACH INSERTED BAR. GREASE THE BAR BEFORE INSERTION.
   C. GREASE PROTRUDING DOWEL BAR PRIOR TO CONCRETE PLACEMENT.
17. BOND BREAKER: PLACE BOND BREAKER ON ALL PAVEMENT JOINTS THAT COMPOSE EXISTING JOINTS, BOTH TRANSVERSE AND HORIZONTAL.
18. CONCRETE PLACEMENT: REPACK LOOSE BARS AND DAMPEN BASE COURSE UNIFORMLY. ALLOW FIRM SET OF ADHESIVE PRIOR TO PLACING CONCRETE. PLACE CONCRETE, CONSOLIDATE ALONG FACE OF EXISTING CONCRETE PANELS AND UNDER REINFORCEMENT, KEEP VIBRATORS AWAY FROM REINFORCING STEEL, AND PREVENT SEGREGATION. MATCH ADJACENT SURFACE TEXTURE.
19. CURE: APPLY CURING AGENT IN TOTAL COVERAGE IN 2 DIRECTIONS AFTER TEXTURING. KEEP CURE TEMPERATURE EVEN THROUGHOUT EXTENT AND DEPTH OF CONCRETE PATCH.
20. TRAFFIC: NOT ALLOWED ON PATCH UNTIL CONCRETE STRENGTH IS ACHIEVED.
21. SURFACE DISTORTIONS: AFTER CURE, REMOVE SURFACE DISTORTIONS THAT EXCEED 1/4-INCH DEVIATION IN 10-FEET. APPLY WATER REPELLANT TO SURFACES RECEIVING GRINDING.
22. FINISH: TEXTURE SURFACE TO MATCH EXISTING. DO NOT TOOL JOINTS THAT ARE TO BE SAWCUT AND SEALED.
23. REPAIR: REMOVE AND REPLACE ANY CONCRETE SLAB REPLACEMENT THAT EXHIBIT CRACKING, SHRINKAGE, OR FAILURE CAUSED BY TRAFFIC.

CONCRETE PAVEMENT PATCH — A
NTS — —

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TWEEDIE
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3					
DRAFTED	MAJ	2					
CHECKED	GST	1					
DATE	APRIL 2024	NO.	DATE	REVISIONS		BY	APVD.


SCALE: AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
SOUTH SALT LAKE STANDARD DETAILS III

SHEET C-703
126.42.300


7/04



RUBBER BOOT — NTS — A — | A C-802 | A C-803 | A C-805




MH-250 — NTS — B — PP-101




MH-251 — NTS — C — PP-101

MANHOLE LOCATIONS				
	CONTROL POINT 1		CONTROL POINT 2	
MANHOLE NUMBER	NORTHING	EASTING	NORTHING	EASTING
MH-250	7,432,218.98	1,527,602.87	7,432,212.98	1,527,608.87
MH-251	7,432,218.93	1,527,626.14	7,432,213.03	1,527,631.26
MH-202	7,432,271.73	1,527,736.79	7,432,263.27	1,527,737.44
MH-211	7,432,156.89	1,529,630.05	7,432,150.87	1,529,636.03
MH-212	7,432,611.66	1,529,631.75	7,432,605.64	1,529,637.73



SECTION — NTS — 1 — —



SECTION — NTS — 2 — —

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-801 MH DETAILS.DWG
FILE DATE: 3.6.2024 08:45:36 (MAJ)

LICENSED PROFESSIONAL ENGINEER — 4/19/24 — No. 5052482 — GREGORY S. TOBIAS — STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3					
DRAFTED	TPB	2					
CHECKED	GST	1					
DATE	APRIL 2024	NO.	DATE	REVISIONS		BY	APVD.

SCALE: NOT TO SCALE


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
MANHOLE DETAILS


SHEET C-801

126.42.300


7/04




MH-202 NTS — A PP-101




MH-211 NTS — B PP-105




MH-212 NTS — C PP-106



SECTION 1 NTS —



SECTION 2 NTS —



SECTION 3 NTS —

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-802 MH DETAILS.DWG
FILE DATE: 3.6.2024 08:47:22 (MAJ)

HANSEN ALLEN & LUCE inc ENGINEERS

LICENSED PROFESSIONAL ENGINEER — 4/19/24 — No. 5052482 — GREGORY S. TWEEDIE — STATE OF UTAH

DESIGNED	ACS	3			
DRAFTED	TPB	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY / APVD.


SCALE: NOT TO SCALE

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
MANHOLE DETAILS


SHEET C-802
126.42.300

7/04




TYPICAL 6' DIA MANHOLE — NTS

A	A	A	A
PP-101	PP-103	PP-104	PP-105



UDOT STORM DRAIN CONFLICT BOX — NTS

B
PP-101




STEEL CASING — NTS


C	C
–	PP-203

NOTES:

1. CARRIER PIPE WITHIN CASING SHALL BE SUPPORTED BY CASING SPACERS. THE NUMBER OF CASING SPACERS, THE SPACING BETWEEN THE CASING SPACERS, AND THE SPACING OF THE SPACERS FROM THE CARRYING PIPE JOINTS SHALL BE IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE MANUFACTURER, BUT IN NO CASE SHALL SPACERS BE SPACED GREATER THAN 5 FEET. SPACERS SHALL CENTER THE CARRIER PIPE WITHIN THE CASING PIPE AND THE CARRIER PIPE SHALL BE A CONTINUOUS GRADE AS SHOWN ON THE DRAWINGS. THE SPACERS SHALL BE SIZED TO BE CAPABLE OF SUPPORTING THE WEIGHT OF THE CARRIER PIPE AT MAXIMUM SANITARY SEWER FLOWS. SPACERS SHALL BE SECURELY ATTACHED TO THE CARRIER PIPE PER MANUFACTURER'S REQUIREMENTS. CASING SPACERS FOR STEEL CASING SHALL ELECTRICALLY ISOLATE THE CASING AND CARRIER PIPING.
2. STEEL CASING LENGTH SHOWN ON PLANS IS MINIMUM. LONGER CASINGS TO ACCOMMODATE MANUFACTURING STANDARDIZATION SHALL BE SHOWN ON SHOP DRAWINGS.
3. ISOLATING CASING SPACERS SHALL BE STAINLESS STEEL MODEL SSI12 AS MANUFACTURED BY APS.
4. MECHANICAL ELASTOMER SEALS SHALL BE USED ON BOTH ENDS OF CASING PIPE. MECHANICAL ELASTOMER SEALS SHALL BE INNERLYNX MODEL OS-316 BY APS.
5. ALL CARRIER PIPE JOINTS SHALL BE FULLY RESTRAINED WHEN WITHIN CASING. CARRIER PIPE SHALL BE TESTED BEFORE SEALING THE ENDS OF THE CASING.
6. CASING PIPE SHALL BE WELDED STEEL PER APWA STANDARD SPECIFICATION 33 05 23.35 OR AS REQUIRED FOR JACKING OPERATIONS.
7. CASING PIPE SHALL MEET UTA STANDARDS AND REQUIREMENTS FOR CASINGS. JACK AND BORE STEEL CASING MUST EXTEND 5-FEET OUTSIDE OF UTA RIGHT-OF-WAY LINES. UTA SHALL CONFIRM THE LIMITS OF THE CASING.



SECTION 1 — NTS



SECTION 2 — NTS

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\C-803 MH DETAILS.DWG
FILE DATE: 3.6.2024 08:56:16 (MAJ)

LICENSED PROFESSIONAL ENGINEER — 4/19/24 — No. 5052482 — GREGORY S. THOMAS — REGISTERED ENGINEER

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3				
DRAFTED	TPB	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.


SCALE: NOT TO SCALE

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
MANHOLE DETAILS


SHEET C-803
126.42.300

7/24



DETAIL NOTES:
1. POLYWRAP AND TRACER WIRE SHALL BE INSTALLED IN ACCORDANCE WITH SECTION 33 05 05.
2. BACKFILL TO TOP OF SUBGRADE PRIOR TO MAKING THE SECOND PAVEMENT CUT.
3. BASE COURSE SHALL BE 3/4"-MINUS UNTREATED BASE COURSE AS SPECIFIED IN SECTION 32 11 23.
4. COLD WEATHER PATCH NOT ALLOWED.
5. DEPTH OF PIPE ZONE MATERIAL BELOW PIPE (BEDDING) SHALL BE 4" (MIN) FOR PIPE UP TO 24" DIA, AND 6" (MIN) FOR PIPE OVER 24" DIA.


TYPICAL PIPELINE TRENCH DETAIL — A — NTS




DETAIL C —

DETAIL NOTES:
1. FOR LATERAL CONNECTION TO HDPE PIPE, INSTALL INSERTA TEE (OR APPROVED EQUAL), SIZE TO MATCH LATERAL. INCLUDE GROUT AROUND CONNECTION TO SEWER MAIN.
2. CONNECT EXISTING LATERAL TO NEW PVC SDR-35 LATERAL WITH FERNCO STRONG BACK RC 1000 SERIES COUPLING.

TYPICAL SERVICE TO MAIN DETAIL — B — NTS




PLAN




SECTION 1 — NTS

DETAIL NOTES:
1. INSIDE LENGTH AND WIDTH OF PRECAST BOX SHALL BE AS CALLED OUT IN PLANS.
2. FRAME AND GRATE SHALL BE CAST IRON OR GALVANIZED STEEL W/ BICYCLE SAFE GRATING. SIZE TO MATCH INSIDE DIMENSIONS OF BOX.
3. WALL AND BASE THICKNESS AND REINFORCEMENT SHALL BE AS REQUIRED BY MANUFACTURER FOR REQUIRED LOADS.

TYPICAL INLET BOX — D PP-301 — D PP-302 — NTS





TYPICAL 5' DIA SD MANHOLE — E PP-301 — E PP-302 — NTS

SECTION 2 — NTS

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TWEEDY
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3				
DRAFTED	MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.


SCALE: NOT TO SCALE

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
MISCELLANEOUS DETAILS I

SHEET C-804
126.42.300


FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-804 MISC DETAILS 1.DWG
FILE DATE: 3.6.2024 08:59:36 (MAJ)
7/04




TYPICAL 5' DIA MANHOLE

NTS

A	A	A	A	A
PP-101	PP-102	PP-103	PP-104	PP106



SECTION 1 — NTS — —




FIRE HYDRANT SECTION B — NTS — PP-104


LEGEND			
NO.	*	ITEM	DESCRIPTION
A		FIRE HYDRANT	AWWA C502
B		VALVE BOX WITH LID	2-PIECE CAST IRON
C		GATE VALVE WITH 2" X 2" NUT	AWWA C509
D		TEE WITH 125 # FLANGE	AWWA C110

DETAIL NOTES:

1. BEFORE BACKFILLING, SECURE INSPECTION OF INSTALLATION BY ENGINEER.
2. ADDITIONAL REQUIREMENTS ARE SPECIFIED IN APWA SECTION 33 11 00.
3. HYDRANT: DRY BARREL, AWWA C502.
4. THRUST BLOCKS: CONCRETE CLASS 4000, APWA SECTION 03 30 04.
5. REINFORCEMENT: DEFORMED, 60 KSI YIELD GRADE STEEL, ASTM A615.
6. BACKFILL: APWA SECTION 31 05 13. MAXIMUM PARTICLE SIZE 2-INCHES.
   A. SEWER ROCK: ASTM SIZE NO. 3 (2" TO 1") OR LARGER.
   B. OTHER TYPE OF COMMON FILL: CONTRACTOR'S CHOICE.
7. GEOTEXTILE: STABILIZATION-SEPARATION FABRIC, APWA SECTION 31 05 19.
8. INSTALLATION:
9. A. PROVIDE AT LEAST 1 CUBIC YARD OF SEWER ROCK AROUND DRAIN HOLE AT BASE OF HYDRANT SPOOL. WRAP GEOTEXTILE AROUND SEWER ROCK AND TAPE GEOTEXTILE TO HYDRANT SPOOL TO PREVENT SILTING OF SEWER ROCK.
10. PAINT FIRE HYDRANT TO AGENCY'S FIRE HYDRANT PAINT CODE.
11. APPLY NON-OXIDE GREASE TO ALL BURIED METAL SURFACES. WRAP WITH POLYETHYLENE SHEET AND TAPE WRAP.
12. NOTIFY FIRE DEPARTMENT AS SOON AS HYDRANT IS PLACED IN SERVICE.
13. THRUST BLOCKS: BEFORE POURING CONCRETE, WRAP PIPE SYSTEM WITH POLYETHYLENE SHEET TO PREVENT BONDING OF CONCRETE TO PIPE SYSTEM.
14. THRUST BLOCKS NOT REQUIRED FOR FLANGE OR WELDED PIPE SYSTEMS.
15. BACKFILL: MAXIMUM LIFT THICKNESS IS 8-INCHES BEFORE COMPACTION. COMPACTION IS 95 PERCENT OR GREATER RELATIVE TO A MODIFIED PROCTOR DENSITY, APWA SECTION 31 23 26.



SECTION 1 — NTS — —



NOTES:

1. CARRIER PIPE WITHIN CASING SHALL BE SUPPORTED BY CASING SPACERS. THE NUMBER OF CASING SPACERS, THE SPACING BETWEEN THE CASING SPACERS, AND THE SPACING OF THE SPACERS FROM THE CARRYING PIPE JOINTS SHALL BE IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE MANUFACTURER, BUT IN NO CASE SHALL SPACERS BE SPACED GREATER THAN 5 FEET. SPACERS SHALL CENTER THE CARRIER PIPE WITHIN THE CASING PIE AND THE CARRIER PIPE SHALL BE A CONTINUOUS GRADE AS SHOWN ON THE DRAWINGS. THE SPACERS SHALL BE SIZED TO BE CAPABLE OF SUPPORTING THE WEIGHT OF THE CARRIER PIPE AT MAXIMUM SANITARY SEWER FLOWS. SPACERS SHALL BE SECURELY ATTACHED TO THE CARRIER PIPE PER MANUFACTURER'S REQUIREMENTS. CASING SPACERS FOR STEEL CASING SHALL ELECTRICALLY ISOLATE THE CASING AND CARRIER PIPING.
2. STEEL CASING LENGTH SHOWN ON PLANS IS MINIMUM. LONGER CASINGS TO ACCOMMODATE MANUFACTURING STANDARDIZATION SHALL BE SHOWN ON SHOP DRAWINGS.
3. ISOLATING CASING SPACERS SHALL BE STAINLESS STEEL MODEL SSI12 AS MANUFACTURED BY APS.
4. MECHANICAL ELASTOMER SEALS SHALL BE USED ON BOTH ENDS OF CASING PIPE. MECHANICAL ELASTOMER SEALS SHALL BE INNERLYNX MODEL OS-316 BY APS.
5. ALL CARRIER PIPE JOINTS SHALL BE FULLY RESTRAINED WHEN WITHIN CASING. CARRIER PIPE SHALL BE TESTED BEFORE SEALING THE ENDS OF THE CASING.
6. CASING PIPE SHALL BE WELDED STEEL PER APWA STANDARD SPECIFICATION 33 05 23.35 OR AS REQUIRED FOR JACKING OPERATIONS.
7. CASING PIPE SHALL MEET UTA STANDARDS AND REQUIREMENTS FOR CASINGS. JACK AND BORE STEEL CASING MUST EXTEND 5-FEET OUTSIDE OF UTA RIGHT-OF-WAY LINES. UTA SHALL CONFIRM THE LIMITS OF THE CASING.

STEEL CASING C — NTS — PP-203

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE inc
ENGINEERS

DESIGNED	ACS	3				
DRAFTED	MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: NOT TO SCALE

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
MISCELLANEOUS DETAILS II

SHEET C-805


126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-805 MISC DETAILS II.DWG
FILE DATE: 3.6.2024 09:06:41 (MAJ)

7/04



PLAN



SECTION 1 / – NTS

CONDUIT TO MANHOLE MH–201 CONNECTION A / C–102 NTS

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\C–806 MISC DETAILS III.DWG
FILE DATE: 3.6.2024 11:09:57 (MAJ)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
REGISTERED ENGINEER

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3					
DRAFTED	MAJ	2					
CHECKED	GST	1					
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.	

SCALE: NOT TO SCALE


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
MISCELLANEOUS DETAILS III

SHEET C–806

126.42.300

7/04



PUMP STATION SITE NOTES

1. EXISTING PUMP STATION SHALL REMAIN IN SERVICE DURING CONSTRUCTION.
2. EXISTING PUMP STATION SHALL REMAIN AS BACKUP FOR THE NEW PUMPING STATION.
3. CONTRACTOR SHALL COORDINATE SITE ACCESS WITH SOUTH SALT LAKE.
4. CONTRACTOR SHALL MAINTAIN ACCESS TO THE EXISTING PUMP STATION FOR CITY PERSONNEL AND VEHICLES.

FILE NAME PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-901 TO C-906 BYPASS PUMPING PLAN.DWG
FILE DATE: 3.20.2024 11:01:39 (MAJ)

HANSEN ALLEN & LUCE Inc
ENGINEERS

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052480
GREGORY S. THOMAS
REGISTERED ENGINEER

DESIGNED	ACS	3				
DRAFTED	SWM	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
BYPASS PUMPING PLAN

SHEET C-901

126.42.300

7/04



FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-901 TO C-906 BYPASS PUMPING PLAN.DWG
FILE DATE: 3.20.2024 11:01:39 (MAJ)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH
REGISTERED ENGINEER

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3			
DRAFTED	SWM	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
BYPASS PUMPING PLAN

SHEET C-902
126.42.300

7/04



FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-901 TO C-906 BYPASS PUMPING PLAN.DWG
FILE DATE: 5.20.2024, 11:01:39 (MAJ)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE Inc ENGINEERS

DESIGNED	ACS	3					
DRAFTED	SWM	2					
CHECKED	GST	1					
DATE	APRIL 2024	NO.	DATE	REVISIONS		BY	APVD.

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
BYPASS PUMPING PLAN

SHEET C-903

126.42.300

7/04



FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWN
FILE DATE: 3.20.2024 11:01:39 (MAJ)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE inc
ENGINEERS

DESIGNED	ACS	3				
DRAFTED	SWM	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
BYPASS PUMPING PLAN

SHEET C-904

126.42.300

7/04



FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-901 TO C-906 BYPASS PUMPING PLAN.DWG
FILE DATE: 3.20.2024 11:01:39 (MAJ)

HANSEN ALLEN & LUCE Inc ENGINEERS

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

DESIGNED	ACS	3				
DRAFTED	SWM	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
BYPASS PUMPING PLAN

SHEET C-905

126.42.300

7/04



FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-901 TO C-906 BYPASS PUMPING PLAN.DWG
FILE DATE: 3.20.2024 11:01:39 (MAJ)

HANSEN ALLEN & LUCE Inc ENGINEERS

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

DESIGNED	ACS	3				
DRAFTED	SWM	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
BYPASS PUMPING PLAN

SHEET C-906

126.42.300

7/04



FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-907 TO C-910 BYPASS PUMPING PLAN.DWG
FILE DATE: 12.27.2023 12:51:26 (SWN)

7/04

HANSEN ALLEN & LUCE inc
ENGINEERS

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. [illegible]
STATE OF UTAH
REGISTERED ENGINEER

DESIGNED	ACS	3				
DRAFTED	TMT	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE
AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
BYPASS PUMPING PLAN

SHEET
C-907
126.42.300



FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\C-907 TO C-910 BYPASS PUMPING PLAN.DWG
FILE DATE: 12.27.2023 12:51:26 (SWM)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TIMMS
STATE OF UTAH

DESIGNED	ACS	3				
DRAFTED	TMT	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

HANSEN ALLEN & LUCE inc. ENGINEERS

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
BYPASS PUMPING PLAN

SHEET: C–908

126.42.300

7/04



FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-907 TO C-910 BYPASS PUMPING PLAN.DWG
FILE DATE: 12.27.2023 12:51:26 (SWM)

HANSEN ALLEN & LUCE inc ENGINEERS

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TIMOTHY
STATE OF UTAH
PROFESSIONAL ENGINEER

DESIGNED	ACS	3				
DRAFTED	TMT	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
BYPASS PUMPING PLAN

SHEET: C-909

126.42.300

7/04



FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\C-907 TO C-910 BYPASS PUMPING PLAN.DWG
FILE DATE: 12.27.2023 12:51:26 (SWM)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TIMMERMAS
STATE OF UTAH

HANSEN ALLEN & LUCE Inc. ENGINEERS

DESIGNED	ACS	3					
DRAFTED	TMT	2					
CHECKED	GST	1					
DATE	APRIL 2024	NO.	DATE	REVISIONS		BY	APVD.


SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
CIVIL
BYPASS PUMPING PLAN

SHEET: C-910
126.42.300

7/04




NOTES:

1. CONTRACTOR SHALL PROTECT IN PLACE AND MAINTAIN IN SERVICE ALL EXISTING UTILITIES. REFER TO GENERAL NOTE 4 ON SHEET G-005.
2. REFER TO NOTE 1 ON SHEET G-102 FOR SUE LEVEL DEFINITIONS.
3. CONTRACTOR SHALL FIELD VERIFY MANHOLE RIM ELEVATIONS PRIOR TO FABRICATION OF MANHOLES.
4. PIPE INVERT ELEVATIONS ARE AT INSIDE EDGE OF MANHOLE.
5. PIPE LENGTHS ARE FROM INSIDE EDGE OF MANHOLE TO INSIDE EDGE OF MANHOLE.
6. TRENCH PER DETAIL A ON DRAWING SHEET C-804.
7. CURB & GUTTER RESTORATION PER DETAIL A ON SHEET C-701. CURB & GUTTER REMOVAL AND REPLACEMENT SHALL BE FROM EXPANSION/CONTRACTION JOINT TO EXPANSION/CONTRACTION JOINT.
8. CURVED SEWER ALIGNMENT BETWEEN MH-202 AND MH-204 TO BE FIELD SURVEYED PRIOR TO BACKFILLING. SURVEY POINTS ALONG INSTALLED ALIGNMENT AT INTERVALS OF 50-FEET. CONTACT TIM NEWELL, HANSEN, ALLEN & LUCE FOR SURVEY VERIFICATION. 48-HOURS ADVANCED NOTICE REQUIRED.

#KEYED NOTES:


1. REMOVE EXISTING SANITARY SEWER AND MANHOLES AND INSTALL PROPOSED.
2. RECONNECT EXISTING SANITARY SEWER. FIELD VERIFY LOCATION AND ELEVATION PRIOR TO CONSTRUCTION.
4. REMOVE EXISTING MANHOLE.
5. ABANDON EXISTING MANHOLE AND 30" PIPELINE.
6. CONTRACTOR TO FIELD VERIFY PIPE DIAMETER PRIOR TO CONSTRUCTION OF DOWNSTREAM SANITARY SEWER. CONTACT ENGINEER IF OTHER THAN 8-INCH NOMINAL.
7. ORIENT VERTICAL SIDE OF CONE ON MH-201 TOWARDS 8" CPVC CONDUIT TO ALLOW CONDUIT TO PENETRATE THE MANHOLE CONE THROUGH A VERTICAL WALL.



LICENSED PROFESSIONAL ENGINEER
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH
4/4/24

HANSEN ALLEN & LUCE inc ENGINEERS	DESIGNED TPB	3					SCALE AS SHOWN
	DRAFTED TPB	2					SOUTH SALT LAKE
	CHECKED GST	1					DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION PLAN & PROFILE STA. 1+00 TO STA. 6+00
	DATE APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.	SHEET PP-101 126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\PP-DOWNTOWN-UTOPIA.DWG
FILE DATE: 4.2.2024 10:22:20 (LRH)
7/04



NOTES:


1. CONTRACTOR SHALL PROTECT IN PLACE AND MAINTAIN IN SERVICE ALL EXISTING UTILITIES. REFER TO GENERAL NOTE 4 ON SHEET G-005.
2. REFER TO GENERAL NOTE 1 ON SHEET G-102 FOR SUE LEVEL DEFINITIONS.
3. CONTRACTOR SHALL FIELD VERIFY MANHOLE RIM ELEVATIONS PRIOR TO FABRICATION OF MANHOLES.
4. PIPE INVERT ELEVATIONS ARE AT INSIDE EDGE OF MANHOLE.
5. PIPE LENGTHS ARE FROM INSIDE EDGE OF MANHOLE TO INSIDE EDGE OF MANHOLE.
6. TRENCH PER DETAIL A ON DRAWING SHEET C-804.
7. CURVED SEWER ALIGNMENT BETWEEN MH-202 AND MH-204 TO BE FIELD SURVEYED PRIOR TO BACKFILLING. SURVEY POINTS ALONG INSTALLED ALIGNMENT AT INTERVALS OF 50-FEET. CONTACT TIM NEWELL, HANSEN, ALLEN & LUCE FOR SURVEY VERIFICATION. 48-HOURS ADVANCED NOTIFICATION REQUIRED.

#KEYED NOTES:

(1) REMOVE EXISTING SANITARY SEWER AND MANHOLES AND INSTALL PROPOSED.

(4) REMOVE EXISTING MANHOLE.

(6) INSTALL TEMPORARY CONSTRUCTION FENCE (SNOW FENCE) 10' OFF TRAX CENTERLINE. CONTRACTOR PERSONNEL SHALL NOT CROSS TEMPORARY CONSTRUCTION FENCE WITHOUT UTA PERSONNEL ON SITE.



LICENSED PROFESSIONAL ENGINEER
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH
4/4/24

HANSEN ALLEN & LUCE Inc ENGINEERS

DESIGNED	TPB	3			
DRAFTED	TPB	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY APVD.

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
PLAN & PROFILE
STA. 6+00 TO STA. 11+00

SHEET PP-102
126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\PP-DOWNTOWN-UTOPIA.DWG
FILE DATE: 4.2.2024 10:22:20 (LRH)

7/04




NOTES:

1. CONTRACTOR SHALL PROTECT IN PLACE AND MAINTAIN IN SERVICE ALL EXISTING UTILITIES. REFER TO GENERAL NOTE 4 ON SHEET G-005.
2. REFER TO GENERAL NOTE 1 ON SHEET G-102 FOR SUE LEVEL DEFINITIONS.
3. CONTRACTOR SHALL FIELD VERIFY MANHOLE RIM ELEVATIONS PRIOR TO FABRICATION OF MANHOLES.
4. PIPE INVERT ELEVATIONS ARE AT INSIDE EDGE OF MANHOLE.
5. PIPE LENGTHS ARE FROM INSIDE EDGE OF MANHOLE TO INSIDE EDGE OF MANHOLE.
6. TRENCH PER DETAIL A ON DRAWING SHEET C-804.
7. ASPHALT PAVEMENT T-PATCH RESTORATION PER APWA PLAN 255. 2-FOOT WIDE MILL AND OVERLAY BEYOND TRENCH T-PATCH SHALL BE REQUIRED.
8. CURB & GUTTER RESTORATION PER DETAIL A ON SHEET C-701. CURB & GUTTER REMOVAL AND REPLACEMENT SHALL BE FROM EXPANSION/CONTRACTION JOINT TO EXPANSION/CONTRACTION JOINT.

#KEYED NOTES:

1. REMOVE EXISTING SANITARY SEWER AND MANHOLES AND INSTALL PROPOSED.
2. RECONNECT EXISTING SANITARY SEWER. FIELD VERIFY LOCATION AND ELEVATION PRIOR TO CONSTRUCTION.
6. INSTALL TEMPORARY CONSTRUCTION FENCE (SNOW FENCE) 10' OFF TRAX CENTERLINE. CONTRACTOR PERSONNEL SHALL NOT CROSS TEMPORARY CONSTRUCTION FENCE WITHOUT UTA PERSONNEL ON SITE.



LICENSED PROFESSIONAL ENGINEER
5/10/24
No. 5052482
GREGORY S. THOMAS
REGISTERED PROFESSIONAL ENGINEER

HANSEN ALLEN & LUCE Inc ENGINEERS

DESIGNED	TPB	3				
DRAFTED	TPB	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
PLAN & PROFILE
STA. 11+00 TO STA. 16+00

SHEET PP-103
126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\PP-DOWNTOWN-UTOPIA.DWG
FILE DATE: 4.2.2024 10:22:20 (LRH)

7/04




NOTES:

1. CONTRACTOR SHALL PROTECT IN PLACE AND MAINTAIN IN SERVICE ALL EXISTING UTILITIES. REFER TO GENERAL NOTE 4 ON SHEET G-005.
2. REFER TO GENERAL NOTE 1 ON SHEET G-102 FOR SUE LEVEL DEFINITIONS.
3. CONTRACTOR SHALL FIELD VERIFY MANHOLE RIM ELEVATIONS PRIOR TO FABRICATION OF MANHOLES.
4. PIPE INVERT ELEVATIONS ARE AT INSIDE EDGE OF MANHOLE.
5. PIPE LENGTHS ARE FROM INSIDE EDGE OF MANHOLE TO INSIDE EDGE OF MANHOLE.
6. TRENCH PER DETAIL A ON DRAWING SHEET C-804.
7. CURB & GUTTER RESTORATION PER DETAIL A ON SHEET C-701. CURB & GUTTER REMOVAL AND REPLACEMENT SHALL BE FROM EXPANSION/CONTRACTION JOINT TO EXPANSION/CONTRACTION JOINT.
8. WATERWAY RESTORATION PER DETAIL B ON SHEET C-701.

#KEYED NOTES:

1. REMOVE EXISTING SANITARY SEWER AND MANHOLES AND INSTALL PROPOSED.
2. RECONNECT EXISTING SANITARY SEWER. FIELD VERIFY LOCATION AND ELEVATION PRIOR TO CONSTRUCTION.
3. RECONNECT EXISTING 4" LATERAL TO NEW MAIN PER DETAIL B ON DRAWING SHEET C-804.



LICENSED PROFESSIONAL ENGINEER
GREGORY S. THOMAS
No. 5052482
STATE OF UTAH
5/10/24

DESIGNED	TPB	3					
DRAFTED	TPB	2					
CHECKED	GST	1					
DATE	APRIL 2024	NO.	DATE	REVISIONS		BY	APVD.

HANSEN ALLEN & LUCE Inc ENGINEERS

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
PLAN & PROFILE
STA. 16+00 TO STA. 21+00

SHEET PP-104
126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\PP-DOWNTOWN-UTOPIA.DWG
FILE DATE: 4.2.2024 10:22:20 (LRH)

7/04




NOTES:

1. CONTRACTOR SHALL PROTECT IN PLACE AND MAINTAIN IN SERVICE ALL EXISTING UTILITIES. REFER TO GENERAL NOTE 4 ON SHEET G-005.
2. REFER TO GENERAL NOTE 1 ON SHEET G-102 FOR SUE LEVEL DEFINITIONS.
3. CONTRACTOR SHALL FIELD VERIFY MANHOLE RIM ELEVATIONS PRIOR TO FABRICATION OF MANHOLES.
4. PIPE INVERT ELEVATIONS ARE AT INSIDE EDGE OF MANHOLE.
5. PIPE LENGTHS ARE FROM INSIDE EDGE OF MANHOLE TO INSIDE EDGE OF MANHOLE.
6. TRENCH PER DETAIL A ON DRAWING SHEET C-804.

#KEYED NOTES:

1. REMOVE EXISTING SANITARY SEWER AND MANHOLES AND INSTALL PROPOSED.
2. RECONNECT EXISTING SANITARY SEWER. FIELD VERIFY LOCATION AND ELEVATION PRIOR TO CONSTRUCTION.
3. RECONNECT EXISTING 4" LATERAL TO NEW MAIN PER DETAIL B ON DRAWING SHEET C-804.
4. REMOVE EXISTING MANHOLE.




LICENSED PROFESSIONAL ENGINEER
No. 5052482
GREGORY S. THORNE
STATE OF UTAH
5/10/24

HANSEN ALLEN & LUCE inc ENGINEERS	DESIGNED TPB	3					SCALE AS SHOWN
	DRAFTED TPB	2					SOUTH SALT LAKE
	CHECKED GST	1					DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
	DATE APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.	PLAN & PROFILE STA. 21+00 TO STA. 26+00
							SHEET PP-105
							126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\PP-DOWNTOWN-UTOPIA.DWG
FILE DATE: 4.2.2024 10:22:20 (LRH)

7/04




NOTES:

1. CONTRACTOR SHALL PROTECT IN PLACE AND MAINTAIN IN SERVICE ALL EXISTING UTILITIES. REFER TO GENERAL NOTE 4 ON SHEET G-005.
2. REFER TO GENERAL NOTE 1 ON SHEET G-102 FOR SUE LEVEL DEFINITIONS.
3. CONTRACTOR SHALL FIELD VERIFY MANHOLE RIM ELEVATIONS PRIOR TO FABRICATION OF MANHOLES.
4. PIPE INVERT ELEVATIONS ARE AT INSIDE EDGE OF MANHOLE.
5. PIPE LENGTHS ARE FROM INSIDE EDGE OF MANHOLE TO INSIDE EDGE OF MANHOLE.
6. TRENCH PER DETAIL A ON DRAWING SHEET C-804.

#KEYED NOTES:

1. REMOVE EXISTING SANITARY SEWER AND MANHOLES AND INSTALL PROPOSED.
2. RECONNECT EXISTING SANITARY SEWER. FIELD VERIFY LOCATION AND ELEVATION PRIOR TO CONSTRUCTION.
3. RECONNECT EXISTING 4" LATERAL TO NEW MAIN PER DETAIL B ON DRAWING SHEET C-804.



LICENSED PROFESSIONAL ENGINEER
No. 5052482
GREGORY S. THORNE
STATE OF UTAH
5/10/24

HANSEN ALLEN & LUCE Inc ENGINEERS

DESIGNED	TPB	3				
DRAFTED	TPB	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
PLAN & PROFILE
STA. 26+00 TO STA. 30+07

SHEET PP-106
126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\PP-DOWNTOWN-UTOPIA.DWG
FILE DATE: 4.2.2024 10:22:20 (LRH)

7/04




NOTES:

1. CONTRACTOR SHALL PROTECT IN PLACE AND MAINTAIN IN SERVICE ALL EXISTING UTILITIES. REFER TO GENERAL NOTE 4 ON SHEET G-005.
2. REFER TO NOTE 1 ON SHEET G-102 FOR SUE LEVEL DEFINITIONS.
3. CONTRACTOR SHALL FIELD VERIFY MANHOLE RIM ELEVATIONS PRIOR TO FABRICATION OF MANHOLES.
4. PIPE INVERT ELEVATIONS ARE AT INSIDE EDGE OF MANHOLE.
5. PIPE LENGTHS ARE FROM INSIDE EDGE OF MANHOLE TO INSIDE EDGE OF MANHOLE.
6. TRENCH PER DETAIL A/C-804.
7. CONCRETE PAVEMENT RESTORATION PER DETAIL A ON SHEET C-703. FULL PANEL REMOVAL AND REPLACEMENT IS REQUIRED. PARTIAL PANEL REMOVAL AND REPLACEMENT WILL NO BE ALLOWED.

#KEYED NOTES:

1. REMOVE EXISTING SANITARY SEWER AND MANHOLES AND INSTALL PROPOSED.
2. RECONNECT EXISTING SANITARY SEWER. FIELD VERIFY LOCATION AND ELEVATION PRIOR TO CONSTRUCTION.
3. RECONNECT EXISTING 4" LATERAL TO NEW MAIN PER DETAIL B/C-804.



FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\PP-201 TO PP-204 DOWNTOWN-WTEMPLE.DWG
FILE DATE: 12.27.2023 11:12:46 (SWM)

HANSEN ALLEN & LUCE, Inc. ENGINEERS

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TUCKER
PROJECT ENGINEER

DESIGNED	TPB	3			
DRAFTED	TPB	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY / APVD.


SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
PLAN & PROFILE – WEST TEMPLE
STA. 22+70 TO STA. 27+00

SHEET: PP-201
126.42.300

7/04




NOTES:

1. CONTRACTOR SHALL PROTECT IN PLACE AND MAINTAIN IN SERVICE ALL EXISTING UTILITIES. REFER TO GENERAL NOTE 4 ON SHEET G-005.
2. REFER TO NOTE 1 ON SHEET G-102 FOR SUE LEVEL DEFINITIONS.
3. CONTRACTOR SHALL FIELD VERIFY MANHOLE RIM ELEVATIONS PRIOR TO FABRICATION OF MANHOLES.
4. PIPE INVERT ELEVATIONS ARE AT INSIDE EDGE OF MANHOLE.
5. PIPE LENGTHS ARE FROM INSIDE EDGE OF MANHOLE TO INSIDE EDGE OF MANHOLE.
6. TRENCH PER DETAIL A/C-804.
7. CONCRETE PAVEMENT RESTORATION PER DETAIL A ON SHEET C-703. FULL PANEL REMOVAL AND REPLACEMENT IS REQUIRED. PARTIAL PANEL REMOVAL AND REPLACEMENT WILL NO BE ALLOWED.

#KEYED NOTES:

1. REMOVE EXISTING SANITARY SEWER AND MANHOLES AND INSTALL PROPOSED.
2. RECONNECT EXISTING SANITARY SEWER. FIELD VERIFY LOCATION AND ELEVATION PRIOR TO CONSTRUCTION.
3. RECONNECT EXISTING 4" LATERAL TO NEW MAIN PER DETAIL B/C-804.



FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\PP-201 TO PP-204 DOWNTOWN-WTEMPLE.DWG
FILE DATE: 12.27.2023 11:12:46 (SWM)

HANSEN ALLEN & LUCE ENGINEERS

LICENSED PROFESSIONAL ENGINEER — GREGORY S. TWEEDY — No. 5052482 — 4/10/24 — STATE OF UTAH — CIVIL ENGINEER

DESIGNED	TPB	3			
DRAFTED	TPB	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY / APVD.


SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
PLAN & PROFILE – WEST TEMPLE
STA. 27+00 TO STA. 32+00

SHEET: PP-202
126.42.300

7/04




NOTES:

1. CONTRACTOR SHALL PROTECT IN PLACE AND MAINTAIN IN SERVICE ALL EXISTING UTILITIES. REFER TO GENERAL NOTE 4 ON SHEET G-005.
2. REFER TO NOTE 1 ON SHEET G-102 FOR SUE LEVEL DEFINITIONS.
3. CONTRACTOR SHALL FIELD VERIFY MANHOLE RIM ELEVATIONS PRIOR TO FABRICATION OF MANHOLES.
4. PIPE INVERT ELEVATIONS ARE AT INSIDE EDGE OF MANHOLE.
5. PIPE LENGTHS ARE FROM INSIDE EDGE OF MANHOLE TO INSIDE EDGE OF MANHOLE.
6. TRENCH PER DETAIL A/C-804.
7. CONCRETE PAVEMENT RESTORATION PER DETAIL A ON SHEET C-703. FULL PANEL REMOVAL AND REPLACEMENT IS REQUIRED. PARTIAL PANEL REMOVAL AND REPLACEMENT WILL NO BE ALLOWED.

#KEYED NOTES:

1. REMOVE EXISTING SANITARY SEWER AND MANHOLES AND INSTALL PROPOSED.
2. RECONNECT EXISTING SANITARY SEWER. FIELD VERIFY LOCATION AND ELEVATION PRIOR TO CONSTRUCTION.
3. RECONNECT EXISTING 4" LATERAL TO NEW MAIN PER DETAIL B/C-804.



FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\PP-201 TO PP-204 DOWNTOWN-WTEMPLE.DWG
FILE DATE: 12.27.2023 11:12:46 (SWM)

HANSEN ALLEN & LUCE ENGINEERS

LICENSED PROFESSIONAL ENGINEER
No. 5052482
GREGORY S. TIMOTHY
4/10/24
PROJECT ENGINEER

DESIGNED	TPB	3				
DRAFTED	TPB	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.


SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
PLAN & PROFILE – WEST TEMPLE
STA. 32+00 TO STA. 37+00

SHEET: PP-203
126.42.300

7/04




NOTES:

1. CONTRACTOR SHALL PROTECT IN PLACE AND MAINTAIN IN SERVICE ALL EXISTING UTILITIES. REFER TO GENERAL NOTE 4 ON SHEET G-005.
2. REFER TO NOTE 1 ON SHEET G-102 FOR SUE LEVEL DEFINITIONS.
3. CONTRACTOR SHALL FIELD VERIFY MANHOLE RIM ELEVATIONS PRIOR TO FABRICATION OF MANHOLES.
4. PIPE INVERT ELEVATIONS ARE AT INSIDE EDGE OF MANHOLE.
5. PIPE LENGTHS ARE FROM INSIDE EDGE OF MANHOLE TO INSIDE EDGE OF MANHOLE.
6. TRENCH PER DETAIL A/C-804.
7. CONCRETE PAVEMENT RESTORATION PER DETAIL A ON SHEET C-703. FULL PANEL REMOVAL AND REPLACEMENT IS REQUIRED. PARTIAL PANEL REMOVAL AND REPLACEMENT WILL NO BE ALLOWED.

#KEYED NOTES:

1. REMOVE EXISTING SANITARY SEWER AND MANHOLES AND INSTALL PROPOSED.
2. RECONNECT EXISTING SANITARY SEWER. FIELD VERIFY LOCATION AND ELEVATION PRIOR TO CONSTRUCTION.
3. RECONNECT EXISTING 4" LATERAL TO NEW MAIN PER DETAIL B/C-804.
4. REMOVE EXISTING MANHOLE.



FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\PP-201 TO PP-204 DOWNTOWN-WTEMPLE.DWG
FILE DATE: 12.27.2023 11:12:46 (SWM)

HANSEN ALLEN & LUCE, Inc. ENGINEERS

LICENSED PROFESSIONAL ENGINEER No. 5052482 GREGORY S. TOMSIC 4/10/24 CIVIL

DESIGNED	TPB	3				
DRAFTED	TPB	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN


SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
PLAN & PROFILE - WEST TEMPLE
STA. 37+00 TO STA. 41+58

SHEET: PP-204

126.42.300


7/04





NOTES:

1. CONTRACTOR SHALL PROTECT IN PLACE AND MAINTAIN IN SERVICE ALL EXISTING UTILITIES. REFER TO GENERAL NOTE 4 ON SHEET G-005.
2. REFER TO NOTE 1 ON SHEET G-102 FOR SUE LEVEL DEFINITIONS.
3. CONTRACTOR SHALL FIELD VERIFY MANHOLE RIM ELEVATIONS PRIOR TO FABRICATION OF MANHOLES.
4. PIPE INVERT ELEVATIONS ARE AT INSIDE EDGE OF MANHOLE.
5. PIPE LENGTHS ARE FROM INSIDE EDGE OF MANHOLE TO INSIDE EDGE OF MANHOLE.




LICENSED PROFESSIONAL ENGINEER
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS	DESIGNED TPB	3				SCALE AS SHOWN	SOUTH SALT LAKE
	DRAFTED TPB	2					DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION PLAN & PROFILE LIFT STATION STORM DRAIN I
	CHECKED GST	1					SHEET PP-301
	DATE APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.	126.42.300

FILE NAME PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\PP-301 - STORM DRAIN.DWG
FILE DATE: 3.20.2024 09:04:40 (MA)

7/04




NOTES:

1. CONTRACTOR SHALL PROTECT IN PLACE AND MAINTAIN IN SERVICE ALL EXISTING UTILITIES. REFER TO GENERAL NOTE 4 ON SHEET G-005.
2. REFER TO NOTE 1 ON SHEET G-102 FOR SUE LEVEL DEFINITIONS.
3. CONTRACTOR SHALL FIELD VERIFY MANHOLE RIM ELEVATIONS PRIOR TO FABRICATION OF MANHOLES.
4. PIPE INVERT ELEVATIONS ARE AT INSIDE EDGE OF MANHOLE.
5. PIPE LENGTHS ARE FROM INSIDE EDGE OF MANHOLE TO INSIDE EDGE OF MANHOLE.

#KEYED NOTES:

(1) SIZE, ELEVATION AND LOCATION OF SEWER ESTIMATED. CONTRACTOR TO POTHOLE AND VERIFY ELEVATION PRIOR TO CONSTRUCTION STORM DRAIN. NOTIFY ENGINEER OF ANY CONFLICTS.

(2) IF CLEARANCE IS LESS THAN 1", EXPOSE SEWER PIPE AND THEN BACKFILL FROM SPRINGLINE OF SEWER PIPE TO SPRINGLINE OF STORM DRAIN PIPE WITH FLOWABLE FILL, UNLESS DIRECTED OTHERWISE BY ENGINEER.



LICENSED PROFESSIONAL ENGINEER
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

DESIGNED	TPB	3				
DRAFTED	TPB	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

HANSEN ALLEN & LUCE inc ENGINEERS

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
PLAN & PROFILE
LIFT STATION STORM DRAIN II

SHEET PP-302
126.42.300


FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\PP-302 - STORM DRAIN.DWG
FILE DATE: 3.20.2024 09:32:04 (MAJ)

7/04



NOTES:

1. CONTRACTOR SHALL PROTECT IN PLACE AND MAINTAIN IN SERVICE ALL EXISTING UTILITIES. REFER TO GENERAL NOTE 4 ON SHEET G-005.
2. REFER TO NOTE 1 ON SHEET G-102 FOR SUE LEVEL DEFINITIONS.
3. CONTRACTOR SHALL FIELD VERIFY MANHOLE RIM ELEVATIONS PRIOR TO FABRICATION OF MANHOLES.
4. PIPE INVERT ELEVATIONS ARE AT INSIDE EDGE OF MANHOLE.
5. PIPE LENGTHS ARE FROM INSIDE EDGE OF MANHOLE TO INSIDE EDGE OF MANHOLE.



LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH
REGISTERED ENGINEER

HANSEN ALLEN & LUCE inc
ENGINEERS

DESIGNED	TPB	3			
DRAFTED	TPB	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
PLAN & PROFILE
LIFT STATION STORM DRAIN III

SHEET: PP-303
126.42.300

FILE NAME PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\PP-303 - STORM DRAIN.DWG
FILE DATE: 3.12.2024 13:08:35 (MA)

7/04

GENERAL STRUCTURAL NOTES

GENERAL NOTES:

1. THE GENERAL CONTRACTOR AND SUB-CONTRACTORS SHALL PROVIDE SUFFICIENT SKILLED WORKMEN AND SUPERVISORS WHO SHALL BE PRESENT AT ALL TIMES DURING EXECUTION OF THE WORK. A PROJECT MANAGER, SHALL BE ASSIGNED BY THE GENERAL CONTRACTOR, AND SHALL BE RESPONSIBLE FOR THE DAILY COORDINATION OF THE PROJECT AND SHALL MAINTAIN ALL REQUIRED DRAWINGS, SPECIFICATIONS, REPORTS, AND OTHER ITEMS FOR REVIEW AT THE SITE.
2. ALL CONSTRUCTION SHALL BE ACCORDING TO THE 2018 EDITION OF THE INTERNATIONAL BUILDING CODE (IBC). AS AMENDED BY THE STATE OF UTAH.
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF AND SAFETY IN AND AROUND THE JOB SITE AND/OR ADJACENT PROPERTIES.
4. THE CONTRACTOR AND/OR OWNER SHALL KEEP LOADS ON THE STRUCTURE WITHIN THE LIMITS OF THE DESIGN LOADS BOTH DURING AND AFTER CONSTRUCTION.

DESIGN CRITERIA

1.	RISK CATEGORY:	IV
2.	IMPORTANCE FACTOR, I_s :	1.20
3.	IMPORTANCE FACTOR, I_e :	1.50
4.	WIND SPEED (3 SECOND GUST):	115 MPH;
	EXPOSURE:	"C"
5.	SEISMIC DESIGN CATEGORY:	"D"
	SITE CLASS:	"E"
	Ss :	1.55g
	Fa:	1.2
	Sds:	1.24g
	S1:	0.553g
	Fv:	1.447
	Sd1 :	0.534g
	R:	5
	Ωo:	2.5
	Cd:	3.5
6.	ROOF DEAD LOAD:	20 PSF
7.	GROUND SNOW LOAD (Pg):	28 PSF
8.	ROOF LIVE/SNOW LOAD (P_f=P_s):	24 PSF
9.	ROOF LIVE/SNOW LOAD (UNBALANCED)	34 PSF
10.	SOILS REPORT PROVIDED BY:	NINYO & MOORE (PROJECT #800051002)
	ALLOWABLE SOIL BEARING PRESSURE:	1100 PSF (UP TO 6 FT EMBEDMENT). ADD 150 PSF FOR EACH ADDITIONAL FOOT OF DEPTH UP TO 3200 PSF MAX)
	COEFFICIENT OF FRICTION (u):	0.36
	LATERAL PRESSURE FOR UNDERGROUND STRUCTURES:	58 PCF
	INCREASE FOR SATURATION:	+27 PCF
	PASSIVE PRESSURE:	3000 PCF

STRUCTURAL NOTES:

REINFORCED CONCRETE:

1. ALL CONCRETE CONSTRUCTION, INCLUDING BENDING OF BARS, SHALL COMPLY WITH ACI "BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE" (ACI 318).
2. UNLESS CALLED OUT OTHERWISE ON THE PLANS, MINIMUM REINFORCEMENT OF CONCRETE WORK SHALL BE:
   WALLS:
   8" THICK OR LESS – USE #5 @ 16" EW
   9" OR THICKER – USE #5 @ 12" EW, EF
   SLABS:
   8" THICK OR LESS – USE #4 @ 16" EW
3. ALL WALL REINFORCEMENT AT CORNERS OR JUNCTIONS OF WALLS SHALL BE CONTINUOUS, LAPPED, OR TERMINATED IN A STANDARD 90 DEGREE HOOK. LAP SPLICES SHALL CONFORM WITH NOTE 6.
4. UNLESS SHOWN OTHERWISE ALL BARS SHALL BE DOWELED. DOWELS SHALL BE THE SAME SIZE AND SPACING AS THE REINFORCEMENT WHICH IS TO BE SPLICED TO THE DOWELS.
5. ALL REINFORCING BARS SHALL BE GRADE 60 AND SHALL CONFORM TO ASTM A-615, CURRENT REVISION. REINFORCING STEEL SHALL BE NEW AND FREE FROM RUST, OIL OR OTHER BOND INHIBITOR.
6. ALL CONTINUOUS REINFORCING BARS SHALL LAP AT LEAST 40 BAR DIAMETERS. SPLICES SHALL BE MADE AWAY FROM POINTS OF MAXIMUM STRESS. MINIMUM LAP SHALL BE 18 IN.
7. CONCRETE COVER OVER REINFORCEMENT SHALL BE AS FOLLOWS:
   7.1. SURFACE NOT EXPOSED DIRECTLY TO THE GROUND, WATER OR WEATHER AFTER FORM REMOVAL:
   CONCRETE SLABS IN BUILDINGS – – – – – 3/4"
   7.2. CONCRETE SLABS IN WATER BEARING SURFACES EXPOSED DIRECTLY TO THE GORUND, WATER OR WEATHER AFTER FORM REMOVAL:
   FOR #5 BARS OR SMALLER– – – – – 1-1/2"
   FOR #6 BARS OR LARGER– – – – 2"
   7.3. CONCRETE PLACED DIRECTLY AGAINST GROUND – – – – 3"
   7.4. REINFORCEMENT SHALL BE PLACED WITHIN A TOLERANCE OF ±1/4" OF POSITION SPECIFIED.
8. CONCRETE CURING SHALL BE IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. SOME CONCRETE WORK REQUIRES WATER CURING, AS MEMBRANE CURING IS NOT ALLOWED. THE CONTRACTOR IS WARNED THAT WATER CURING IS DIFFICULT AT TIMES DUE TO WIND AND DRY CONDITIONS. THE CONTRACTOR SHALL STUDY REQUIREMENTS AND SHALL FURNISH ADEQUATE SYSTEMS TO PROVIDE WATER CURING WHERE REQUIRED. TOP OF WALLS SHALL BE KEPT VISIBLY MOIST AT ALL TIMES AND SHALL BE FLOODED NOT LESS THAN THREE TIMES DAILY.
   A. FOR POURING CONCRETE DURING COLD WEATHER:
      1. FOLLOW RECOMMENDATIONS CONTAINED IN PUBLICATION ACI 306R "COLD-WEATHER CONCRETING," CURRENT REVISION.
      2. PROTECT CONCRETE WORK FROM PHYSICAL DAMAGE OR REDUCED STRENGTH WHICH COULD BE CAUSED BY FROST, FREEZING ACTIONS OR LOW TEMPERATURES.
   WHEN AIR TEMPERATURE HAS FALLEN TO OR IS EXPECTED TO FALL BELOW 40°F OR 4°C, UNIFORMLY HEAT WATER AND AGGREGATES BEFORE MIXING TO OBTAIN A CONCRETE MIXTURE TEMPERATURE OF NOT LESS THAN 50°F OR 10°C, AND NOT MORE THAN 80°F OR 27°C AT TIME OF PLACEMENT.
   CONCRETE SHALL BE AIR ENTRAINED WITH AIR CONTENT OF 6% +/- 1% BY VOLUME.

REINFORCED CONCRETE CONT.

   4. CONCRETE SHALL BE AIR ENTRAINED WITH AIR CONTENT OF 6% +/- 1% BY VOLUME.
   5. DO NOT USE FROZEN MATERIALS OR MATERIALS CONTAINING ICE OR SNOW. DO NOT PLACE CONCRETE ON FROZEN SUBGRADE OR ON SUBGRADE CONTAINING FROZEN MATERIALS.
   6. DO NOT USE CALCIUM CHLORIDE, SALT OR OTHER MATERIALS CONTAINING ANTIFREEZE AGENTS OR CHEMICAL ACCELERATORS, UNLESS OTHERWISE APPROVED IN THE MIX DESIGN.
   7. COVER AND HEAT CONCRETE FOR A MINIMUM OF 7 DAYS AS RECOMMENDED BY ACI 306R, CURRENT REVISION.

B. FOR POURING CONCRETE DURING HOT WEATHER:
   FOLLOW RECOMMENDATIONS CONTAINED IN PUBLICATION ACI 305R "HOT-WEATHER CONCRETING," CURRENT REVISION.
   PROTECT CONCRETE FROM FLASH CURING BY PROVIDING A WATER/MOISTURE CURE FOR 3 DAYS.
   A 4500 PSI (WITH A 6-1/2 BAG MIX) IS RECOMMENDED FOR THESE CONDITIONS.

9. NO BACKFILL SHALL BE PLACED AGAINST WALLS UNTIL CONCRETE HAS REACHED 85 PERCENT OF THE SPECIFIED STRENGTH AND THE CONNECTING SLABS AND BEAMS HAVE BEEN CAST AND HAVE REACHED 85 PERCENT OF THE SPECIFIED STRENGTH.
10. CONCRETE TO HAVE A MIN 28 DAY STRENGTH OF 4000 PSI, EXCEPT IN AREAS THAT COME IN CONTACT WITH SEWAGE/CHEMICALS. THOSE AREAS TO HAVE MIN 28 DAY STRENGTH OF 4500 PSI.

MASONRY WALL REINFORCING NOTES:

1. WALL REINFORCEMENT SHALL BE PLACED AND GROUTED AS DESCRIBED IN THE SPECIFICATIONS AND SHALL CONFORM TO IBC REQUIREMENTS.
2. ALL WALLS SHALL BE REINFORCED WITH A MINIMUM OF (1) #5 VERTICAL REINFORCING GROUTED PER WALL SECTIONS AND (1) #5 @ 48" OC HORIZONTAL BOND BEAM. SEE WALL ELEVATION OR NOTE 5 FOR ADDITIONAL VERTICAL REINFORCEMENT ADJACENT TO WALL OPENINGS. WALLS TO BE PARTIALLY GROUTED.
3. ALL VERTICAL REINFORCING SHALL EXTEND TO ROOF LEVEL AND SHALL BE DOWELED TO THE FOOTING WITH MATCHING DOWELS.
4. ALL DOWELS SHALL LAP WALL REINFORCING 48 DIA AND EXTEND INTO FOUNDATION A MINIMUM OF 40 DIA OR EXTEND 12 DIA PLUS HAVE A STANDARD HOOK.
5. A #5 VERTICAL BAR SHALL BE PLACED AND GROUTED AT ALL WALL CORNERS AND WALL INTERSECTIONS AND TWO #5 VERTICAL BARS SHALL BE PLACED AT JAMBS OF WALL OPENINGS AND SUCH BARS SHALL EXTEND THE FULL HEIGHT OF WALL AND BE ANCHORED IN THE ROOF BOND BEAM AND FOOTING AS SPECIFIED IN PARAGRAPH ABOVE.
6. LINTELS FOR ALL OPENINGS SHALL BE AS PER DETAILS. "TYPICAL WALL DETAILS", UNLESS OTHERWISE NOTED.
7. ALL HORIZONTAL AND VERTICAL JOINTS ON MASONRY UNITS SHALL BE CONCAVE ON BOTH FACES UNLESS SHOWN OR SPECIFIED OTHERWISE.
8. MASONRY CONTROL JOINTS IN WALLS SHALL BE INSTALLED AT 24'-0"± SPACING UNLESS SHOWN OTHERWISE.
9. EXTERIOR WALL CELLS SHALL BE PARTIALLY GROUTED. EXTERIOR WALL CELLS NOT FILLED WITH GROUT SHALL BE FILLED WITH INSULATION.
10. ALL REINFORCING BARS SHALL BE GRADE 60, AND SHALL CONFORM WITH: "SPECIFICATIONS FOR DEFORMED BILLET-STEEL BARS FOR CONCRETE REINFORCEMENT", ASTM A-615. REINFORCING BARS SHALL BE NEW, FREE FROM RUST, OIL OR OTHER BOND INHIBITOR. WELDABLE REBAR TO BE ASTM A-706.
11. COLD WEATHER PLACEMENT OF MASONRY: IF THE LOW TEMPERATURE FOR ANY 24-HOUR PERIOD FOR THE FIRST SEVEN DAYS AFTER THE MASONRY IS PLACED OR GROUTED DROPS BELOW 40°F BUT REMAINS ABOVE 28°F, COVER MASONRY WITH INSULATED BLANKETS. IF THE TEMPERATURE DROPS BELOW 28°F FOR ANY PERIOD AS DESCRIBED ABOVE, APPLY HEAT AND INSULATED BLANKETS AND MAINTAIN A TEMPERATURE AT OR ABOVE 34°F FOR SEVEN DAYS.
12. PROVIDE (2) #5 @ TOP OF WALLS (TYP)
13. ALL MASONRY TO HAVE SPECIAL INSPECTION PER TABLE 1704.5.1 OF IBC.
14. ALL TERMINAL BARS TO HAVE HOOK @ END.

WELDING

1. WELDS SHALL CONFORM TO AMERICAN WELDING SOCIETY (AWS), LATEST EDITION:
   D1.1, STRUCTURAL WELDING CODE – STEEL
   D1.2, STRUCTURAL WELDING CODE – ALUMINUM
   D1.3, STRUCTURAL WELDING CODE – SHEET STEEL
   D1.4, STRUCTURAL WELDING CODE – REINFORCING STEEL
   D1.6, STRUCTURAL WELDING CODE – STAINLESS STEEL
2. REPAIR WELDS FOUND DEFECTIVE IN ACCORDANCE WITH AWS D1.1, SEC 5.26.
3. USE INTERMITTENT WELDS AT FIELD WELDS OF EMBED PLATES AND ANGLES TO AVOID SPALLING OR CRACKING OF THE EXISTING CONCRETE.

WOOD FRAMING NOTES

1. FRAMING LUMBER: DOUGLAS FIR LARCH (SURFACED DRY NOT TO EXCEED 19% MAXIMUM MOISTURE CONTENT), CONFORMING TO NATIONAL DESIGN SPECIFICATIONS (NDS) SUPPLEMENTS FOR WOOD DESIGN VALUES AND APPLICABLE STANDARDS IN THE FOLLOWING GRADES:
   A. SILLS: REDWOOD, OR PRESSURE TREATED, FOUNDATION GRADE.
   B. PLATES @ TOP OF MASONRY WALLS: DOUGLAS FIR-LARCH, NO. 1, FB=1000 PSI MIN
   C. STUDS: DOUGLAS FIR-LARCH, OR HEMLOCK-FIR, STUD GRADE.
   D. BEAMS, JOISTS, LEDGERS, POSTS & HEADERS: DOUGLAS FIR-LARCH, NO. 2 MIN, 900 PSI MIN
   E. ALL OTHER HORIZONTAL FRAMING MEMBERS: DOUGLAS FIR-LARCH, CONSTRUCTION GRADE.
   F. ALL OTHER VERTICAL FRAMING MEMBERS: DOUGLAS FIR-LARCH, STANDARD OR BETTER GRADE.
   G. SHEATHING: STANDARD EXTERIOR GRADE WITH EXTERIOR GLUE. APA RATED.
   H. GLUE-LAM BEAMS: OUGLAS FIR-LARCH, 2400 PSI WITH AITC STAMP FOR QUALITY
2. PROVIDE SOLID BLOCKING AT LEAST 1-1/2" THICK AT ENDS AND AT EACH SUPPORT OF JOIST. PROVIDE APPROVED BRIDGING AT A MAXIMUM 8'-0" OC BETWEEN SUPPORTS.
3. NAILING SHALL CONFORM TO STANDARD NAILING SCHEDULE 2304.10.1 OF INTERNATIONAL BUILDING CODE UNLESS NOTED OTHERWISE ON PLANS OR SCHEDULES. ALL NAILS SHALL BE COMMON NAILS.

WOOD FRAMING NOTES CONT.

USE SIMPSON STRONG TIE (SST) HANGERS FOR ALL FLUSH CONNECTIONS. USE STRONGEST HANGER COMPATIBLE WITH MEMBER SIZE AND NAIL PER MANUFACTURER'S SPECIFICATION TO OBTAIN MAXIMUM LOAD CARRYING CAPACITY.

ALL METAL HANGERS AND CONNECTORS SHALL BE "SIMPSON" OR EQUAL.

SECURE SILL PLATE TO CONCRETE WITH 5/8" DIA X 12" AB @ 8" OC UNLESS NOTED OTHERWISE ON PLAN.

DOUBLE TOP AND BOTTOM PLATES TO BE LAPPED 4'-0" AT SPLICE AND CONNECT WITH 16D COMMON NAILS @ 3" OC, STAGGERED.

NOTCHING OR DRILLING THROUGH ANY LUMBER MEMBER WILL NOT BE ALLOWED WITHOUT SPECIFIC APPROVAL OF STRUCTURAL ENGINEER.

ROOF SHEATHING:
A. (5/8)" A.P.A. RATED STRUCTURAL II, EXTERIOR, PANEL INDEX #32/16, UNLESS NOTED OTHERWISE
B. NAIL WITH: 10D @ 6" OC – PANEL EDGES, UNLESS NOTED OTHERWISE
   10D @ 12" OC – ALL ELSE, UNLESS NOTED OTHERWISE
C. INSTALL ROOF SHEATHING WITH "H" CLIPS.

10. KEEP ALL MATERIAL CLEARLY IDENTIFIED WITH ALL GRADE MARKS LEGIBLE. KEEP ALL DAMAGED MATERIAL CLEARLY IDENTIFIED AS DAMAGED AND SEPARATELY STORED TO PREVENT ITS INADVERTENT USE. IN THE EVENT OF DAMAGE, IMMEDIATELY MAKE ALL REPAIRS AND REPLACEMENTS NECESSARY TO THE APPROVAL OF THE ENGINEER AND AT NO ADDITIONAL COST TO THE OWNER.
11. PROVIDE 3"X3"X1/4" SLOTTED PLATE WASHERS AT ALL BOLTS IN PLATES, AND 2" DIAMETER PLATE WASHERS AT ALL BOLTS IN LEDGERS, BEAMS, AND COLUMNS. UNLESS OTHERWISE SPECIFIED, USE A307 BOLTS.
12. PROVIDE SOLID BLOCKING UNDER ALL LOCATIONS WHERE CONCENTRATED LOADS ARE LOCATED, SUCH AS COLUMNS, POSTS, BEAMS, ETC. FULL SUPPORT MUST BE PROVIDED TO THE FOUNDATION.

WOOD TRUSSES NOTES

1. DESIGN TRUSSES FOR FOLLOWING CRITERIA:
   DEAD LOAD = 20 PSF
   LIVE LOAD = 24 PSF (BALANCED SNOW)
   LIVE LOAD DEFLECTION = L/480 MAXIMUM

   NOTE: ALL TRUSSES TO BE DESIGNED FOR UNBALANCED AND DRIFT LOADS PER ASCE-7. TRUSSES IN STORAGE AREA TO BE DESIGNED TO MEET ALL EQUIPMENT LOADS AND RISK CATEGORY IV.
2. PROVIDE BRIDGING AT TOP AND BOTTOM CHORDS AND STRUT BRACING, PER MANUFACTURER'S RECOMMENDATIONS.
3. NO STRESS INCREASE ALLOWED FOR TRUSS DESIGN.
4. DESIGN AND FABRICATION OF ALL TRUSSES SHALL COMPLY WITH REQUIREMENTS OF DESIGN SPECIFICATIONS FOR LIGHT METAL PLATE CONNECTED WOOD TRUSSES' BY THE TRUSS PLATE INSTITUTE.
5. TRUSS MANUFACTURER SHALL DESIGN AND FABRICATE TRUSSES TO SUPPORT LOADS SHOWN ON DRAWINGS. COORDINATE DESIGN WITH ALL MECHANICAL EQUIPMENT AND SUSPENDED LOADS. SUBMIT DESIGN CALCULATIONS BEARING STAMP OF A REGISTERED PROFESSIONAL ENGINEER LICENSED BY THE STATE OF UTAH.
6. SUBMIT SHOP DRAWINGS FOR REVIEW PRIOR TO FABRICATION INDICATING, FRAMING PLAN, BRIDGING AND BRACING, DIAGRAM OF THE TRUSSES WITH DIMENSIONS, SIZE AND GRADE OF MEMBERS, SIZE AND LOCATION OF METAL PLATES, BEARING DETAILS AND INSTRUCTION FOR INSTALLATION.
7. MOMENT COEFFICIENTS SHALL BE 1/8 FOR ONE AND TWO CONTINUOUS SPAN CONDITIONS AND 1/10 FOR THREE OR MORE CONTINUOUS SPAN CONDITIONS. LENGTH FACTOR FOR WEB DESIGN SHALL BE ONE. METAL PLATES AT COMPRESSION JOINTS SHALL BE DESIGNED FOR THE FULL LOAD WITHOUT CONSIDERING WOOD TO WOOD BEARING.
8. ALL METAL PLATE DIMENSIONS SHALL BE INCREASED BY 10% ABOVE THAT REQUIRED BY THE ANALYSIS. ALLOWABLE STRESS FOR METAL PLATE SHALL NOT BE INCREASED FOR THE LOAD DURATION. METAL PLATES SHALL BE PRESSED OR ROLLED INTO MEMBERS TO OBTAIN FULL PENETRATION WITHOUT CRUSHING THE WOOD SURFACE.
9. ALL METAL PLATES SHALL BE GALVANIZED STEEL AND SHALL BE ON BOTH SIDES OF EACH CONNECTION. SUBMIT A COPY OF THE I.C.B.O. APPROVAL, INCLUDING ALLOWABLE STRESSES ESTABLISHED BY THIS COMMITTEE, FOR METAL PLATES USED.
10. ALL LUMBER SHALL BE DOUGLAS FIR OR YELLOW PINE #1 GRADE. MOISTURE CONTENT SHALL NOT EXCEED 19% NOR SHALL BE LESS THAN 7%. HANDLING, STORAGE AND INSTALLATION OF ALL TRUSSES SHALL BE DONE SUCH THAT THE SPECIFIED MINIMUM AND MAXIMUM MOISTURE CONTENT LIMITS ARE NOT EXCEEDED. GRADE STAMPS SHALL APPEAR ON ALL MEMBERS.
11. PRIOR TO FABRICATION, CONTRACTOR SHALL SUBMIT IN WRITING PROOF OF COMPLIANCE OF IN PLANT INSPECTION BY AN I.C.B.O. APPROVED INDEPENDENT INSPECTION AGENCY. SUBMIT SHOP DRAWINGS FOR TRUSS LAYOUT & DESIGN.
12. A HURRICANE TIE IS TO BE INSTALLED AT EACH TRUSS TO DOUBLE TOP PLATE LOCATION OR AS REQUIRED ON PLANS.
13. TRUSS MANUFACTURER IS RESPONSIBLE FOR ALL TRUSS HANGERS.

SUBMITTALS:

1. THE FOLLOWING INFORMATION AND SUBMITTALS SHALL BE PROVIDED TO THE CONSTRUCTION MANAGER (CM) BEFORE FABRICATION AND/OR DELIVERY TO THE JOBSITE, NOT ALL MAY APPLY.
   A. CONCRETE MIX DESIGNS.
   B. CONCRETE REINFORCEMENT SHOP DRAWINGS.
   C. MASONRY SPECIFICATIONS.
   D. MASONRY MORTAR MIX DESIGNS.
   E. MASONRY REINFORCEMENT SHOP DRAWINGS.
   F. STRUCTURAL BACKFILL PIT LOCATION AND MATERIAL SPECIFICATION, IF USED ON SITE.
   G. STRUCTURAL STEEL SHOP DRAWINGS.
   H. OPEN WEB ROOF TRUSSES, SHOP DRAWINGS FROM MANUFACTURER.
   I. OTHER SHOP DRAWINGS & SUBMITTALS AS DEEMED NECESSARY BY THE CONSTRUCTION MANAGER.
   J. SPECIAL INSPECTION PER SHEET S-101.

SOIL NOTES

1. SOILS REPORT WAS PREPARED FOR THE SITE BY NINYO & MOORE (PROJECT #800051002). ALL RECOMMENDATIONS CONTAINED IN THE REPORT SUPERCEDE ALL NOTES IN DRAWINGS.
2. ALL ORGANIC MATERIALS, RUBBISH, UNSUITABLE FILL, TOPSOIL, ETC. SHALL BE REMOVED FROM BENEATH LOCATIONS OF PROPOSED FOOTINGS, CONCRETE SLABS AND ASPHALT PAVING. THE GEOTECHNICAL REPORT INDICATES THAT UP TO 8 FEET OF FILL MAY NEED TO BE REMOVED AND REPLACED. REFER TO FOUNDATION SPECIAL INSPECTIONS ON S-101.
3. SLABS SHALL BE PLACED ON COMPACTED GRANULAR BACKFILL COMPACTED PER GEOTECHNICAL REPORT.
4. UNLESS OTHERWISE NOTED, STRUCTURAL BACKFILL SHALL CONFORM TO:
   A. IMPORTED GRANULAR MATERIAL SHALL BE FREE OF ORGANIC MATTER AND OTHER DELETERIOUS SUBSTANCES.
   B. SHALL COMPLY WITH SPECIFICATIONS FOR GRADATIONS.
5. ALL FREE WATER SHALL BE REMOVED FROM THE FOUNDATION EXCAVATION PRIOR TO PLACING CONCRETE.
6. EXTERIOR FOOTINGS AND GRADE BEAMS SHALL BE LOCATED AT LEAST 30" BELOW FINISHED GRADE, AND MAINTAIN 6" BETWEEN FINISH GRADE AND WOOD FRAMING.
7. CONTRACTOR SHALL REMOVE ALL UNSUITABLE FILL FROM UNDER ALL CONCRETE FLATWORK, PAVEMENT, BUILDINGS AND STRUCTURES, ACCORDING TO THE GEOTECHNICAL REPORT AND REPLACE WITH STRUCTURAL FILL COMPACTED TO 95% MAX DRY DENSITY PER ASTM D-1557 OR AS PER GEOTECHNICAL REPORT.

ANCHOR NOTES:

1. ALL ANCHORS TO BE INSTALLED PER THE MANUFACTURER'S REQUIREMENTS. FOR BOTH MECHANICAL AND EPOXY TYPE ANCHORS THESE REQUIREMENTS INCLUDE, BUT IS NOT LIMITED TO:
   A. PROPER HOLE DIAMETER, DEPTH, EDGE DISTANCES, AND SPACING.
   B. PROPER HOLE PREPARATION AND CLEANOUT
   C. WEATHER REQUIREMENTS TO BE FOLLOWED, ESPECIALLY FOR COLD WEATHER APPLICATIONS.
   D. ALL STRUCTURAL ANCHORS TO COMPLY WITH THE CRACKED CONCRETE REQUIREMENTS ON THE CURRENT EDITION OF THE ACI 318.
2. ANY EPOXY TYPE ANCHOR IS TO MEET THE CURRENT ANSI/NSF 61 REQUIREMENTS FOR DRINKING WATER SYSTEM COMPONENTS, WHERE APPLICABLE.

SEISMIC BRACKETS:

1. CONTRACTOR TO SUBMIT FOR REVIEW AND APPROVAL SEISMIC BRACKETS FOR HVAC, MECHANICAL AND ELECTRICAL EQUIPMENT TO MEET LOCAL CODES.

STRUCTURAL STEEL AND METAL FABRICATIONS:

1. ALL STRUCTURAL STEEL AND STRUCTURAL STEEL WORK SHALL COMPLY WITH "SPECIFICATIONS FOR THE DESIGN, FABRICATION AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS OF THE AISC" AND THE "AISC CODE OF STANDARD PRACTICE."
2. STRUCTURAL STEEL SHALL CONFORM TO THE FOLLOWING:

W-SHAPES	A992
MISCELLANEOUS SHAPES INCLUDING ANGLES, CHANNELS, PLATES, ETC.	A36
SQUARE OR RECTANGULAR STEEL	A500, GRADE B
TUBING STEEL PIPE	CLASS 53, GRADE B

3. STRUCTURAL STEEL SHALL BE FABRICATED AND ERRECTED IN CONFORMANCE WITH THE AISC MANUAL OF STEEL CONSTRUCTION, CURRENT EDITION, AND CURRENT OSHA STANDARDS.
4. ALL WELDS AND WELDING SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS OF "THE AMERICAN WELDING SOCIETY, USING ELECTRODES AS SPECIFIED THEREIN." WELDS TO BE MADE WITH E – 70XX ELECTRODES UNO.
5. BOLTS SHALL BE HIGH STRENGTH BOLTS CONFORMING TO THE FOLLOWING, EXCEPT WHERE SPECIFICALLY INDICATED OTHERWISE:

UNLESS SHOWN OTHERWISE	A325-N
SLIP CRITICAL	A325-SC
ANCHOR BOLTS (AB)	
STAINLESS STEEL	F593, AISI TYPE 316, CONDITION CW
STEEL	F1554, GR 36
GALVANIZED STEEL	F1554, GR 36/A153
MACHINE BOLTS (MB)	A307

6. USE A307 BOLTS WITH PLATE WASHERS, UNLESS OTHERWISE SPECIFIED, FOR TYPICAL CONNECTIONS AND CONNECTIONS TO CONCRETE.
7. USE A325 BOLTS WITH PLATE WASHERS, UNLESS OTHERWISE SPECIFIED, FOR STEEL TO STEEL CONNECTIONS.
8. ITEMS TO EMBEDDED IN CONCRETE SHALL BE CLEAN AND FREE OF OIL, DIRT AND PAINT.
9. NO HOLES OTHER THAN THOSE SPECIFICALLY DETAILED SHALL BE ALLOWED THROUGH STRUCTURAL STEEL MEMBERS. NO CUTTING OR BURNING OF STRUCTURAL STEEL IS PERMITTED WITHOUT THE APPROVAL OF THE ENGINEER.
10. METAL FLASHING SHALL BE HOT DIP GALVANIZED, OR HAVE OTHER APPROVED EQUAL CORROSION RESISTANCE.
11. MATERIAL SHALL COMPLY WITH THE FOLLOWING STANDARDS U.N.O.

TYPICAL BOLTS	ASTM A-307 GRADE A
HIGH STRENGTH BOLTS	ASTM A-325
ANCHOR BOLTS	ASTM A-307 GRADE A
NUTS FOR ANCHOR BOLTS	ASTM A-563 GRADE A
STEEL TUBES	ASTM A-500 GRADE B WITH YIELD STRENGTH EQUAL TO 46 KSI
STEEL PIPES	ASTM A-53 GRADE B TYPE E OR S DEFORMED BAR
ANCHORS	MANUFACTURED BY NELSON STUD CO. OR EQUAL
HEADED STUD ANCHORS	ASTM A-108 MANUFACTURED BY NELSON STUD CO. OR EQUAL
ALL OTHER STEEL SHAPES	ASTM A-36 WITH YIELD STRENGTH EQUAL TO 36 KSI.

PROFESSIONAL STRUCTURAL ENGINEER — No. 2774619 — ROBERT C. CONDER — 4/18/2024 — STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER — 4/19/24 — No. 5052482 — GREGORY S. TWELVES — STATE OF UTAH

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\S-100 GENERAL STRUCTURAL NOTES.DWG
FILE DATE: 4/2/2024 14:28:41 (MAJ)

HANSEN ALLEN & LUCE inc ENGINEERS	DESIGNED ACS	3					SCALE: NONE
	DRAFTED MAJ	2					SOUTH SALT LAKE
	CHECKED GST	1					DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION STRUCTURAL GENERAL STRUCTURAL NOTES
	DATE APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.	SHEET S-100
							126.42.300

7/04

SPECIAL INSPECTIONS

SCHEDULE OF SPECIAL INSPECTIONS APPLICABLE TO THIS PROJECT

MATERIAL/ACTIVITY	TYPE OF INSPECTION	C/P *	EXTENT/REFERENCE	INSP INITIALS	INSP DATE
GENERAL					
Pre-construction conference	Meeting with Owner, Contractor and Registered Design Professional to discuss Special Inspection procedures	P	Scheduled by DCRA with the Contractor prior to commencement of work		
EARTHWORK					
Site preparation (building)	Field testing and inspection	P	Field Review; IBC 1705.6		
Fill material (building)	Review submittals, field testing and inspection	P	Field Review; IBC 1705.6		
Fill compaction (building)	In-place density tests, lift thickness	C	Field Review; IBC 1705.6		
Excavation	Field inspection and verification of proper depth	P	Field Review; IBC 1705.6		
Foundation sub-grade	Field inspection of foundation subgrade prior to placement of concrete	P	Field Review; IBC 1705.6		
MASONRY (Level__; Building Risk Category) TYPICAL FOR LEVEL B AND RISK CATEGORY I,II,III					
Materials	Review of products supplied versus certificate of compliance and material submitted	P	Submittal & Field Review; ACI 530/ASCE 5; ACI 530.1/ASCE 6; IBC 1705.4, 1708		
Strength	Testing/review of strength	C	Submittal & Field Review; ACI 530/ASCE 5; ACI 530.1/ASCE 6; IBC 1705.4, 2105.2.2, 2105.3		
Mortar and Grout	Inspection of proportioning and mixing. Placement of mortar only.	C	Field Review; IBC 1705.4; ACI 530/ASCE 5; ACI 530.1/ASCE 6		
Grout placement, including pre-stressing grout	Verification to ensure compliance	C	Field Review; IBC 1705.4; ACI 530/ASCE 5; ACI 530.1/ASCE 6		
Grout space	Verification to ensure compliance	P	Field Review; IBC 1705.4; ACI 530/ASCE 5;ACI 530.1/ASCE 6; TMS 602		
Mortar, grout, and prism specimens	Observe Preparation	C	Field Review; IBC 1704.5, ACI 530.1; ASCE 6;		
Reinforcement, pre-stressing tendons, and connections	Inspect condition, size, location, and spacing	P	Field Review; IBC 1704.5; ACI 530/ASCE 5; ACI 530.1/ASCE 6		
Welding of reinforcing bars	Inspection and testing of welds	C	Field Review; IBC 1705.4; ACI 530/ASCE 5;ACI 530.1/ ASCE 6		
Pre-stressing force	Verify application and measurement	C	Field Review; IBC 1705.4; ACI 530/ASCE 5; ACI 530.1/ASCE 6		
Protection	Inspect procedures for protection during cold and hot weather	P	Field Review; IBC 1705.4,; ACI 530/ASCE 5; ACI 530.1/ASCE 6		
Anchorage	Inspection of anchorages	P	Field Review; ACI 530.1/ASCE 6, ASCE 6; IBC 1705.4; ACI 530/ASCE 5		
Masonry installation	Inspection of placement of masonry and joints (Periodic after the first 5000sq.ft)	C	Field Review; ACI 530/ASCE 5; ACI 530.1/ASCE 6; IBC 1705.4		
Grouting of pre-stressed tendons	Field inspection	C	Field Review; ACI 318: 18.18.4; IBC 1705.3		
Application of forces for pre-stressed concrete	Field inspection	C	Field Review; ACI 318: 18.20; IBC 1705.3		
CONCRETE					
Materials	Review product supplied versus certificates of compliance and mix design	P	Submittal & Field Review; IBC 1705.3; ACI 318: Ch. 4 and 5; IBC 1904.2, 1910.2, 1903.3		
Installation of reinforcing steel, including Pre-stressed tendons and anchor bolts as well as welding	Field inspection of placement	P	Submittal and Field Review; ACI 318:3.5, 3.5.2 3.8.6 & Ch. 7 8.1.3 and 21.2.8; AWS D1.4; IBC 1705.3, 1908.5, 1909.1, 1910.4		
Formwork installation	Field inspection	P	Field Review; ACI 318: 6.1.1; IBC 1705.3		
Concreting operations and placement	Field inspection of placement/sampling	C	Field Review; ACI 318: 5.6, 5.8, 5.9-10; ASTM C 172, C 31; IBC 1705.3, 1910.6, 1910.7, 1910.8, 1910.10		
Concrete curing	Field inspection of curing process	P	Field Review; ACI 318: 5.11-13; IBC 1705.3, 1910.9		
Concrete strength	Evaluation of concrete strength		Laboratory Testing; ACI 318: 6.2; IBC 1705.3		

SCHEDULE OF SPECIAL INSPECTIONS APPLICABLE TO THIS PROJECT

MATERIAL/ACTIVITY	TYPE OF INSPECTION	C/P *	EXTENT/REFERENCE	INSP INITIALS	INSP DATE
PRECAST CONCRETE					
Verify fabrication/QC procedures In-plant	Inspection of plant and QC procedures**		Submittal or Field Review; IBC 1705.3		
Erection and installation	Review submittals and as-built assemblies; Field inspection of in-place precast		Submittal and Field Review; ACI 318; Ch. 16; IBC Table 1705.3		
WOOD					
Verify fabrication/QC procedures	In-plant inspection of fabrication/quality control procedures** or submit Certificate of Compliance	P	Submittal or Field Review; IBC 1704.2.5, 1705.5, 1705.5.2		
Metal plate connected wood/metal trusses spanning 60' or more	Review approved submittal and installation of restraint/bracing	P	Field Review; IBC 1704.2.5, 1705.5, 1705.2		
Joist Hangers – Materials/Installation	Review manufacturer's material and test standards	P	Field Review; IBC 1711, ASTM D 1761		
High-Load Diaphragms – Installation	Review submittal and as-built assemblies; inspection of sheathing, framing size, nail and staple diameter and length, number of fastener lines, and fastener spacing.	C	IBC 1705.5, 1705.5.1		
Wood Shear Walls–installation	Review nailing, bolting, anchoring, fastening, Diaphragms, struts, braces, and hold downs when fasteners are <4" on center.	P	Field Review; IBC1705.10.1		

NOTES:

1. THE SPECIAL INSPECTOR IS RESPONSIBLE FOR ENSURING THE PUBLICATIONS USED FOR INSPECTION CRITERIA ARE THE MOST CURRENT AND UP TO DATE.
2. FAILURE OF INSPECTABLE AREAS ARE TO BE NOTED AND SUBMITTED TO OWNER, ENGINEER OF RECORD, AND GENERAL CONTRACTOR IF CORRETIONS REQUIRE A FOLLOW UP INSPECTION AND CANNOT BE MADE COMPLETED "ON THE SPOT".
3. DOCUMENTATION FOR INSPECTIONS MUST BE COMPLETED AND SUBMITTED IN ACCORDANCE WITH CONTRACT REQUIREMENTS, INTERNATIONAL BUILDING CODE (LATEST EDITION), AND "MANUAL FOR SPECIAL INSPECTIONS" (LATEST EDITION), OR AS AGREED UPON WITH OWNER, ENGINEER OF RECORD, AND CONTRACTOR.
4. SPECIAL INSPECTION DOES NOT INCLUDE OR WAIVE THE RESPONSBILITY FOR ANY REQUIRED INSPECTIONS BY THE BUILDING OFFICIAL. CONTRACTOR IS RESPONSIBLE FOR SCHEDULING BOTH INSPECTIONS.
5. SPECIFIED CONCRETE AND MASONRY TESTING DURING CONSTRUCTION WILL BE CONTRACTOR FURNISHED. SPECIFIED LAB TEST, MIXES, AND SIMILAR TESTING TO VERIFY MATERIAL QUALITY AND CONFORMANCE TO THE SPECIFICATIONS, REQUIRING SUBMITTAL FOR REVIEW AND ACCEPTANCE, SHALL BE THE RESPONSIBLITY OF CONTRACTOR.
6. STRUCTURAL OBSERVATIONS (OWNER FURNISHED) ARE REQUIRED IN ACCORDANCE WITH IBC SECTION 110 AND CHAPTER 17 AS INDICATED IN THE STATEMENT OF SPECIAL INSPECTION.
7. SPECIAL INSPECTOR TO BE PROVIDED BY OWNER.

P = PERIODIC INSPECTION
C = CONTINUOUS INSPECTION

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE inc
ENGINEERS

DESIGNED	ACS	3					
DRAFTED	MAJ	2					
CHECKED	GST	1					
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.	

SCALE: NONE


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCUTRAL
SPECIAL INSPECTIONS

SHEET S-101

126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-101 SPECIAL INSPECTIONS.DWG
FILE DATE: 3.6.2024 14:29:55 (MAJ)
7/04



PLAN

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-102 PUMPHOUSE FOUNDATION SLAB PLAN.DWG
FILE DATE: 3.6.2024 14:31:07 (MAJ)

7/04

HANSEN ALLEN & LUCE inc ENGINEERS

LICENSED PROFESSIONAL ENGINEER 4/19/24 No. 5052482 GREGORY S. THOMAS STATE OF UTAH

DESIGNED ACS	3					
DRAFTED MAJ	2					
CHECKED GST	1					
DATE APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.	

SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
PUMPHOUSE FOUNDATION SLAB PLAN

SHEET S-102
126.42.300

PROFESSIONAL STRUCTURAL ENGINEER No. 2774619 ROBERT C. CONDER 4/18/2024 STATE OF UTAH

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-103 PUMPHOUSE FOUNDATION WALL PLAN.DWG
FILE DATE: 4.15.2024 16:40:50 (MAJ)

46'-0"

1'-2" 10" 1'-2"

2 S-107

N

0 2 4
SCALE IN FEET

4'-2" 1'-2" 2"

(3) #6 VERT BARS (I.F.) AND (2) #5 VERT BARS (O.F.) EACH SIDE OF WALL PENETRATION. PROVIDE (4) #4 DIAGONAL BARS (5'-0" LONG) AT EDGES OF PIPE, EACH FACE. TYPICAL FOR ALL WALL PENETRATIONS UP TO 14" IN DRY WELL

14" DIP PIPE

1'-2" THICK WALL (DRY WELL) WITH #6 VERT BAR @ 6" OC (I.F.), #5 VERT BAR @ 12" OC (O.F.) AND #5 HORIZ BAR @ 12" OC (BOTH FACES)

1'-2" THICK WALL (DRY WELL) WITH #6 VERT BAR @ 6" OC (I.F.), #5 VERT BAR @ 12" OC (O.F.) AND #5 HORIZ BAR @ 12" OC (BOTH FACES)

(4) 2'-8"x10" CONCRETE PUMP STAND WALLS (SEE SECTION 1/S-106)

4'-7" 2'-4" 2'-0" 2'-4" 2'-0" 2'-4" 2'-0" 2'-4" 1'-10 1/4"

10" TYP

10'-11 1/2"

CANTILEVERED CONCRETE STAIRS

A S-504

2'-8"

1'-4"

23'-4"

1 S-106

19'-2"

3'-0"

(8) 3'-0"x10" CONCRETE PUMP STAND WALLS (SEE SECTION 1/S-106)

1'-7 1/2" 1'-10 1/2" 1'-10 1/2" 9'-6 1/4" 2"

10'-2 1/2"

11'-11 1/2"

11'-4 1/2"

1'-2" 2"

12" DIP WALL PIECE

#5 HORIZ DOWELS @ 12" OC, BOTH FACES. TYPICAL AT ALL CORNERS (26"x26")

1'-2" THICK WALL (DRY WELL) WITH #6 VERT BAR @ 6" OC (I.F.), #5 VERT BAR @ 12" OC (O.F.) AND #5 HORIZ BAR @ 12" OC (BOTH FACES)

OVERHEAD BRIDGE CRANE (NOT SHOWN FOR CLARITY). SEE SHEET S-151

10" DIP WALL PIECE

(5) #8 VERT BARS (I.F.) AND (2) #5 VERT BARS (O.F.) EACH SIDE OF WALL PENETRATION. (2) #5 HORIZ BARS AT TOP AND BOTTOM (FULL WALL WIDTH). PROVIDE (4) #4 DIAGONAL BARS (5'-0" LONG) AT EDGES OF PIPE, EACH FACE

10" 1'-4" 1'-4"

(2) #8 VERT BARS (I.F.) AND (2) #5 VERT BARS (O.F.) EACH SIDE OF WALL PENETRATION. PROVIDE (4) #4 DIAGONAL BARS (5'-0" LONG) AT EDGES OF PIPE, EACH FACE. TYPICAL FOR ALL WALL PENETRATIONS UP TO 14" IN WET WELL

3'-10 1/2"

9'-1"

3 S-108

1'-4" THICK WALL (WET WELL) WITH #8 VERT BAR @ 6" OC (I.F.), #5 VERT BAR @ 12" OC (O.F.) AND #5 HORIZ BAR @ 12" OC (BOTH FACES)

14" DIP WALL PIECE 14" DIP WALL PIECE 4" SEWER DRAIN

1'-4"

11'-7" 5'-8 1/2" 14'-8" 4'-0 1/2"

9'-8" 36'-0" 4"

DON'T CUT WALL REINFORCEMENT FOR DRAIN LINE PENETRATION

PLAN

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TUCKER
STATE OF UTAH

HANSEN ALLEN & LUCE INC ENGINEERS

DESIGNED ACS	3					
DRAFTED MAJ	2					
CHECKED GST	1					
DATE APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.	

SCALE AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
PUMPHOUSE FOUNDATION WALL PLAN

SHEET S-103

126.42.300

7/04

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\S-104 PUMPHOUSE FLOOR SLAB & STEM WALL PLAN.DWG
FILE DATE: 3.15.2024, 14:14:30 (MAJ)

46'-0"

(4) #6 CROSSWISE BARS @ 2" OC (BOTTOM) & (2) #5 CROSSWISE BARS @ 2" OC (TOP), TYP AT SIDES OF ALL PUMP OPENINGS IN DRY WELL, UNO

(5) #6 CROSSWISE BARS @ 2" OC (BOTTOM) & (3) #5 CROSSWISE BARS @ 2" OC (TOP)

2/S-107

(10) #6 CROSSWISE BARS @ 2" OC (BOTTOM) & (4) #5 CROSSWISE BARS EQUALLY SPACED (TOP)

(2) #6 CROSSWISE BARS @ 2" OC (BOTTOM) & (2) #5 CROSSWISE BARS @ 2" OC (TOP)

(5) #6 CROSSWISE BARS @ 2" OC (BOTTOM) & (3) #5 CROSSWISE BARS EQUALLY SPACED (TOP)

N

0 1 2
SCALE IN FEET

STEM WALL, TYP (SEE SHEET S-106 FOR DIMENSIONS)

#5 BARS @ 12" OC (TOP & BOTTOM) LENGTHWISE BARS, TYP IN DRY WELL

(1) #5 BAR (TOP & BOTTOM) AT EDGE OF OPENING

3'-6"

OPEN

CONCRETE SHELF PER SECTIONS ON S-106 & S-107

EDGE OF SLAB

#6 BARS @ 6" OC (BOTTOM) AND #5 BARS @ 12" OC (TOP), CROSSWISE BARS, TYP IN DRY WELL

12'-0"

5'-8"

(4) #6 BARS @ 2" OC (BOTTOM) & (2) #5 BARS @ 2" OC (TOP), FULL LENGTH OF BUILDING

BLOCKOUT FOR DOORWAY (TYP) (NOTE: HOLD BLOCKOUT FOR DOORWAY DOWN TO ALLOW FOR SLAB TO POUR THROUGH OPENING)

1'-2"

3'-4 1/2" | 3'-6" | 2'-6" | 3'-6" | 2'-6" | 3'-6" | 2'-6" | 3'-6" | 1'-10 1/2" | 3'-6" | 1'-10 1/2" | 3'-6" | 8'-0 1/2"

(2) #6 BARS @ 2" OC (BOTTOM) & (1) #5 BARS @ 2" OC (TOP), FULL LENGTH OF BUILDING

(1) #6 BAR (BOTTOM) & (1) #5 BAR (TOP) AT EDGE OF OPENING (PARTIAL LENGTH OF BUILDING)

1
S-106

OPEN

10'-5 1/2"

3'-0"

9'-10 1/2"

10" DIP PIPE PENETRATION

(2) #4 DIAG BARS (3'-6" LONG) @ 2" CLR FROM PIPE TOP AND BOTTOM OF SLAB

8'-7"

CONTRACTOR TO BEND BARS AROUND PIPE PENETRATION (DO NOT CUT)

#4 DIAG BAR (5'-0" LONG), TOP AND BOTTOM AT ALL CORNERS OF OPENINGS. BEND AS REQUIRED

(2) #6 BARS @ 2" OC (BOTTOM) & (1) #5 BARS @ 2" OC (TOP), FULL LENGTH OF BUILDING

CONCRETE SHELF PER SECTIONS ON S-106 & S-107

1'-10 1/2"

(2) #5 BARS (2'-5" LONG)

10"

#4 DIAG BARS (3'-0" LONG) @ 2" CLR FROM PIPE TOP AND BOTTOM OF SLAB

EDGE OF SLAB, TYP

SEE SHEET S-105 FOR HOUSEKEEPING PADS

STEM WALL, TYP (SEE SHEET S-106 FOR DIMENSIONS)

10'-8 1/2"

10'-1 1/2"

2'-6"

23'-4"

(2) #5 BARS (10'-0" LONG)

7'-4" | 4'-8"

6"

#5 BARS @ 12" OC (TOP & BOTTOM) EACH WAY, TYP IN WET WELL

STEM WALL OVER SLAB (SEE SECTION 2/S-107)

2'-4 1/2"

3'-0"

9'-1"

3'-8 1/2"

(2) #6 BARS (15'-0" LONG) @ 2" OC (BOTTOM) AND (1) #5 BAR (15'-0" LONG) @ 2" OC (TOP)

GOOSENECK AIR VENT PENETRATION (SEE DETAIL A/C-502)

6"

OPEN

GOOSENECK AIR VENT COLLAR (SEE DETAIL H/S-507)

3
S-108

(3) #6 BARS (28'-0" LONG) @ 2" OC (BOTTOM) AND (2) #5 BARS (28'-0" LONG) @ 2" OC (TOP)

B
S-510 PUMPHOUSE WALL PIPE PENETRATION

(2) #5 CROSSWISE BARS @ 2" OC (BOTTOM) AND (1) #5 CROSSWISE BAR @ 2" OC (TOP), TYP AT SIDES OF ALL OPENINGS IN WET WELL, UNO

(2) #5 LENGTHWISE BARS @ 2" OC (BOTTOM) AND (1) #5 LENGTHWISE BAR @ 2" OC (TOP), TYP AT BOTH SIDES OF OPENINGS IN WET WELL, UNO

#4 DIAG BAR (5'-0" LONG), TOP AND BOTTOM AT ALL CORNERS OF OPENINGS. BEND AS REQUIRED

EDGE OF SLAB

1'-4" | 7'-0" | 1'-9" | 3'-0" | 2'-8" | 3'-0" | 11" | 6'-0" | 6'-0" | 3'-0" | 1'-4"

9'-8" | 36'-0" | 4"

GENERAL SHEET NOTES:
1. ALL CROSSWISE BARS TO BE LOCATED BELOW LENGTHWISE BARS, UNO.

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE inc
ENGINEERS

DESIGNED	ACS	3			
DRAFTED	MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY APVD.

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
PUMPHOUSE FLOOR SLAB & STEM WALL PLAN

SHEET S-104

126.42.300

7/04



GENERAL SHEET NOTES:

1. ADJUST DOOR OPENING SIZE AS REQUIRED TO MEET DOOR OR DOOR FRAME MANUFACTURER'S REQUIREMENTS.
2. INTERIOR WALLS TO ALIGN WITH STAIR OPENING. POSITION RELATIVE TO EDGE OF OPENING AS SHOWN IN DETAIL D/S-507.

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TUCKETT
STATE OF UTAH

HANSEN ALLEN & LUCE Inc
ENGINEERS

DESIGNED	ACS	3				
DRAFTED	MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
PUMPHOUSE CMU WALL PLAN

SHEET S-105

126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-105 PUMPHOUSE CMU WALL PLAN.DWG
FILE DATE: 3.6.2024 14:36:45 (MAJ)

7/04



SECTION 1 S-102 | 1 S-103 | 1 S-104 | 1 S-105

0 1 2
SCALE IN FEET

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-106 PUMPHOUSE DRY WELL SECTION.DWG
FILE DATE: 4.15.2024 16:29:07 (MAJ)

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE Inc ENGINEERS

DESIGNED	ACS	3				
DRAFTED	MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
PUMPHOUSE DRY WELL SECTION

SHEET S-106

126.42.300

7/04



FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-107 PUMPHOUSE DRY & WET WELL SECTION.DWG
FILE DATE: 4.15.2024 16:35:34 (MAJ)

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE Inc
ENGINEERS

DESIGNED	ACS	3				
DRAFTED	MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.


SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
PUMPHOUSE DRY & WET WELL SECTION


SHEET S-107
126.42.300

7/04




SECTION | 3 | S-102 | 3 | S-103 | 3 | S-104 | 3 | S-105

DETAIL NOTES:
1. SEE SHEETS S-102, S-103 AND S-107 FOR TYPICAL WALL AND FLOOR SLAB(S) REINFORCEMENT.




DETAIL NOTES:
1. WELD MAY BE SHOP OR FIELD WELDED DEPENDING ON WHETHER CONTRACTOR ELECTS TO INSTALL THE FLAT PLATES IN THE SLAB INDEPENDENT OF THE SPLITTER PLATES.

WET WELL TRENCH FLOW GUIDES (NTS) | A | A | — | C-107 | A | A | C-108 | S-107




DETAIL NOTES:
1. WET SET THREADED 1/2"x4" NELSON STUD INTO FLOOR SLAB AND PROJECT 1" ABOVE TOP OF SLAB. SET ELEVATION OF PLATE AFTER FLOOR SLAB HAS CURED USING ADJUSTMENT NUT BELOW PLATE. FIELD CUT STUD FLUSH WITH TOP OF PLATE AND SPOT WELD TO STUD. GRIND WELD FLUSH. GROUT BLOCKOUT W/ NON-SHRINK GROUT.
2. VERIFY DIMENSION IN FIELD AND ADJUST TO ALIGN WITH END OF FLARED END AND/OR TO PROVIDE CLEARANCES SHOWN AROUND FLARED END SECTION, AS APPLICABLE.

ANTI-VORTICES FIXTURE (NTS) | B | B | B | — | C-105 | C-108




DETAIL NOTES:
1. SEE SHEETS S-102, S-103 AND S-107 FOR TYPICAL WALL AND FLOOR SLAB(S) REINFORCEMENT.

SECTION (NTS) | 4 | —



DETAIL NOTES:
1. SEE SHEETS S-102, S-103 AND S-107 FOR TYPICAL WALL AND FLOOR SLAB(S) REINFORCEMENT.


SECTION (NTS) | 5 | —



DETAIL NOTES:
1. SEE SHEETS S-102, S-103 AND S-107 FOR TYPICAL WALL AND FLOOR SLAB(S) REINFORCEMENT.

SECTION (NTS) | 6 | —

GENERAL SHEET NOTES:
1. ALL DIMENSIONS FOR METAL FABRICATION SHALL BE VERIFIED PRIOR TO MANUFACTURE. SHOP DRAWINGS SHALL BE SUBMITTED TO ENGINEER FOR APPROVAL PRIOR TO MANUFACTURING.
2. ALL STAINLESS STEEL SHALL BE TYPE 316.
3. SEE SHEET C-111 FOR PUMPHOUSE PIPE, FITTING AND EQUIPMENT SCHEDULE.



SECTION (NTS) | 7 | —

ANTI-VORTICES BAFFLE (NTS) | C | C | C | — | C-105 | C-108

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE Inc ENGINEERS

DESIGNED ACS | DRAFTED MAJ | CHECKED GST | DATE APRIL 2024

NO.	DATE	REVISIONS	BY	APVD.
3				
2				
1				

SCALE AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
PUMPHOUSE WET WELL SECTIONS & DETAILS

SHEET S-108

126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-108 PUMPHOUSE WET WELL SECTIONS & DETAILS.DWG
FILE DATE: 3.15.2024 14:24:04 (MAJ)

7/04



GENERAL SHEET NOTES:
1. SEE STRUCTURAL NOTES SHEET S-100 FOR LOAD AND TRUSS REQUIREMENTS.

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TILLEY
STATE OF UTAH

HANSEN ALLEN & LUCE Inc
ENGINEERS

DESIGNED	ACS	3				
DRAFTED	MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
PUMPHOUSE ROOFING PLAN

SHEET S-109

126.42.300

FILE NAME:PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-109 PUMPHOUSE ROOFING PLAN.DWG
FILE DATE: 3.6.2024 14:42:02 (MAJ)

7/04



PLAN

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-151 PUMPHOUSE DRY WELL CRANE PLAN.DWG
FILE DATE: 4.17.2024 08:37:03 (MAJ)

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE inc
ENGINEERS

DESIGNED	ACS	3				
DRAFTED	BKC, MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.


SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
PUMPHOUSE DRY WELL CRANE PLAN


SHEET S-151
126.42.300

7/04



SECTION 1 S-151

0 2 4
SCALE IN FEET



SECTION 2 S-151

0 2 4
SCALE IN FEET

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
REGISTERED PROFESSIONAL ENGINEER

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

HANSEN ALLEN & LUCE, Inc. ENGINEERS

DESIGNED	ACS	3					
DRAFTED	BKC, MAJ	2					
CHECKED	GST	1					
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.	

SCALE AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
PUMPHOUSE DRY WELL CRANE SECTIONS

SHEET S-152

126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - S-152 PUMPHOUSE DRY WELL CRANE SECTIONS.DWG
FILE DATE: 4/17/2024 08:47:50 (MAJ)

7/04



FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\S–201 SCREEN BUILDING FOOTING & SLAB PLAN.DWG
FILE DATE: 3.6.2024 14:44:07 (MAJ)

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TWEEDIE
STATE OF UTAH

HANSEN ALLEN & LUCE Inc
ENGINEERS

DESIGNED	ACS	3				
DRAFTED	MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.


SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
SCREEN BUILDING FOOTING & SLAB PLAN

SHEET S–201
126.42.300

7/04



GENERAL SHEET NOTES:

1. ADJUST DOOR OPENING SIZE AS REQUIRED TO MEET DOOR OR DOOR FRAME MANUFACTURER'S REQUIREMENTS.

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE Inc. ENGINEERS

DESIGNED	ACS	3					
DRAFTED	MAJ	2					
CHECKED	GST	1					
DATE	APRIL 2024	NO.	DATE	REVISIONS		BY	APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
SCREEN BUILDING FOUNDATION WALL PLAN

SHEET S-202

126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWN
FILE DATE: 3.6.2024 14:47:24 (MAJ)

7/04



GENERAL SHEET NOTES:

1. OVERALL EXTENTS OF GRATES TO BE 1/2" LESS THAN THE DIMENSIONS STATED ABOVE TO ALLOW CLEARANCE TO INSTALL AND REMOVE THE GRATING.
2. AS-BUILT DIMENSIONS TO BE VERIFIED IN THE FIELD PRIOR TO FABRICATION OF GRATING.
3. GRATING SHALL BE FIBERGLASS REINFORCED POLYMER PER SECTION 05 50 00. GRATING DIMENSIONS TO BE FIELD MEASURED AND CUSTOM FABRICATED TO FIT.

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-203 SCREEN BUILDING GRATING & CAP SLAB PLAN.DWG
FILE DATE: 3.6.2024 14:52:47 (MAJ)

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TWITCHELL
STATE OF UTAH

HANSEN ALLEN & LUCE inc
ENGINEERS

DESIGNED	ACS	3				
DRAFTED	MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
SCREEN BUILDING GRATING & CAP SLAB PLAN

SHEET S-203

126.42.300

7/04



PLAN

GENERAL SHEET NOTES:

1. ADJUST DOOR OPENING SIZE AS REQUIRED TO MEET DOOR OR DOOR FRAME MANUFACTURER'S REQUIREMENTS.
2. ALL CROSSWISE BARS TO BE LOCATED BELOW OTHERS, UNO.

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TWELVES
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3				
DRAFTED	MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
SCREEN BUILDING UPPER FLOOR SLAB PLAN

SHEET S-204

126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-204 SCREEN BUILDING UPPER FLOOR SLAB PLAN.DWG
FILE DATE: 4.15.2024 15:57:31 (MAJ)

7/04



GENERAL SHEET NOTES:

1. ADJUST DOOR OPENING SIZE AS REQUIRED TO MEET DOOR OR DOOR FRAME MANUFACTURER'S REQUIREMENTS.
2. INTERIOR WALLS TO ALIGN WITH STAIR OPENING. POSITION RELATIVE TO EDGE OF OPENING AS SHOWN IN DETAIL D/S-507.

PLAN

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TUCKETT
STATE OF UTAH

HANSEN ALLEN & LUCE INC. ENGINEERS

DESIGNED	ACS	3				
DRAFTED	MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
SCREEN BUILDING CMU WALL PLAN


SHEET S-205

126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-205 SCREEN BUILDING CMU WALL PLAN.DWG
FILE DATE: 4.15.2024 16:04:04 (MAJ)

7/04





SECTION 4 S-204

0 2 4

SCALE IN FEET

PROFESSIONAL STRUCTURAL ENGINEER No. 2774619 ROBERT C. CONDER 4/18/2024 STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER 4/19/24 No. 5052482 GREGORY S. TUCKETT STATE OF UTAH

HANSEN ALLEN & LUCE, Inc. ENGINEERS

DESIGNED	ACS	3					
DRAFTED	MAJ	2					
CHECKED	GST	1					
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.	

SCALE: AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
SCREEN BUILDING SECTIONS I

SHEET S-206

126.42.300


FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-206 SCREEN BUILDING SECTIONS I.DWG
FILE DATE: 4.15.2024 16:14:02 (MAJ)

7/04




SECTION 2 | 2 | 2 | 2 | 2
S-201 | S-202 | S-203 | S-204 | S-205

0 2 4
SCALE IN FEET



SECTION 3 | 3 | 3
S-201 | S-202 | S-203

0 2 4
SCALE IN FEET



PIPE BLOCKOUT IN SLAB A –

0 1 2
SCALE IN FEET

GENERAL SHEET NOTES:
1. SEE SHEETS S-204 & S-206 FOR TYPICAL WALL AND FLOOR REINFORCEMENT.

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TUCKER
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED ACS	3					
DRAFTED MAJ	2					
CHECKED GST	1					
DATE APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.	

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
SCREEN BUILDING SECTIONS II

SHEET S-207
126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-207 SCREEN BUILDING SECTIONS II.DWG
FILE DATE: 3.15.2024 14:28:45 (MAJ)

7/04



GENERAL SHEET NOTES:
1. SEE SHEET S-100 STRUCTURAL NOTES FOR LOAD AND TRUSS REQUIREMENTS.

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TWOMBLY
STATE OF UTAH

HANSEN ALLEN & LUCE inc
ENGINEERS

DESIGNED	ACS	3			
DRAFTED	MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY / APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
SCREEN BUILDING ROOFING PLAN

SHEET S-208

126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-208 SCREEN BUILDING ROOFING PLAN.DWG
FILE DATE: 3.6.2024 1:52:24 23 (MAJ)


7/04



PIPE PENETRATION THROUGH MASONRY WALLS

A
–


NTS



TYPICAL MASONRY WALL REINFORCING

B	B	B
–	S-105	S-205

NTS




NOTES:

1. USE BAR QUANTITIES AND SIZES GIVEN IN LINTEL SCHEDULE UNLESS OTHERWISE NOTED ON THE DRAWINGS.
2. EXTEND "C" BARS 48 BAR DIAMETERS, BUT NOT LESS THAN 2'-0" BEYOND TOP AND BOTTOM OF OPENING EXCEPT THAT WHEN "H" OR "W" EXCEEDS 2'-0". "C" BARS SHALL EXTEND FULL HEIGHT. WHERE THERE IS LESS THAN 8'-0" BETWEEN ADJACENT OPENINGS, EXTEND REINFORCING CONTINUOUS TO 2'-8" BEYOND FURTHEST OPENING.
3. "A" AND "B" BARS SHALL EXTEND 48 BAR DIAMETERS, BUT NOT LESS THAN 2'-0" EACH SIDE OF THE OPENINGS.
4. FOR BARS SIZES. MATCH TYPICAL WALL REINFORCING AS SHOWN ON THE BUILDING WALL SECTIONS.
5. FOR LINTEL DEPTH EQUAL TO OR GREATER THAN 48", PROVIDE ADDITIONAL LAYER OF HORIZONTAL REINFORCEMENT AT 12" FROM BOTTOM OF LINTEL. MATCH SIZE OF TYPICAL WALL HORIZONTAL REINFORCEMENT.
6. MATCH TYPICAL #5 VERTICAL WALL REINFORCEMENT FOR STIRRUPS ("S" SHAPED STIRRUPS WITH HOOKS AT BOTH TOP & BOTTOM).

CMU OPENING REINF SCHEDULE 8" WALLS						
W	LINTEL DEPTH	STIRRUP SIZE / SPACING	A BARS	B BARS	C BARS	JAMB WIDTH
<6'-6"	1'-4"	NOTE 6	(2) #5	(1) #5	(4) #6	16"
<13'-0"	2'-0"	NOTE 6	(2) #5	(1) #5	(4) #6	16"

MASONRY LINTEL DETAILS AT WALL OPENINGS

NTS




NOTES:

1. SET ANCHOR BOLTS WITH TEMPLATE.
2. CUT BLOCK WEB AS REQUIRED TO ALLOW PLACEMENT OF ANCHOR BOLT AND 1/2" MINIMUM OF GROUT BETWEEN ANCHOR BOLT AND BLOCK.
3. STAINLESS STEEL WEDGE OR SCREW ANCHORS MAY BE USED IN LIEU OF ANCHOR BOLTS. CONTACT ENGINEER W/ ALT. IF DESIRED.

ANCHOR BOLTS IN MASONRY

C
–




NOTE: SEE MASONRY NOTES (SEE SHEET S-100)

MASONRY WALL REINFORCING AT TYPICAL BOND BEAM

D	D
–	S-105

NTS




DETAIL NOTES:

1. SEE DETAILS B/S-503 & F/S-507 FOR EMBEDDED BEARING PAD AND ATTACHMENT TO CONCRETE PILASTER BELOW.
2. USE SIMILAR DETAIL FOR PILASTERS IN CORNER.

MASONARY PILASTER

E	E	E
S-105	S-205	S-503

NTS




NOTES:

1. EXACT LOCATIONS OF JOINTS TO BE DETERMINED BY THE CONTRACTOR & APPROVED BY THE ENGINEER. SPACING OF JOINTS TO NOT EXCEED 24' MAX.
2. SMOOTH BARS ACROSS JOINT SHALL MATCH HORIZONTAL BAR SPACING. PREVENT BOND BETWEEN BAR AND GROUT ON ONE SIDE OF JOINT WITH GREASE FILLED PVC SLEEVE. CAP AND SIZE SLEEVES TO ALLOW ONE INCH OF MOVEMENT BEYOND END OF PANELS.
3. ROOF LEVEL CHORD REINF. SHALL BE CONTINUOUS THROUGH CONTROL JOINT.
4. CONTROL JOINTS SHALL NOT INTERSECT LINTELS.

CMU EXPANSION JOINT DETAIL

F
–

NTS



MASONRY LINTEL DETAILS

G	G	G	G
–	S-105	S-109	S-205

NTS

PROFESSIONAL STRUCTURAL ENGINEER No. 2774619 ROBERT C. CONDER 4/18/2024 STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER 4/19/24 No. 5052482 GREGORY S. TWOMBS STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3			
DRAFTED	MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY / APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
TYPICAL MASONRY DETAILS

SHEET S-501

126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-501 TYP MASONRY DETAILS.DWG
FILE DATE: 3/15/2024 14:43:29 (MAJ)

7/04




DETAIL NOTE:

1. CONTRACTOR TO VERIFY ACCESS HATCH IS CENTERED OVER SCREEN.

SCREEN ACCESS HATCH
NTS

A	A	A
S-206	S-207	S-208




DETAIL NOTE:

1. INSTALL ROOFING SYSTEM PER MANUFACTURER'S RECOMMENDATIONS.


TYPICAL GABLE DETAIL (SCREEN BUILDING)
NTS

B	B	B
–	S-207	S-208




TYPICAL EAVE-TRUSS & CEILING
NTS

C	C
S-106	S-107
C	C
S-109	S-208



GABLE W/ METAL SIDING
NTS

D
S-207



TYPICAL GABLE DETAIL
NTS

E
S-208

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\S-502 TYP ROOFING DETAILS 1.DWG
FILE DATE: 3/6/2024 1:52:58:34 (MAJ)
7/04

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

HANSEN ALLEN & LUCE Inc
ENGINEERS


DESIGNED	ACS	3			
DRAFTED	MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY / APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
TYPICAL ROOFING DETAILS I


SHEET S-502
126.42.300



TYPICAL CONTINUOUS ROOF VENT AND CAP

NTS


A	A
–	S–107
A	A
S–206	S–502



BEAM SUPPORT

NTS

B	B	B
S–105	S–106	S–206




SHEAR TAB CONNECTION FOR TROLLEY HOIST BEAM

NTS

C	C
S–105	S–106

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\S-503 TYP ROOFING DETAILS II.DWG
FILE DATE: 4/19/2024 11:53:29 (MAJ)





HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3				
DRAFTED	MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
TYPICAL ROOFING DETAILS II

SHEET S–503


126.42.300

7/04




PUMPHOUSE STAIR PLAN


A	A	A	A
C–107	S–103	S–106	S–107



SECTION 1 — NTS




SECTION 2 — NTS




SCREEN BLDG STAIR PLAN

B	B	B	B	B
S–201	S–203	S–206	S–207	S–505



SECTION 3 — NTS



SECTION 4 — NTS

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TUCKETT
STATE OF UTAH

HANSEN ALLEN & LUCE, Inc. ENGINEERS

DESIGNED	ACS	3			
DRAFTED	MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY / APVD.

SCALE: NTS

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
CONCRETE STAIR PLANS & SECTIONS

SHEET S–504


126.42.300

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\S–504 CONC STAIR PLANS & SECTIONS.DWG
FILE DATE: 3.6.2024 15:33:17 (MAJ)


7/04




CONCRETE COLUMN | A S-201 | A S-202 | A S-504



SECTION 1 — NTS



SECTION 2 — NTS



10" SQ COLUMN B — NTS

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-505 CONC COLUMN PLAN & SECTIONS.DWG
FILE DATE: 3.6.2024 15:35:00 (MAJ)

PROFESSIONAL STRUCTURAL ENGINEER — No. 2774619 — ROBERT C. CONDER — 4/18/2024 — STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER — 4/19/24 — No. 5052482 — GREGORY S. THOMAS — STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3			
DRAFTED	MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY / APVD.

SCALE: NTS


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
CONCRETE COLUMN PLAN & SECTIONS

SHEET S-505


126.42.300

7/04



RAILING/FLOOR CONNECTION | A | —


NTS



SECTION | 1 | —


RAILING/STAIR TREAD CONNECTION | B | —

NTS




GUARDRAIL | C | — | C | C-202

NTS



GUARDRAIL TO WALL DETAIL | D | —

NTS




SECTION | 2 | —

SECTION | 3 | —

TYPICAL STAIR RAIL TERMINATION | E | C-106 | E | C-202 | E | S-504

NTS



STAIR TREAD & HANDRAIL DETAIL | F | S-504

NTS

GENERAL SHEET NOTES:

1. ALL RAILING, DECKING, PLATES, AND STRUCTURAL MEMBERS TO BE ALUMINUM FABRICATION UNLESS OTHERWISE NOTED.
2. ALL BOLTS AND NUTS TO BE STAINLESS STEEL UNLESS OTHERWISE NOTED.
3. DRILL AND EPOXY ANCHOR PER MANUFACTURER'S REQUIREMENTS.
4. HANDRAIL HEIGHT SHALL BE 38" (VERTICAL) MEASURED FROM STAIR NOSING LINE OR FLOOR.
5. ALL ALUMINUM IN CONTACT WITH CONCRETE MUST BE COATED WITH AN APPROVED BITUMINOUS PAINT, COLOR-MATCHED POLYURETHANE PAINT OR SIMILAR.

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TILLOTSON
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3				
DRAFTED	MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: NTS

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
TYPICAL GUARDRAIL DETAILS

SHEET S-506


126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-506 TYP GUARDRAIL DETAILS.DWG
FILE DATE: 3.6.2024 15:36:41 (MAJ)


7/04




TYPICAL GRATING EMBED — A C-501 | A S-206 | A S-508



HOUSE KEEPING PAD — NTS — B – | B C-109 | B C-110 | B S-105 | B S-106




DUMPSTER BARRIER — C C-202 | C S-206




DETAIL NOTES:
1. EDGE OF STEEL FRAMING TO BE SET BACK 1" FROM EDGE OF ADJACENT OPENINGS IN CONCRETE SLAB, AS APPLICABLE.

INTERIOR FRAME WALLS — D S-105 | D S-205 | D S-207




DETAIL NOTE:
1. PVC WATERSTOP SHALL BE GREENSTREAK TYPE 781 OR APPROVED EQUAL, UNO. BULBED WATERSTOP SHALL BE GREENSTREAK TYPE 702 OR APPROVED EQUAL.


TYPICAL WATERSTOP DETAIL — NTS — E –




TYPICAL STRIP FOOTING — NTS — F – | F S-206



PILASTER FOUNDATION DETAIL — NTS — G – | G S-106 | G S-202 | G S-204





GOOSENECK AIR VENT COLLAR — NTS — H C-106 | H C-502 | H S-104

PROFESSIONAL STRUCTURAL ENGINEER — No. 2774619 — ROBERT C. CONDER — 4/18/2024 — STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER — 4/19/24 — No. 5052482 — GREGORY S. TUCKER — STATE OF UTAH

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-507 MISC STRUCTURAL DETAILS 1.DWG
FILE DATE: 4.17.2024 09:00:57 (MAJ)

HANSEN ALLEN & LUCE, Inc. ENGINEERS

DESIGNED	ACS	3			
DRAFTED	BKC, MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY / APVD.

SCALE: NOT TO SCALE


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
MISCELLANEOUS STRUCTURAL DETAILS I

SHEET S-507

126.42.300


7/04



WALL MOUNTED GRATING SUPPORT


B	B	B
–	C–203	S–203
B	B	
S–206	S–207	

0 .25 .5
SCALE IN FEET



SUMP DETAIL


C	C
C–107	S–107



DETAIL NOTES:
1. ALLTHREAD TO BE SUSPENDED FROM ANGLE. IT IS NOT DRILLED THROUGH THE ROOF TRUSS. ROOF TRUSSES TO REMAIN INTACT.


DISCHARGE CHUTE HANGER

D	D
C–203	S–206
D	D
S–207	S–208




MANUAL SCREEN ASSEMBLY

E
C–201




SECTION

1
–



MANUAL SCREEN

F
–



MANUAL SCREEN ASSEMBLY
LIFTING EYE

G
–

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TUCKETT
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3			
DRAFTED	BKC	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY APVD.


SCALE AS SHOWN

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
MISCELLANEOUS STRUCTURAL DETAILS II

SHEET S–508
126.42.300

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\S–508 MISC STRUCTURAL DETAILS II.DWG
FILE DATE: 3.6.2024 - 15:39:39 (MAJ)
7/04




SECTION 1 / NTS — —




DETAIL NOTES:
1. CONTRACTOR/MANUFACTURER SHALL VERIFY THE DESIGN OF THE MOUNTING BRACKET AND ANCHORS.

12x10 PUMP MOUNTING BRACKET — A / S-106
NTS





SECTION 2 / NTS — —



DETAIL NOTES:
1. CONTRACTOR/MANUFACTURER SHALL VERIFY THE DESIGN OF THE MOUNTING BRACKET AND ANCHORS.


10x6 PUMP MOUNTING BRACKET — B / S-106
NTS






SECTION 3 / NTS — —

FACE-MOUNTED GRATING SUPPORT BEAM — C / S-203
NTS





SECTION 4 / NTS — —

GRATING SUPPORT BEAM — D / S-203
NTS

LICENSED PROFESSIONAL ENGINEER — 4/19/24 — No. 5052482 — GREGORY S. TUCKER — STATE OF UTAH

PROFESSIONAL STRUCTURAL ENGINEER — No. 2774619 — ROBERT C. CONDER — 4/18/2024 — STATE OF UTAH

DESIGNED	ACS	3					
DRAFTED	MAJ	2					
CHECKED	GST	1					
DATE	APRIL 2024	NO.	DATE	REVISIONS		BY	APVD.

HANSEN ALLEN & LUCE inc ENGINEERS

SCALE: NOT TO SCALE

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
MISCELLANEOUS STRUCTURAL DETAILS III

SHEET S-509


126.42.300


FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-509 MISC STRUCTURAL DETAILS III.DWG
FILE DATE: 3.6.2024 15:41:26 (MAJ)

7/04





DETAIL NOTES:
1. CONTRACTOR TO PROVIDE AND INSTALL DOWELS IF MANUFACTURER DOES NOT PRE-INSTALL THE SIMILAR DOWELS FOR THE RISER SECTION.







5' GRATING SUPPORT BEAM A S-203
NTS









DETAIL NOTES:
1. INSTALL #5 HORIZ BAR TO LINE UP WITH BARS IN CMU WALLS. EXTEND A MIN OF 38" INTO CMU WALL.

PUMPHOUSE WALL PIPE PENETRATION B A-101 B S-104
0 2 4
SCALE IN FEET

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TIMMINS
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3			
DRAFTED	MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY APVD.

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
MISCELLANEOUS STRUCTURAL DETAILS IV

SHEET S-510
126.42.300


FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-510 MISC STRUCTURAL DETAILS IV.DWG
FILE DATE: 3.15.2024 15:01:27 (MAJ)

7/04




RAIL BEAM TO WALL DETAIL
NTS

A	A
S-151	S-152



RAIL BEAM STEEL POST DETAIL
NTS

B
S-152



REMOVEABLE BOLLARD
NTS

C	C
C-202	C-203

C	C	C
S-204	S-205	S-206

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\S-511 MISC STRUCTURAL DETAILS V.DWG
FILE DATE: 4.17.2024 09:11:45 (MAJ)

PROFESSIONAL STRUCTURAL ENGINEER
No. 2774619
ROBERT C. CONDER
4/18/2024
STATE OF UTAH

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. TIMOTHY
STATE OF UTAH

HANSEN ALLEN & LUCE inc
ENGINEERS

DESIGNED	ACS	3			
DRAFTED	MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY APVD.

SCALE
NOT TO SCALE

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
STRUCTURAL
MISCELLANEOUS STRUCTURAL DETAILS V

SHEET
S-511
126.42.300

7/04

PLUMBING SYMBOL LEGEND

SYMBOL	DESCRIPTION
	DROP IN PIPE
	RISE IN PIPE
	VALVE IN RISE
	UNION
	GAS SHUT OFF VALVE (GAS COCK)
	BALL VALVE
	CAP
WHA	GAS TYPE WATER HAMMER ARRESTOR
	THERMOMETER
PRV	PRESSURE REDUCING VALVE – (PRV)
FD RD	FLOOR DRAIN, FLOOR SINK OR ROOF DRAIN
FCO	FLOOR CLEAN OUT
WCO	WALL CLEAN OUT
CO	CLEAN OUT
VTR	VENT THROUGH ROOF
	COLD WATER
	DOMESTIC HOT WATER
	SEWER OR WASTE
	VENT
G	GAS (NATURAL GAS)
	SAFETY OR RELIEF VALVE
(FC #)	FIXTURE COUNT

GENERAL PLUMBING NOTES

1. CONTRACTOR SHALL VERIFY ALL PLUMBING FIXTURES, EQUIPMENT REQUIREMENTS AND LOCATIONS, AND ALL RELATED UTILITIES WITH THE MECHANICAL AND ARCHITECTURAL PLANS AND SPECIFICATIONS AND SHALL PROVIDE ALL SERVICES AS REQUIRED.
2. ALL WALL–HUNG PLUMBING FIXTURES SHALL BE SECURELY ATTACHED TO AND SUPPORTED BY FLOOR–MOUNTED CARRIERS OF ALL–METAL CONSTRUCTION. FIXTURE HANGERS OR ARMS SHALL BE SUPPORTED FREE OF THE FINISHED WALL. HANGERS SHALL BE BY WADE, SMITH, JOSAM, OR ZURN.
3. EACH INDIVIDUAL FIXTURE SUPPLY SHALL BE PROVIDED WITH A CHROME–PLATED STOP VALVE WITH HAND WHEEL. VALVE SHALL BE BALL TYPE, QUARTER TURN AS APPROVED BY ENGINEER. STOPS SHALL BE ON BOTH HOT AND COLD WATER LINES.
4. FIXTURES AND ACCESSORIES SHALL BE AS SPECIFIED. EACH ITEM SHALL BE COMPLETE WITH CHROME–PLATED BRASS TRIM. SEE PLUMBING FIXTURE SCHEDULE.
5. CAULK WITH SILICONE COMPOUND AROUND ALL FIXTURES AT INTERFACE WITH WALLS AND/OR FLOOR.
6. ALL PLUMBING SHALL BE DONE IN ACCORDANCE WITH THE LATEST ADOPTED EDITION OF THE UTAH PLUMBING CODE AND/OR LOCAL ORDINANCES.
7. ALL DOMESTIC COLD AND HOT WATER PIPING IS TO BE INSULATED PER THE SCHEDULE ON THIS DRAWING.

PLUMBING FIXTURE SCHEDULE

SYM	DESCRIPTION	COLD	HOT	TEPID	TRAP	WASTE	VENT	REMARKS
P–1	SINK – 16 GAUGE STAINLESS STEEL, SINGLE COMPARTMENT, STAND ALONE, 21" x 25–13/16" x 43–3/4" TALL, NO DRAINBOARDS, ELKAY MODEL 14–1C16X20–0X. PROVIDE WITH WALL MOUNTED FAUCET, QUARTER TURN CERAMIC DISC HANDLES, 8" CENTERSET, ELKAY MODEL LK940BP03L2H.	1/2"	1/2"	–	INT	2"	2"	–

GAS FIRED WATER HEATER

SYMBOL	MANUFACTURER AND MODEL NO	SERVICE	TYPE	FUEL TYPE/ PRESSURE	INPUT CAPACITY (BTUH)	VOLTS/ø/HZ	WATER TEMP IN/OUT	OVERALL SIZE	VENT CONNECTION SIZE	OPERATING WEIGHT (LBS)	REMARKS
DWH–1	RINNAI CU160I	DOMESTIC HOT WATER	FULLY CONDENSING	NATURAL GAS	160,000	120/1/60	40/120	18.5"x31.3"H	3" PVC INTAKE 3" PVC EXHAUST	62	PROVIDE VENT TERMINATION KIT

EXPANSION TANKS


SYMBOL	TANK VOLUME GALLONS	ACCEPT VOLUME GALLONS	AMTROL MODEL	ARRANGEMENT	DUTY	REMARKS
DET–1	2.0	0.9	ST–5	VERTICAL	DOMESTIC COLD WATER SYSTEM	

PIPE MATERIAL SCHEDULE

SYMBOL	DESCRIPTION	PIPE MATERIAL	INSULATION/COVERING
DCW	DOMESTIC COLD WATER	COPPER TYPE L	SEE DETAIL 7/P5.1
DHW	DOMESTIC HOT WATER	COPPER TYPE L	1" FIBERGLASS WITH ASJ
GAS	NATURAL GAS	BLACK STEEL, SCHEDULE 40 THREADED	NONE
WASTE	SANITARY WASTE	PVC SOLID CORE SCHEDULE 40 WITH DWV FITTINGS	NONE
VENT	VENT	PVC SOLID CORE SCHEDULE 40 WITH DWV FITTINGS	NONE

THERMOSTATIC MIXING VALVE SCHEDULE

SYMBOL	MANUFACTURER AND MODEL NO	LOCATION	FLOW RATE (GPM)	ALLOWABLE PRESSURE DIFFERENTIAL (PSI)	OUTLET HOT WATER TEMP. (°F)	INLET SIZE	OUTLET SIZE	ACCESSORIES AND REMARKS
MV–1	POWERS – LFG480	BELOW HAND SINKS	0.5–2.0	5	105°	1/2"	1/2"	ASSE 1070



GAS FLOW DIAGRAM
SCALE: NONE

GAS DESIGN NOTES

LENGTH:	20'
DESIGN MBH:	160
BTU / CU FT:	890
DESIGN CFH:	180
BUILDING PRESSURE:	4 OZ
BRANCH SIZE:	3/4"

FILE NAME: PROJECTS\126 – SOUTH SALT LAKE CITY\42.200 – ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 – DOWNTOWN AND PUMP STATION\P–001 SCHEDULES.DWG
FILE DATE: 3.7.2024 09:49:50 (MAJ)

HANSEN ALLEN & LUCE inc ENGINEERS

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

DESIGNED	ACS	3			
DRAFTED	MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY / APVD.

SCALE: NONE


SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
PLUMBING
SCHEDULES

SHEET P–001

126.42.300

7/04





PLAN

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\P-101 DRY & WET WELL PLAN.DWG
FILE DATE: 3.6.2024 16:01:22 (MAJ)

7/04

HANSEN ALLEN & LUCE inc ENGINEERS

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH


DESIGNED	ACS	3				
DRAFTED	MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
PLUMBING
PUMPHOUSE DRY & WET WELL PLAN

SHEET
P-101
126.42.300



PLAN

GENERAL SHEET NOTES:

1. SHIFT SOUTH WALL HYDRANT AS REQUIRED TO PROVIDE 8-INCH MIN DISTANCE BETWEEN HYDRANTS, SUCH THAT A SOLID CELL OF CMU CAN BE INSTALLED BETWEEN THEM.

N

0 2 4
SCALE IN FEET

FILE NAME:PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\P-102 PUMPHOUSE BLDG FLOOR PLAN.DWG
FILE DATE: 3.6.2024 17:04:09 (MAJ)

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE Inc
ENGINEERS

DESIGNED	ACS	3				
DRAFTED	MAJ	2				
CHECKED	GST	1				
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
PLUMBING
PUMPHOUSE BUILDING FLOOR PLAN

SHEET P-102
126.42.300

7/04

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\P-201 SCREEN BUILDING TRENCH PLAN.DWG
FILE DATE: 3.6.2024 17:29:29 (MAJ)



LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE, INC. ENGINEERS

DESIGNED	ACS
DRAFTED	MAJ
CHECKED	GST
DATE	APRIL 2024

NO.	DATE	REVISIONS	BY	APVD.
3				
2				
1				

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
PLUMBING
SCREEN BUILDING TRENCH PLAN

SHEET P-201

126.42.300

7/04




SECTION 1 / -

DETAIL NOTES:

1. PIPE TO BE PLACED TO PREVENT ANY STRUCTURAL REINFORCEMENT IN CONCRETE FROM BEING CUT.

2" WATER SERVICE LINE @ PUMP HOUSE PLAN — A / P-101




SECTION 2 / -

DETAIL NOTES:


1. PIPE TO BE PLACED TO PREVENT ANY STRUCTURAL REINFORCEMENT IN CONCRETE FROM BEING CUT.

2" WATER SERVICE LINE @ SCREEN BLDG PLAN — B / P-201




LOWER HOSE BIBB — C / - | C / P-101 | C / P-201

NTS



UPPER HOSE BIBB — D / - | D / P-102

NTS



SUMP DETAIL — E / P-101 | E / P-102

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED	ACS	3			
DRAFTED	TPB, MAJ	2			
CHECKED	GST	1			
DATE	APRIL 2024	NO.	DATE	REVISIONS	BY / APVD.

SCALE: AS SHOWN


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
PLUMBING
DETAILS I


SHEET P-501

126.42.300


FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\P-501 DETAILS I.DWG
FILE DATE: 3.7.2024 09:14:20 (MAJ)
7/04



VENT THRU ROOF DETAIL — A
NTS —




CONCENTRIC VENT KIT DETAIL — B
NTS —



GAS CONNECTION TO APPLIANCE / EQUIPMENT DETAIL
(WITHOUT GAS PRESSURE REGULATOR)

GAS CONNECTION DETAIL — C
NTS —



TANKLESS WATER HEATER DETAIL — D
NTS —

LICENSED PROFESSIONAL ENGINEER
4/19/24
No. 5052482
GREGORY S. THOMAS
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

DESIGNED ACS	3				
DRAFTED MAJ	2				
CHECKED GST	1				
DATE APRIL 2024	NO.	DATE	REVISIONS	BY	APVD.

SCALE: AS SHOWN

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
PLUMBING
DETAILS II

SHEET P-502
126.42.300

FILE NAME: PROJECTS\126 - SOUTH SALT LAKE CITY\42.200 - ZELLER AND DOWNTOWN SEWER IMPROVEMENTS\CAD\2 - DOWNTOWN AND PUMP STATION\P-502 DETAILS II.DWG
FILE DATE: 3.7.2024 10:18:18 (MAJ)

7/04

WALL MOUNTED AIR CONDITIONING UNIT

SYMBOL	COOLING (1)		MIN. EER	ENTERING AIR		NOM. ACFM	ESP	ELECTRICAL								BARD MODEL	UNIT WEIGHT (LBS)	REMARKS
	STANDARD RATING TOTAL MBH	STANDARD RATING SENS. MBH		°Fdb	°Fwb			HEATER (KW)	VOLTS	HERTZ	PHASE	SUPPLY FAN HP	CONDENSER FAN HP	MCA	MOCP			
WAC-1	78	66	10.0	75	62	2850	0.35	9	460	60	3	2	3	21	30	W090APC09EP	1300	FURNISH UNIT WITH PGDX CONTROLLER, 2" MERV 8 FILTERS, FULL ECONOMIZER, SUPPLY REGISTER, AND RETURN GRILLE.

NOTES: (1) 95° F O.A.T.

SEE SPECIFICATION SECTION 236100

VENTILATION FAN

SYMBOL	AIR FLOW CFM	TOTAL STATIC PRESS IN WC @ ALTITUDE	FAN MAX RPM	FAN ELECTRICAL				BHP	DRIVE	SONES	LWA	COOK MODEL	DUTY	REMARKS
				VOLTS	HERTZ	PHASE	MOTOR HP							
REF-1	1,400	0.5	2770	115	60	5/8	1	0.5	DIRECT	29	91	100R28D (VF2)	LOWER PUMP RM	(1)

NOTES: (1) EC MOTOR WITH EXTERNAL 2 SPEED CONTROLLER

SEE SPECIFICATION SECTION 238200

ELECTRIC UNIT HEATER SCHEDULE

SYMBOL	BTUH INPUT	NOMINAL CFM	ELECTRICAL DATA					MARKEL MODEL	DUTY	REMARKS
			VOLTS	HZ	PHASE	AMPS	KW			
EUH-1	34,130	1500	480	60	3	12.7	10	HLA-16	SCREENINGS RM	SURFACE MOUNTED, INTEGRAL THERMOSTAT. PROVIDE WITH CLASS 1 DIV. 11 RATING.
EUH-2	34,130	1500	480	60	3	12.7	10	HLA-16	SCREENINGS RM	SURFACE MOUNTED, INTEGRAL THERMOSTAT. PROVIDE WITH CLASS 1 DIV. 11 RATING.
EUH-3	34,130	700	480	60	3	12.1	10	P3P5510T	LOWER PUMP RM	SURFACE MOUNTED, INTEGRAL THERMOSTAT.

SEE SPECIFICATION SECTION 237600

FILTER SECTION

SYMBOL	FILTER SIZE	FILTER THICKNESS	FILTER TYPE	FARR MODEL	DUTY	NO. AND SIZE OF FILTERS	REMARKS
FS-1	36"x24"	2"	PLEATED	30-30	ODOR CONTROL	(2)18"x24"	SLIDE-IN FILTER RACK
FS-2	36"x24"	2"	PLEATED	30-30	LOWER PUMP ROOM INTAKE	(2)18"x24"	SLIDE-IN FILTER RACK

SEE SPECIFICATION SECTION 239000

LOUVER

SYMBOL	APPROXIMATE SIZE	DUTY	RUSKIN MODEL	REMARKS
L-1	36"x24"	ODOR CONTROL	ELF6375DX	-
L-2	36"x24"	LOWER PUMP ROOM INTAKE	ELF6375DX	-

SEE SPECIFICATION SECTION 233700

HVAC SYMBOL LEGEND

	RETURN AIR OR EXHAUST DIRECTION		SUPPLY DUCT (CROSS SECTION)
	OPPOSED BLADE DAMPER		RETURN AIR OR EXHAUST DUCT (CROSS SECTION)
	PARALLEL BLADE DAMPER		ROUND DUCT (CROSS SECTION)
O.A.	OUTSIDE AIR	24"x12"	DUCT SIZE, INSIDE CLEAR DIMENSION IN INCHES
S.A.	SUPPLY AIR		DROP OR RISE IN SUPPLY DUCT
E.A.	EXHAUST AIR		SUPPLY AIR OR OUTSIDE AIR DIRECTION
V.A.	VENTILATION AIR	(T)	THERMOSTAT
		(S)	WALL SENSOR

GENERAL NOTES

1. EQUIPMENT MANUFACTURERS AND MODEL NUMBERS ON DRAWING SCHEDULES ARE PROVIDED FOR REFERENCE ONLY IN ORDER TO AID THE CONTRACTOR ESTABLISH SIZES. DO NOT LIMIT EQUIPMENT SELECTION TO SHOWN MAKES. APPROVED EQUAL MANUFACTURERS WILL BE ACCEPTED. REFERENCE DIV. 23 SPECIFICATIONS FOR OTHER APPROVED MANUFACTURERS.
2. SIZES OF EQUIPMENT PADS, FLOOR, AND WALL PENETRATIONS ARE GIVEN FOR REFERENCE ONLY AND SHALL BE FIELD VERIFIED PRIOR TO FABRICATION OR ORDERING EQUIPMENT. COORDINATE ALL FLOOR / WALL / ROOF PENETRATIONS WITH STRUCTURAL ENGINEER.
3. THE HVAC CONTRACTOR SHALL BE RESPONSIBLE TO COORDINATE WITH THE GENERAL CONTRACTOR. THE FINAL SIZE AND LOCATION OF ROOF AND WALL OPENINGS REQUIRED FOR THE HVAC EQUIPMENT INSTALLATION.
4. REFERENCE ELECTRICAL CONTROL LADDER DIAGRAMS FOR EXHAUST FAN WIRING DIAGRAM.
5. ALL DUCTWORK IN PROCESS AREAS TO BE STAINLESS STEAL, ALUMINUM, OR PVC COATED AND LINED GALVANIZED DUCT.

PROFESSIONAL ENGINEER
6647772-2202
KARSON DAVID HALVERSON
04/01/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED KDH	3		·		
DRAFTED KGM	2				
CHECKED KDH	1				
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE ·

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
HVAC SCHEDULES
AND DETAILS


SHEET H-001


126.42.300

I:\2005801 - DWG\HVAC\SHEET\20658 - H-001.dwg, 4/19/2024 4:40:08 PM, Heath Engineering co/GJE

DRAWING NOTES

1. 14"x14" STAINLESS STEEL EXHAUST DUCT UP TO LEVEL ABOVE. SUPPORT DUCT RISE PER SMACNA GUIDLINES. FIELD COORDINATE EXACT LOCATION OF DUCT RISER. SEE SECTION FOR ADDITIONAL DETAILS.
2. MOUNT UNIT HEATER AT HEIGHT AS RECOMMENDED BY MANUFACTURER. FIELD VERIFY EXACT UNIT HEATER LOCATION.
3. HONEYWELL THERMOSTAT MODEL T775A2009





LOWER LEVEL HVAC PLAN

SCALE: 1/4"=1'-0"

5 0 10

1
H-100

N

PROFESSIONAL ENGINEER
6647772-2202
KARSON
DAVID
HALVERSON
04/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS	HEATH Engineering Company	DESIGNED KDH	3		·		
		DRAFTED KGM	2				
		CHECKED KDH	1				
		DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE
·

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
HVAC
DRY PIT PLAN

SHEET
H-100
126.42.300

I:\20085\01 - DWG\HVAC\SHEET\20085 - H-100.dwg, 4/19/2024 4:40:14 PM, Heath Engineering csa\GJE

DRAWING NOTES

1. MOUNT UNIT HEATER AT HEIGHT AS RECOMMENDED BY MANUFACTURER. FIELD VERIFY EXACT UNIT HEATER LOCATION.
2. BOTTOM OF LOUVER TO BE 24" ABOVE GRADE. FIELD COORDINATE EXACT LOCATION.
3. 14"x14" STAINLESS STEEL EXHAUST DUCT UP FROM LEVEL BELOW. OFFSET AS SHOWN AND CONTINUE UP TO REF-1 ON ROOF. TRANSITION AS REQUIRED AND CONNECT TO REF-1. SUPPORT DUCT RISE PER SMACNA GUIDLINES. FIELD COORDINATE EXACT LOCATION OF DUCT RISER. SEE SECTION FOR ADDITIONAL DETAILS.
4. SEE SECTION FOR WAC-1 INSTALLATION NOTES.
5. HONEYWELL THERMOSTAT MODEL T775A2009.
6. REFERENCE CIVIL DRAWINGS FOR ODOR CONTROL DESIGN.




MAIN LEVEL HVAC PLAN

SCALE: 1/4"=1'-0"

1 H-100

5 0 10



PROFESSIONAL ENGINEER
6647712-2202
KARSON DAVID HALVERSON
04/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS	HEATH Engineering Company	DESIGNED KDH	3				
		DRAFTED KGM	2				
		CHECKED KDH	1				
		DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE .

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
HVAC
TOP FLOOR PLAN


SHEET H-101

126.42.300

I:\20058\01 - DWG\HVAC\SHEET\20058 - H-101.dwg, 4/19/2024 4:40:18 PM, Heath Engineering co\GJE

DRAWING NOTES

1. SECURELY ANCHOR AIR CONDITIONING UNIT TO WALL AND SUPPORT STRUCTURE PROVIDED BY THE GENERAL CONTRACTOR. ANCHOR SUPPORT STRUCTURE ON A CONCRETE PAD. HVAC CONTRACTOR TO PROVIDE ENGINEERED DRAWINGS FOR REVIEW AND APPROVAL PRIOR TO INSTALLATION. INSTALL UNIT PER MANUFACTURER'S REQUIREMENTS.
2. PROVIDE SLEEVES IN WALL FOR DUCTWORK PENETRATIONS. SEE DETAIL.
3. MOUNT TOP OF SUPPLY AIR DIFFUSER AT 10' -/+ ABOVE THE MAIN FLOOR.
4. MOUNT BOTTOM OF UNIT WITH MINIMUM OF 2' CLEARANCE TO CONCRETE PAD.



PUMP ROOM HVAC SECTION

SCALE: 1/4"=1'-0"

5 0 10

A H-300

PROFESSIONAL ENGINEER
6647772-2202
KARSON DAVID HALVERSON
04/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS	HEATH Engineering Company	DESIGNED KDH	3		·		
		DRAFTED KGM	2				
		CHECKED KDH	1				
		DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE ·


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
HVAC
BUILDING SECTIONS

SHEET H-300

126.42.300

I:\2005801 - DWG\HVAC\SHEET\2005S - H-300.dwg, 4/19/2024 4:40:22 PM, Heath Engineering co/GJE



DUCT PENETRATION DETAIL


SCALE: NONE — 6 / H-501

DIMENSION OF LONGEST SIDE, (INCHES)	SHEET METAL GAGE (ALL FOUR SIDES)	MINIMUM REINFORCING ANGLE SIZE & MAXIMUM LONGITUDINAL SPACING BETWEEN TRANSVERSE JOINTS &/OR INTERMEDIATE REINFORCING	TRANSVERSE REINFORCING * AT JOINTS: MIN H, IN.	DRIVE SLIP / PLAIN S SLIP — RECOM-MENDED GAGE	HEMMED S SLIP — RECOM-MENDED GAGE	ALT. BAR SLIP — RECOM-MENDED GAGE	REIN-FORCED BAR SLIP — RECOM-MENDED GAGE	BAR SLIP / ANGLE SLIP — RECOM-MENDED GAGE	BAR SLIP / ANGLE SLIP — REINFORCED ANGLE SIZE	STD. SEAM / ANGLE REINFORCED STD. SEAM — REINFORCED ANGLE SIZE	POCKET LOCK / ANGLE REINFORCED POCKET LOCK — RECOM-MENDED GAGE	POCKET LOCK / ANGLE REINFORCED POCKET LOCK — REINFORCED ANGLE SIZE
UP THRU 12	24	NONE REQ.	1	26	26	24	24	24	NOT REQ.	NOT REQ.	24	NOT REQ.
13-18	24	NONE REQ.	1	24	24	24	24	24	NOT REQ.	NOT REQ.	24	NOT REQ.
19-30	24	1x1x1/8" @60in.	1	-	24	24	24	24	NOT REQ.	NOT REQ.	24	NOT REQ.
31-42	22	1x1x1/8" @60in.	1	-	-	22	22	22	NOT REQ.	NOT REQ.	22	NOT REQ.
43-54	22	1-1/2"x1-1/2"x1/8" @60in.	1-1/2	-	-	22	22	22	1-1/2"x1-1/2"x1/8"	NOT REQ.	22	NOT REQ.
55-60	20	1-1/2"x1-1/2"x1/8" @60in.	1-1/2	-	-	-	22	22	1-1/2"x1-1/2"x1/8"	NOT REQ.	22	NOT REQ.
61-84	20	1-1/2"x1-1/2"x1/8" @60in.	1-1/2	-	-	-	22	22	1-1/2"x1-1/2"x1/8"	1-1/2"x1-1/2"x1/8"	22	1-1/2"x1-1/2"x1/8"

* TRANSVERSE REINFORCING SIZE IS DETERMINED BY DIMENSION OF SIDE TO WHICH ANGLE IS APPLIED.


SHEETMETAL DUCT CONSTRUCTION DETAIL

SCALE: NONE — 1 / H-501




EXHAUST FAN DETAIL

SCALE: NONE — 7 / H-501




BRANCH DUCT AND DAMPER DETAIL

SCALE: NONE — 4 / H-501



INLET LOUVER WITH FILTER DETAIL


SCALE: NONE — 5 / H-501



NOTES:
1. ALL DUCTS (SUPPLY, RETURN AND EXHAUST) TO HAVE TURNING VANES IN SQUARE ELBOW.
2. INSIDE SQUARE, OUTSIDE RADIUS ELBOWS NOT ALLOWED.

RECTANGULAR AND ROUND DUCT FITTING DETAIL

SCALE: NONE — 2 / H-501



UNIT HEATER MOUNTING DETAIL


SCALE: NONE — 3 / H-501

PROFESSIONAL ENGINEER — 6647772-2202 — KARSON DAVID HALVERSON — 04/11/2024 — STATE OF UTAH

DESIGNED KDH	3		·			SCALE ·	DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION HVAC DETAILS
DRAFTED KGM	2						SHEET H–501
CHECKED KDH	1						126.42.300
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.		

HANSEN ALLEN & LUCE inc ENGINEERS — HEATH Engineering Company — SOUTH SALT LAKE


I:\2008501 - DWG\HVAC\SHEET\20058 - H-501.dwg, 4/19/2024 4:40:26 PM, Heath Engineering co\GJE



NOTES:
A. REF-1 TO BE CONTROLLED SUCH THAT THE DEFAULT FAN SPEED IS SPEED 1 (3 ACH). WHEN EITHER THERMOSTAT CONTACT IS MADE THEN REF-1 RAMPS UP TO SPEED 2 (6 ACH).


REF-1 CONTROL DIAGRAM

SCALE: NONE — 3 / H-601



WALL MOUNTED AIR CONDITIONING UNIT CONTROL DIAGRAM

SCALE: NONE — SEE PLANS FOR EXACT CONFIGURATION — 1 / H-601



ELECTRIC UNIT HEATER CONTROL DIAGRAM

SCALE: NONE — 2 / H-601

CONTROL SEQUENCES AND AIRFLOW DESIGN NOTES

SCREENING ROOM (EUH-1 & 2):

CLASSIFICATION: CLASS 1 DIVISION 11
WHEN THE LOCAL BUILT-IN SPACE THERMOSTATS SERVING ELECTRIC UNIT HEATERS EUH-1 & 2 CALL FOR HEATING, THE UNIT HEATER IS ENERGIZED TO SATISFY THE LOCAL SPACE TEMPERATURE THROUGH ITS FACTORY WIRED CONTROLS. THE UNIT OPERATES UNTIL THE SPACE TEMPERATURE IS SATISFIED AND THEN POWERS OFF. SET BUILT-IN THERMOSTAT SET POINT TO 45°F (ADJ.) THE SCREENING ROOM WILL BE CONTINUOUSLY VENTILATED FOR ODOR CONTROL. LOUVER L-1 WILL SERVE AS THE ODOR CONTROL MAKE UP INLET.

LOWER PUMP ROOM (REF-1 & EUH-3):

SPACE MUST BE CONTINUOUSLY VENTILATED WITH ROOFTOP EXHAUST FAN REF-1 PER THE SCHEDULE BELOW:
6 AC/HOUR WHEN OUTSIDE AIR TEMPERATURE>50°F OR WHEN THE SPACE TEMPERATURE RISES ABOVE SETPOINT (85°F ADJ.).
3 AC/HOUR WHEN OUTSIDE AIR TEMPERATURE<50°F.
LOWER PUMP ROOM VOLUME = 13,600 CU. FT.
6 AC/HOUR = 1360 CFM (USE 1400 CFM).
3 AC/HOUR = 680 CFM (USE 700 CFM).
WHEN THE LOCAL BUILT-IN SPACE THERMOSTAT SERVING ELECTRIC UNIT HEATER EUH-3 CALLS FOR HEATING, THE UNIT HEATER IS ENERGIZED TO SATISFY THE LOCAL SPACE TEMPERATURE THROUGH ITS FACTORY WIRED CONTROLS. THE UNIT OPERATES UNTIL THE SPACE TEMPERATURE IS SATISFIED AND THEN POWERS OFF. SET BUILT-IN THERMOSTAT SET POINT TO 45°F (ADJ.)

UPPER PUMP ROOM (WAC-1):

WAC-1 OPERATES THROUGH ITS OWN INTERNAL CONTROLS BASED UPON A SIGNAL FROM A WALL MOUNTED REMOTE PROGRAMMABLE CONTROLLER.
THE REMOTE PROGRAMMABLE CONTROLLER IS FURNISHED WITH THE AIR CONDITIONING UNIT AND SHALL BE CAPABLE OF CONTROLLING THE UNIT IN COOLING AND HEATING MODES. THE UNIT SHALL OPERATE IN FULL OUTSIDE AIR ECONOMIZER MODE WHEN THE OUTDOOR CONDITIONS PERMIT AS SENSED BY THE UNIT LOGIC BOARD (OUTDOOR TEMPERATURE, HUMIDITY, AND PARTICULATE LEVEL ARE MONITORED BY THE UNIT LOGIC BOARD). THE REMOTE CONTROLLER IS TO BE FIELD PROGRAMMED SO THAT THE SYSTEM MAINTAINS A SPACE TEMPERATURE SET POINT OF 70°F (ADJUSTABLE) IN COOLING MODE AND 50°F (ADJUSTABLE) IN HEATING MODE.

PROFESSIONAL ENGINEER
6647722202
KARSON DAVID HALVERSON
04/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED KDH	3		·			SCALE ·
DRAFTED KGM	2					
CHECKED KDH	1					
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.	

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
HVAC CONTROL DIAGRAMS

SHEET H-601

126.42.300

T:\2065\501 - DWG\HVAC\SHEET\2065S - H-601.dwg, 4/19/2024 4:40:29 PM, Heath Engineering cox\GJE

B274<0C82B 3806A0<B

SYMBOL	DESCRIPTION
	TERMINAL LUG OR STRIP
	TRANSFORMER
	GROUND CONNECTION
	BOND TO METALLIC WATER PIPE
	BOND TO METALLIC WATER PIPE
	BOND TO BUILDING STEEL
	GENERATOR

;867C8=6

SYMBOL	DESCRIPTION
	FLUORESCENT LIGHT FIXTURE, SEE FIXTURE SCHEDULE.
	EMERGENCY LIGHTING, SEE FIXTURE SCHEDULE.
F#	LIGHTING FIXTURE TYPE - SEE FIXTURE SCHEDULE.
$	SINGLE POLE SWITCH
$3	3 WAY SWITCH
$m	WALL MOUNTED MOTION SWITCH - DUAL TECHNOLOGY
$T	MOTOR RATED TOGGLE SWITCH
$D	DIGITAL OVERRIDE SWITCH
$P	SINGLE POLE SWITCH WITH PILOT LIGHT
SP	RECESSED CEILING MOUNTED SPEAKER BY OTHERS
	WALL MOUNTED MOTION SENSOR
	CEILING MOUNTED MOTION SENSOR
	CEILING-MOUNTED EXIT LIGHT, SEE FIXTURE SCHEDULE
	WALL-MOUNTED EXIT LIGHT, SEE FIXTURE SCHEDULE
	RECESSED CAN LIGHT, SEE FIXTURE SCHEDULE

2>=CA>;B 8=BCAD<4=CB

SYMBOL	DESCRIPTION
AE	ANALYZER ELEMENT
AIT	ANALYZING INDICATING TRANSMITTER
CGD	COMBUSTIBLE GAS DETECTOR
CIT	CONDUCTIVITY INDICATING TRANSMITTER
FE	FLOW ELEMENT
FIT	FLOW INDICATING TRANSMITTER
FS	FLOW SWITCH
LE	LEVEL ELEMENT
LIT	LEVEL INDICATING TRANSMITTER
LS	LEVEL SWITCH
LT	LEVEL TRANSMITTER
ME	MOISTURE ELEMENT
MV	MOTOR OPERATED VALVE OR GATE
OS	OVER TORQUE SWITCH
PIT	PRESSURE INDICATING TRANSMITTER
PS	PRESSURE SWITCH
SV	SOLENOID OPERATED VALVE
TE	TEMPERATURE ELEMENT
TS	TEMPERATURE SWITCH
TT	TEMPERATURE TRANSMITTER
ZS	LIMIT OR POSITION SWITCH

B274<0C82B 3806A0<B ?>F4A

SYMBOL	DESCRIPTION
	EMERGENCY STOP PUSH BUTTON (MAINTAINED)
	NORMALLY CLOSED PUSH BUTTON
	LOCKOUT STOP PUSH BUTTON
	NORMALLY OPEN PUSH BUTTON
T.C.	CONTACT - TIME DELAY T.C. = NORMALLY OPEN W/TIME DELAY CLOSING. I.C. - T.O. = NORMALLY OPEN WITH INSTANT CLOSING AND TIME DELAY OPENING. T.C.-T.O. = NORMALLY OPEN W/TIME DELAY CLOSING AND TIME DELAY OPENING AFTER DEENERGIZATION.
T.O.	CONTACT - TIME DELAY T.C. = NORMALLY CLOSED WITH TIME DELAY OPENING. T.O.-T.C. = NORMALLY CLOSED WITH TIME DELAY OPENING AND TIME DELAY CLOSING AFTER DEENERGIZATION. I.O.-T.C. = NORMALLY CLOSED WITH INSTANT OPENING AND TIME DELAY CLOSING.
	NORMALLY OPEN CONTACT
	NORMALLY CLOSED CONTACT
	LIMIT SWITCH
	PRESSURE SWITCH LOW
	PRESSURE SWITCH HIGH
	FLOW SWITCH
	LEVEL FLOAT SWITCH
	TEMPERATURE SWITCH
AMPS / POLES	DISCONNECT SWITCH SHOWN WITH RATING AND NUMBER OF POLES.
	FUSEHOLDER OR FUSEBLOCK
AMPS POLES	CIRCUIT BREAKER OR MOTOR CIRCUIT PROTECTOR, SHOWN WITH TRIP RATING AND NUMBER OF POLES.
H O A OOX	3 POSITION SELECTOR SWITCH HAND - OFF - AUTO, POSITION LEGEND: X=CLOSED O=OPEN
ON OFF XO	2 POSITION SELECTOR SWITCH, POSITION LEGEND: X=CLOSED O=OPEN
ICTO	TIMER RELAY CONTACT INSTANTANEOUS CLOSE TIME DELAY OPEN.
NOTC	TIMER RELAY CONTACT NORMALLY OPEN TIME DELAY CLOSE.
5	FULL VOLTAGE NONREVERSING (FVNR) MOTOR STARTER OR CONTACTER NUMBER DESIGNATES NEMA SIZE.
	RTU, PLC, OR RIO CONTACT
UM	UTILITY METER
X	BEACON ALARM LIGHT. LETTER INDICATES COLOR: R=RED, A=AMBER, B=BLUE, G=GREEN
X	PILOT LIGHT. LETTER INDICATES COLOR: R=RED, A=AMBER, B=BLUE, G=GREEN
R	RELAY
TD	TIME DELAY RELAY
AR	ALARM RELAY
ETM ETM	ELAPSED TIME METER
M	MOTOR STARTER OR CONTACTOR COIL
EOL	ELECTRONIC OVERLOAD RELAY
SSRV	SOLID STATE REDUCED VOLTAGE STARTER
VFD	VARIABLE FREQUENCY DRIVE
HF	HARMONIC FILTER
CTS	CURRENT TRANSFORMER
	THERMAL OVERLOAD RELAY
	LTC CONNECTION
	MC CONNECTION
X	MOTOR, X = HORSEPOWER
	DEVICE LOCATED AT REMOTE LOCATION.
	FUSE
	NODE OR CONNECTION

SYMBOL	DESCRIPTION
	DUPLEX RECEPTACLE
	DUPLEX RECEPTACLE, RECESSED FLOOR MOUNTED
	DUPLEX RECEPTACLE, RECESSED CEILING MOUNTED
	QUADRAPLEX RECEPTACLE
	QUADRAPLEX RECEPTACLE, RECESSED FLOOR MOUNTED
	QUADRAPLEX RECEPTACLE, RECESSED CEILING MOUNTED
	ISOLATED GROUND TYPE DUPLEX RECEPTACLE
	SPECIAL PURPOSE OR WELDING OUTLET.
GFCI	GROUND FAULT CIRCUIT INTERRUPTER RECEPTACLE.
WP	WEATHERPROOF CONVENIENCE OUTLET
	FLUSH FLOOR DEVICE BOX
	HOME RUN TO PANEL - INDICATING 2 #12, #12 GND, 3/4" CONDUIT OR AS SHOWN.
	HOME RUN TO PANEL - INDICATING NUMBER OF CONDUCTORS - #12 OR AS SHOWN.
X-1,3,5	HOME RUN TO PANEL SHOWING BRANCH CIRCUIT NUMBERS.
	HATCH MARKS IN CONDUIT RUN DENOTES NUMBER OF CONDUCTORS IN CONDUIT. LONG HATCH MARK DENOTES GROUND CONDUCTOR. SIZE OF CONDUCTORS TO BE #12 AWG CONDUCTORS IN CONDUIT UNLESS NOTED OTHERWISE. UNMARKED CONDUITS SHALL BE 3/4" WITH 3 #12.
(E)	DENOTES EXISTING EQUIPMENT OR DEVICES
T	THERMOSTAT
X M	MOTOR, X = HORSE POWER
F	CEILING EXHAUST FAN
J	JUNCTION BOX
	ELECTRICAL PANEL, POWER OR LIGHTING
	METER BASE
	COMBINATION MOTOR STARTER, SEE SPECS
	DISCONNECT SWITCH. (VOLTAGE RATING, NEMA ENCLOSURE, FUSE (NF-NO FUSE), POLES, SIZE (AMPS))
+0'-0"	THIS NOTATION ADJACENT TO WALL OUTLET SYMBOL DENOTES MOUNTING HEIGHT ABOVE FINISHED FLOOR TO CENTER OF OUTLET DEVICE. IF NOT NOTED, THE MOUNTING HEIGHT TO CENTER SHALL BE AS DETAILED OR SPECIFIED.
$M	MANUAL MOTOR STARTER
$T	MANUAL MOTOR STARTER WITH OVERLOADS
DM	DAMPER MOTOR
F#	LIGHTING FIXTURE TYPE - SEE FIXTURE SCHEDULE.
$	SINGLE POLE SWITCH
$3	3 WAY SWITCH
$4	4 WAY SWITCH
	COMMUNICATION/DATA JACK. CONDUIT TO ABOVE CEILING. OWNER TO RUN WIRING.
2	DATA OR CATHODE RAY TUBE (CRT) TERMINAL OUTLET. + 1'-6". (SINGLE, DOUBLE)
2 4	TELEPHONE JACK OUTLET. 1'-6". (SINGLE, DOUBLE, QUAD)

54434A 34B86=0C8>=:;>682

6	I	P: 2 N: 3 G: 4	5

1. NUMBER OF CONDUITS
2. P: NUMBER - SIZE OF PHASE CONDUCTORS PER CONDUIT
3. N: NUMBER - SIZE OF NEUTRAL CONDUCTOR(S) PER CONDUIT
4. G: NUMBER- SIZE OF GROUND CONDUCTOR(S) PER CONDUIT
5. SIZE OF EACH CONDUIT IN INCHES
6. CONDUIT NUMBER

KEY TO CONDUCTOR SIZE & TYPE

14 = #14 AWG COPPER	6 = #6 AWG COPPER	1/0 = 1/0 AWG COPPER	250 = 250 KCMIL COPPER
12 = #12 AWG COPPER	4 = #4 AWG COPPER	2/0 = 2/0 AWG COPPER	350 = 350 KCMIL COPPER
10 = #10 AWG COPPER	2 = #2 AWG COPPER	3/0 = 3/0 AWG COPPER	500 = 500 KCMIL COPPER
8 = #8 AWG COPPER		4/0 = 4/0 AWG COPPER	750 = 750 KCMIL COPPER

011A4E80C8>=B

A	AMPERE	N	NEUTRAL
AFF	ABOVE FINISHED FLOOR	NEC	NATIONAL ELECTRICAL CODE
AI	ANALOG INPUT	NECA	NATIONAL ELECTRICAL CONTRACTOR ASSOCIATION
AIC	AMPS INTERRUPTING CAPACITY		
AFD	ADJUSTABLE FREQUENCY DRIVES	NOTC	NORMALLY OPEN TIMED CLOSED
AO	ANALOG OUTPUT	NPW	NON-POTABLE WATER
AS	AIR SUPPLY	NS	NITROGEN SUPPLY
ATS	AUTOMATIC TRANSFER SWITCH	NTS	NOT TO SCALE
		NTU	TURBIDITY
BC	BYPASS CONTACTOR		
		O.C.	ON CENTER
C	CONDUIT	OF	OVERFLOW
CB	CIRCUIT BREAKER	OIT	OPERATOR INTERFACE TERMINAL
CL2	CHLORINE	OL	OVERLOAD
CON	CONTACTOR	OO	ON/OFF (MAINTAINED)
CPM	CUSTOMER POWER MONITORING	OR	OFF-REMOTE
CPT	CONTROL POWER TRANSFORMER		
CU	COPPER, BARE	P	PHASE OR POLE
CV	CONTROL VALVE	PB	PULL BOX
		PCP	PROCESS CONTROL PANEL
DCS	DISTRIBUTED CONTROL SYSTEM	PFR	PHAS/POWER FAILURE RELAY
DI	DISCRETE INPUT	PI	PULSE INPUT
DO	DISCRETE OUTPUT	PLC	PROGRAMMABLE LOGIC CONTROLLER
DV/DT	DIFFERENTIAL VOLTAGE/TIME		
DWG	DRAWING	PLI	PLANT INFLUENT
		PKG	PACKAGE
ELR	END OF LINE RESISTER	PMP	PUMP
ETM	ELAPSED TIME METER	PNL	PANEL
EOL	ELECTRONIC OVERLOAD	PO	PULSE OUTPUT
ES	EMERGENCY STOP	PPG	POUNDS PER GALLON
EXIST	EXISTING	PPH	POUNDS PER HOUR
		PPM	PARTS PER MILLION
FA	FOUL AIR	PR	PAIR
FC	FAIL CLOSED	PRES	PRESSURE
FE	FLOW ELEMENT	PS	PRESSURE SWITCH
FLA	FULL LOAD AMPS	PSH	PRESSURE SWITCH, HIGH
FS	FLOW SWITCH	PSI	POUNDS PER SQUARE INCH
FVNR	FULL VOLTAGE NON-REVERSING	PV	PROCESS VARIABLE
FW	FINISHED WATER		
		RAS	RETURN ACTIVATED SLUDGE
G	GROUND	RW	RAW WATER
GES	GROUNDING ELECTRODE SYSTEM	RCL	REMOTE I/O
GFCI	GROUND FAULT CIRCUIT INTERRUPTER	RF	RADIO FREQUENCY
		RIO	REMOTE INPUT/OUTPUT
GFP	GROUND FAULT PROTECTION	RS	RAW SEWAGE
GND	GROUND	RSP	RAW SEWAGE PUMP
GPD	GALLONS PER DAY	RST	RESET
GPH	GALLONS PER HOUR	RTD	RESISTANCE TEMPERATURE DETECTOR
GPM	GALLONS PER MINUTE		
GRS	GALVANIZED RIGID STEEL	RTU	REMOTE TELEMETRY UNIT
		RWT	REFLECTED WAVE TRAP
H, HI	HIGH		
H2S	HYDROGEN SULFIDE	SEQ	SERVICE ENTRANCE EQUIPMENT
HMI	HUMAN MACHINE INTERFACE	SES	SERVICE ENTRANCE SECTION
HOA	HAND-OFF-AUTO	SLC	SINGLE LOOP CONTROLLER
HOR	HAND-OFF-REMOTE	SLOS	START-LOCK-OFF-STOP
		SMC	SUBMERSIBLE MANUFACTURER CABLE
I	CURRENT		
IC	INSTRUMENTATION CABLE	SO2	SULFUR DIOXIDE
ICR	INTERMITTENT CYCLE REACTOR	SP	SET POINT
IO	INPUT/OUTPUT	SPC	SPARE CONDUIT
ISC	SHORT CIRCUIT CURRENT	SPR	SPARE
ISR	INTRINSICALLY SAFE RELAY	SS	START/STOP
		SSS	SOLID STATE STARTER (SOFT START)
JB	JUNCTION BOX		
		ST	SHUNT TRIP
L, LO	LOW		
LAN	LOCAL AREA NETWORK	TC	TELEPHONE CABLE
LC	LOOP CONTROLLER	TDOE	TIME DELAY ON ENERGIZE
LCL	LEVEL CONTROL, LOW	TS	TEMPERATURE SWITCH
LCP	LOCAL CONTROL PANEL	TSP	TWISTED SHIELDED PAIR
LOS	LOCK-OUT-STOP	TVSS	TRANSIENT VOLTAGE SURGE SUPPRESSION
LR	LOCAL/REMOTE		
LS	LEVEL SWITCH	TYP	TYPICAL
LTC	LIQUID TIGHT FLEXIBLE CONDUIT		
		UG	UNDERGROUND
M	MOTOR		
MA	MANUAL/AUTO, MILLIAMP	V	VOLT
MAX	MAXIMUM	VFD	VARIABLE FREQUENCY DRIVE
MC	MANUFACTURER'S CABLE		
MCB	MAIN CIRCUIT BREAKER	W	WATT, WIRE
MCC	MOTOR CONTROL CENTER	WAS	WASTE ACTIVATED SLUDGE
MCP	MOTOR CIRCUIT PROTECTOR	WP	WEATHERPROOF
MFR(S)	MANUFACTURER(S)		
MGD	MILLION GALLONS PER DAY	XFMR	TRANSFORMER
MGL	MILLIGRAMS PER LITER	XMTR	TRANSMITTER
MH	MANHOLE		
MIN	MINIMUM	ZS	POSITION SWITCH
ML	MIXED LIQUOR		
MOV	MOTOR OPERATED VALVE		
MTU	MASTER TELEMETRY UNIT		

4;42CA820; ;8=4CH?4B

SYMBOL	DESCRIPTION
	EXPOSED CONDUIT
	UNDERGROUND CONDUIT
	BARE COPPER GROUND CONDUCTOR
	EXISTING EXPOSED CONDUIT
	EXISTING UNDERGROUND CONDUIT
	CAPPED UNDERGROUND CONDUIT OR STUBBUP
	NEW ELECTRICAL EQUIPMENT
	DETAIL VIEW OR MATCHING
	FUTURE
	CONDUIT DROP
	CONDUIT RISE

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
04/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED	RJH	3		·		
DRAFTED	KGM	2				
CHECKED	RJH	1				
DATE	MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE ·

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
SYMBOL LEGEND

SHEET E-01

126.42.300

I:\26058\01 - DWG\ELEC\SHEET\26058 - E-01.dwg, 4/19/2024 4:05:19 PM, Heath Engineering ca/GJE

LIGHTING FIXTURE SCHEDULE

TYPE	ELECTRICAL	MANUFACTURER	CATALOG NUMBER	DESCRIPTION	SOURCE	NOTES
F1	49W 120-277V	LITHONIA	CLX L48 7000LM SEF ULENS WD MVOLT 50K 80CRI	CLX LED L48 , 7000LM, STANDARD EFFICIENCY, LESS LOUVER, LESS LENS, WIDE, MVOLT, GZ10, 4000K, 80CRI, PAINTED WHITE SHEET METAL	5000K CCT 7000 Lm 80 CRI	1
F1E	49W 120-277V	LITHONIA	CLX L48 7000LM SEF ULENS WD MVOLT 50K 80CRI E10WLCP	SAME AS F1 BUT WITH 10W EMERGENCY BATTERY PACK	5000K CCT 7000 Lm 80 CRI	1
F2	51W 120-277V	LITHONIA	FEM L48 8000LM LPPFL MD 80CRI 50K ST5L	FEM LED 48", 8,000 LUMENS, POLYCARBONATE, LOW PROFILE FROSTED LENS, MEDIUM DISTRIBUTION, 80 CRI, 5000 K STAINLESS STEEL LATCHES	5000K CCT 8000 Lm 80 CRI	1
F2E	51W 120-277V	LITHONIA	FEM L48 8000LM LPPFL MD 80CRI 50K ST5L	SAME AS F2 BUT WITH 10W EMERGENCY BATTERY PACK	5000K CCT 8000 Lm 80 CRI	1
F3	25W 120-277V	LITHONIA	WST LED P2 50K VF MVOLT PE DDBXD	LED WALL PACK. DIE-CAST ALUMINUM HOUSING, FORWARD THROW OPTICS. PROVIDE INTEGRAL BUTTON TYPE PHOTOCELL.	5000K CCT 3000 Lm 70 CRI	1
F4	40W 120-277V	HOLOPHANE	EMXH L48 6000LM PGFL WD MVOLT 40K 80CRI	CLASS 1 DIV 2 HAZARDOUS CLASSIFICATION 4FT LINEAR WIDE DISTRIBUTION	5000K CCT 6000 Lm 80 CRI	1

NOTES:
1 - EQUAL FIXTURE SUBSTITUTIONS ALLOWED UPON PRIOR APPROVAL FROM ENGINEER.

CONTROL CONDUIT SCHEDULE

C100	4-#14, 1-#14 GND, 3/4"C
C101	2-#16 TSP, 1-#16 GND, 1"C
C102	FLOW ELEMENT CABLE TO FLOW TRANSMITTER, 1"C
C103	LEVEL ELEMENT CABLE TO LEVEL TRANSMITTER, 1"C
C104	PULL LINE, 1"C
C105	CAT 6 CABLE, 1"C
C106	14-#14, 1-#14 GND, 1"C
C107	3-#16 TSP, 1-#16 GND, 1"C
C108	FLOAT SWITCH CABLE, 1"C
C109	6-#14, 1-#14 GND, 1"C
C110	8-#14, 1-#14 GND, 1"C
C111	4 - FIBER OPTIC, 4" HDPE WITH (4) 1" INNER DUCTS
C112	MANUFACTURER'S CABLE 1"C
C113	8 - #16 TSP 3-WIRE TRIPLEX RTD CABLE, 2-#12, 1-#12 GND, 1-1/4"C

POWER CONDUIT SCHEDULE

P105	1	P: 3 - #8 N: NONE G: 1 - #10	3/4"
P106	1	P: 3 - #12 N: NONE G: 1 - #12	3/4"
P107	1	P: 2 - #6 N: NONE G: 1 - #10	3/4"
P108	1	P: 3 - #6 N: NONE G: 1 - #10	1"
P109	1	P: 2 - #12 N: NONE G: 1 - #12	3/4"
P110	2	P: 3 - 500 N: 1 - 500 G: NONE	3-1/2"
P111	1	P: 1 - #14 N: 1 - #14 G: 1 - #14	3/4"

P001	3	CONDUCTORS BY UTILITY	4"
P002	1	CONDUCTORS BY UTILITY	1-1/4"
P100	2	P: 3 - 500 N: 1 - 500 G: 1 - 1/0	3-1/2"
P101	1	P: 3 - 3/0 N: NONE G: 1 - #4	2"
P102	1	P: 3 - #10 N: NONE G: 1 - #10	3/4"
P103	1	P: 3 - #4 N: NONE G: 1 - #4	1-1/4"
P104	1	P: 3 - 2/0 N: NONE G: 1 - #6	2"

PROVIDE MINIMUM 1" CONDUIT UNDERGROUND

PANEL L

MAIN BREAKER AMPS 175 — 80% — BUS AMPS: 225

VOLTAGE: 208/120 V 3Ø 4W — CIRCUIT BREAKER TYPE: BOLT-ON — MOUNTING: SURFACE

ENCLOSURE: NEMA 1 — INTERRUPTING CAPACITY: 10 KAIC — COVER TYPE: DOOR-IN-DOOR

LOCATION: AS INDICATED

BRANCH CIRCUIT BREAKER				CONNECTION	DESCRIPTION	PHASE			DESCRIPTION	CONNECTION	BRANCH CIRCUIT BREAKER			
NOTES	#	AMP	P.	LOAD (VA)		A	B	C		LOAD (VA)	P.	AMP	#	NOTES
	L-1	20	1	799	LIGHTING	2299			GENERATOR BLOCK HEATER	1500	2	20	L-2	
	L-3	20	1	1620	RECEPTACLES		3120		------	1500	-	-	L-4	
	L-5	20	1	900	RECEPTACLES			2300	GENERATOR AUX	1400	1	20	L-6	
	L-7	20	1	150	FLOW METER	1326			SUMP	1176	1	20	L-8	
	L-9	25	1		SPARE		4160		WELDER	4160	2	50	L-10	
	L-11	20	1	1200	PLC			5360	------	4160	-	-	L-12	
	L-13	40	3	2004	CRANE HOIST	2504			COMBUSTIBLE GAS ALARM PANEL	500	1	20	L-14	
	L-15	--	--	2004	------		4008		HEADWORKS CRANE HOIST	2004	3	40	L-16	
	L-17	--	--	2004	------			4008	------	2004	--	--	L-18	
	L-19	20	1	1422	PUMP ROOM VENT FAN REF-1	3426			------	2004	--	--	L-20	
	L-21	40	3	2004	LOWER CRANE HOIST		2252		HEADWORKS LIGHTING	248	1	20	L-22	
	L-23	--	--	2004	------			2004	SPARE		1	20	L-24	
	L-25	--	--	2004	------	2004			SPARE		1	20	L-26	
	L-27	20	1		SPARE		0		SPARE		1	20	L-28	
	L-29	20	1		SPARE			0	SPARE		1	20	L-30	
	L-31	20	1		SPARE	0			SPARE		1	20	L-32	
	L-33	20	1		SPARE		0		SPARE		1	20	L-34	
	L-35	20	1		SPARE			0	SPARE		1	20	L-36	
	L-37	20	1		SPARE	0			SPARE		1	20	L-38	
	L-39	20	1		SPARE		0		SPARE		1	20	L-40	
	L-41	20	1		SPARE			0	SPARE		1	20	L-42	
					PHASE SUBTOTALS (VA)	11559	13540	13672						
					PHASE TOTALS (KVA)	11.6	13.5	13.7						
					PHASE TOTALS @ 120V (AMPS)	96.3	112.8	113.9						

NOTES:
GEN PROVIDE WITH SURGE PROTECTION DEVICE

PANEL MDP

MLO — BUS AMPS: 800

VOLTAGE: 480/277 V 3Ø 4W — CIRCUIT BREAKER TYPE: I-LINE — MOUNTING: SURFACE

ENCLOSURE: NEMA 1 — INTERRUPTING CAPACITY: 65 KAIC — COVER TYPE: DOOR-IN-DOOR

LOCATION: AS INDICATED

BRANCH CIRCUIT BREAKER				CONNECTION	DESCRIPTION	PHASE			DESCRIPTION	CONNECTION	BRANCH CIRCUIT BREAKER			
NOTES	#	AMP	P.	LOAD (VA)		A	B	C		LOAD (VA)	P.	AMP	#	NOTES
	MDP-1	225	3	38780	PUMP P1	50339			TRANSFORMER TL (45KVA)	11559	3	70	MDP-2	
	MDP-3	--	--	38780	------		52320		------	13540	--	--	MDP-4	
	MDP-5	--	--	38780	------			52452	------	13672	--	--	MDP-6	
	MDP-7	225	3	38780	PUMP P2	43433.6			WAC-1	4654	3	30	MDP-8	
	MDP-9	--	--	38780	------		43433.6		------	4654	--	--	MDP-10	
	MDP-11	--	--	38780	------			43433.6	------	4654	--	--	MDP-12	
1	MDP-13	225	3	0	PUMP P3	2105			GRINDER	2105	3	20	MDP-14	
	MDP-15	--	--	0	------		2105		------	2105	--	--	MDP-16	
	MDP-17	--	--	0	------			2105	------	2105	--	--	MDP-18	
	MDP-19	40	3	5817	PUMP P4	5817			SPARE		3	20	MDP-20	
	MDP-21	--	--	5817	------		5817		------		--	--	MDP-22	
	MDP-23	--	--	5817	------			5817	------		--	--	MDP-24	
	MDP-25	40	3	5817	PUMP P5	5817			SPARE		3	20	MDP-26	
	MDP-27	--	--	5817	------		5817		------		--	--	MDP-28	
	MDP-29	--	--	5817	------			5817	------		--	--	MDP-30	
	MDP-31	20	3	3333	PUMP ROOM HEATER (EUH-3)	5438			ODOR CONTROL UNIT	2105	3	20	MDP-32	
	MDP-33	--	--	3333	--------		5438		------	2105	--	--	MDP-34	
	MDP-35	--	--	3333	--------			5438	------	2105	--	--	MDP-36	
	MDP-37	50	3	9972	HEADWORKS SCREEN CONTROL PANEL	12077			ODOR CONTROL UNIT	2105	3	20	MDP-38	
	MDP-39	--	--	9972	-------		12077		------	2105	--	--	MDP-40	
	MDP-41	--	--	9972	------			12077	------	2105	--	--	MDP-42	
	MDP-43	20	3	3518	HEADWORKS UNIT HEATER (EUH-1)	3518			SPARE		3	20	MDP-44	
	MDP-45	--	--	3518	--------		3518		-------		--	--	MDP-46	
	MDP-47	--	--	3518	--------			3518	-------		--	--	MDP-48	
	MDP-49	20	3	3518	HEADWORKS UNIT HEATER (EUH-2)	4100			HEADWORKS ROLL-UP DOOR	582	3	20	MDP-50	
	MDP-51	--	--	3518	--------		4100		-------	582	--	--	MDP-52	
	MDP-53	--	--	3518	--------			4100	-------	582	--	--	MDP-54	
	MDP-55	60	3	7479	AERIGATOR 1	14958			AERIGATOR 2	7479	3	60	MDP-56	
	MDP-57	--	--	7479	--------		14958		-------	7479	--	--	MDP-58	
	MDP-59	--	--	7479	--------			14958	-------	7479	--	--	MDP-60	
	MDP-61				PROVISION	0			PROVISION				MDP-62	
	MDP-63				PROVISION		0		PROVISION				MDP-64	
	MDP-65				PROVISION			0	PROVISION				MDP-66	
					PHASE SUBTOTALS (VA)	147603	149584	149716						
					PHASE TOTALS (KVA)	147.6	149.6	149.7						
					PHASE TOTALS @ 277V (AMPS)	532.9	540.0	540.5						

NOTES:
1 - MAXIMUM 2 OF 3 LARGE PUMPS RUNNING ELECTRICALLY INTERLOCKED. ONE ALWAYS STANDBY.
GEN PROVIDE WITH SURGE PROTECTION DEVICE

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
04/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE Inc ENGINEERS

HEATH Engineering Company

DESIGNED	RJH	3		.		
DRAFTED	KGM	2				
CHECKED	RJH	1				
DATE	MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE .


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
PANEL AND CONDUIT SCHEDULES

SHEET E-02

126.42.300

I:\2065801 - DWG\ELEC\SHEET\20658 - E-02.dwg, 4/19/2024 5:00:48 PM, Heath Engineering co\GJE



DRAWING NOTES

1. CLASS 1, DIV 1 TO 3'-0" RADIUS FROM OUTLET.
2. CLASS 1, DIV 2 TO 5'-0" RADIUS FROM OUTLET.
3. CLASS 1, DIV 2 TO 3'-0" RADIUS AROUND EQUIPMENT.
4. UNCLASSIFIED UPSTAIRS. UNCLASSIFIED DOWNSTAIRS WITH 6 AIR CHANGES PER HOUR, 3 AIR CHANGES PER HOUR UNDER 50°F.
5. CLASS 1, DIV 2 TO 1'-6" HEIGHT ABOVE GRADE WITHIN 3'-0" OF ANY HATCH OR OPENING.
6. CLASS 1, DIV 1 WITHIN WET WELL BELOW GRADE
7. VALVE VAULT CLASS 1, DIV 2 CONFINED SPACE.
8. ODOR CONTROL UNIT.
9. ODOR CONTROL OUTLET.
10. CLASS 1, DIV 2 WITHIN ALL INDOOR AREA OF HEADWORKS BUILDING. WITH 12 AIR CHANGES IN LOWER LEVEL.
11. PREPARE SPACE FOR NEW GENERATOR. COORDINATE WITH OWNER AND GENERAL CONTRACTOR REMOVAL OF PORTABLE GENERATOR AND PREPARATION OF SPACE FOR THE INSTALLATION OF A NEW GENERATOR. REPLACE GENERATOR PLUG WITH NEW NEMA 3R GENERATOR BREAKER ENCLOSURE 200A/3P. SEE ONE-LINE DIAGRAM REGARDING CONNECTIONS. FIELD-COORDINATE ALL REQUIREMENTS.
12. PROVIDE WP GFCI RECEPTACLE FOR SUMP PUMP. SEE CIVIL DETAILS. POWER FROM EXISTING BUILDING 120V PANEL SPARE 20A BREAKER.
13. DEMOLISH EXISTING GATE CONTROLLER AND GATE OPERATOR. FIELD-COORDINATE. RE-USE POWER CONDUIT AS PRACTICABLE FOR NEW GATE OPERATOR.
14. PROVIDE POWER TO GATE OPERATOR FROM THE SAME CIRCUIT AS CURRENTLY FEEDS EXISTING GATE OPERATOR. EXTEND TO HERE PER MANUFACTURER'S RECOMMENDATIONS. SEE ALSO CIVIL DRAWINGS.
15. GATE OPERATOR. SEE ALSO CIVIL DRAWINGS
16. POLE MOUNTED KEYPAD. WIRE CONTROLS AS RECOMMENDED BY GATE CONTROLLER MANUFACTURER'S RECOMMENDATIONS. SEE ALSO CIVIL DRAWINGS.
17. POWER METER
18. CT CABINET
19. PRIMARY DISCONNECT FOR NEW BUILDING.
20. BUILDING MAIN DISCONNECT.
21. NEW POWER POLE BY RMP.
22. PROVIDE 4" PVC CONDUIT WITH LONG SWEEP FIBERGLASS ELBOWS AND PULL STRING. STUB UP AT LOCATION OF BASE OF NEW POLE. PROVIDE 4" RISER CONDUIT FOR RMP. CONFIRM CONDUIT COUNT AND SIZE AND INSTALLATION TIMING WITH RMP.
23. UTILITY TRANSFORMER. VAULT AND CONDUIT WITH PULL STRING BY CONTRACTOR. COORDINATE ALL UTILITY REQUIREMENTS WITH ROCKY MOUNTAIN POWER.

1 ES-100 **ELECTRICAL SITE PLAN**
SCALE: 1/8" = 1'-0"
10 5 0 10 20

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
04/19/2024
STATE OF UTAH


HANSEN ALLEN & LUCE Inc ENGINEERS	HEATH Engineering Company	DESIGNED RJH	3				SCALE
		DRAFTED KGM	2				
		CHECKED RJH	1				
		DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY APVD.	


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
SITE PLANS

SHEET ES100
126.42.300

I:\2065801 - DWG\ELEC\SHEET\20658 - ES-100.dwg, 4/19/2024 5:02:12 PM, Heath Engineering co/GJE





1 EP100 **LOWER LEVEL POWER PLAN**

SCALE: 1/4"=1'-0"

5 0 10

N

DRAWING NOTES

1. ACCESS HATCH ABOVE, TYPICAL.
2. GFCI WP +48" AFF
3. 20A LOCK GFCI WP +48" AFF
4. SEE MOTOR CONNECTION DETAIL. ALL WIRING AND CONDUIT ROUTING SHALL NOT INTERFERE WITH CRANE MOTION AND OPERATION.
5. SUMP PUMP WITH INTEGRAL FLOAT SWITCH
6. GRINDER
7. GRINDER DISCONNECT. SEE ONE-LINE DIAGRAM. SEE CLASSIFIED TRANSITION DETAIL TO BE INSTALLED ON CLASSIFIED SIDE OF UNCLASSIFIED DISCONNECT. LABEL ON DISCONNECT "THIS BUILDING HAS MULTIPLE DISCONNECTS AND HAS CIRCUITS FED FROM THE BUILDING TO THE SOUTH."
8. TO MOTOR CONTROL PANEL IN PUMP BUILDING
9. TO HOIST CONTROLLER WIRE PER MANUFACTURER'S INSTRUCTIONS. ENSURE ALL WIRING WITHIN THIS LEVEL DOES NOT INTERFERE WITH CRANE MOVEMENT AND OPERATION.
10. INSTALL CLASS I DIV 2 480V/3PH LOCKING PLUG ON GRINDER TO BE STORED ON UPPER LEVEL AND PLACED IN SERVICE AS NEEDED. INSTALL A MATCHING CLASSIFIED RECEPTACLE ON FIBERGLASS STRUT 2 FT ABOVE FLOOR.

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
04/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED RJH	3		·		
DRAFTED KGM	2				
CHECKED RJH	1				
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE ·

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
DRY PIT POWER PLAN

SHEET EP100

126.42.300

I:\2065801 - DWG\ELEC\SHEET\20658 - EP-100.dwg, 4/19/2024 5:01:55 PM, Heath Engineering cov\GH

GENERAL NOTES

A. PROVIDE SPARE 2" CONDUIT FOR EACH TRENCH, PROVIDE (2) SPARE 2" CONDUITS BETWEEN PUMP BUILDING AND SCREEN BUILDING, BETWEEN PUMP BUILDING, EXISTING BUILDING AND BETWEEN PUMP BUILDING AND GENERATOR. PROVIDE (1) SPARE 1" CONDUIT BETWEEN EVERY ELECTRICAL DEVICE THAT HAS A CONTROL CONDUIT TO THE PLC.


DRAWING NOTES


37 SEPARATE OUT THE POWER AND TEMPERATURE SIGNAL WITHIN THE CLASSIFIED TRANSITION. RUN POWER AND TEMPERATURE SIGNAL IN SAME CONDUIT TO CONTROLLER.


38 TO HEADWORKS MOTOR CONTROL PANEL IN PUMP BUILDING.

39 DISCONNECT. SEE ONE-LINE DIAGRAM. SEE CLASSIFIED TRANSITION DETAIL TO BE INSTALLED ON CLASSIFIED SIDE OF UNCLASSIFIED DISCONNECT. LABEL ON DISCONNECT "THIS BUILDING HAS MULTIPLE DISCONNECTS AND HAS CIRCUITS FED FROM THE BUILDING TO THE SOUTH."

1 UTILITY METER.
2 CT ENCLOSURE.
3 PANEL 'L'.
4 GRINDER CONTROL PANEL
5 AUTOMATIC TRANSFER SWITCH.
6 MAIN DISTRIBUTION PANEL 'MDP'.
7 VFD - 15 HP.
8 VFD - 110 HP.
9 AERIGATOR. PROVIDE WITH MANUFACTURER'S CABLE INCLUDING POWER AND TEMPERATURE SHUTDOWN WIRING.
10 PLC.
11 HEADWORKS MOTOR CONTROL PANEL
12 SEE ODOR CONTROL UNIT DETAIL 5 / E-505
13 TRANSFORMER.
14 CLASSIFIED TRANSITION. SEE DETAIL 9 / E-502.
15 FLOW METER.
16 LEVEL METER. HYDRORANGER LT500 LEVEL TRANSMITTER
17 GENERATOR.
18 EQUIPMENT ACCESS HATCH.
19 ODOR CONTROL UNIT DISCONNECT. SEE ONE-LINE DIAGRAM.
20 AERIGATOR SOFT START
21 SEE MOTOR CONNECTION DETAIL.
22 CRANE HOIST DISCONNECT. SEE ONE-LINE DIAGRAM.
23 MOUNT AT 6" ABOVE SINK AND TABLE TOP.
24 50 / 2 WELDER RECEPTACLE.
25 TO UTILITY POLE-MOUNT TRANSFORMER.
26 TO GENERATOR.
27 ODOR CONTROL UNIT.
28 SERVICE DISCONNECT, SEE ONE-LINE DIAGRAM.
29 NOT USED
30 HEADWORKS COMBUSTIBLE GAS ALARM PANEL.
31 MOUNT THE DOOR MOTOR AND CONTROLS ON THE OUTSIDE OF THE BUILDING
32 ROLL UP DOOR MOTOR, UNCLASSIFIED WHEN INSTALLED OUTDOORS
33 ROLL UP DOOR CONTROL, UNCLASSIFIED WHEN INSTALLED OUTDOORS
34 SCREEN MOTOR







1 EP101 MAIN LEVEL POWER PLAN
SCALE: 1/4"=1'-0"
5 0 10

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
04/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS
HEATH Engineering Company

DESIGNED RJH	3				
DRAFTED KGM	2				
CHECKED RJH	1				
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.


SCALE .


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
TOP FLOOR POWER PLAN

SHEET EP101
126.42.300

I:\26058\01 - DWG\ELEC\SHEET\26058 - EP-101.dwg, 4/19/2024 5:01:59 PM, Heath Engineering co\GJE





1 / EP102 **LOWER LEVEL GROUNDING PLAN**

SCALE: 1/4"=1'-0"

5 0 10

N

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
04/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED RJH	3		·		
DRAFTED KGM	2				
CHECKED RJH	1				
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE ·

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
DRY PIT GROUNDING PLAN


SHEET EP102


126.42.300

I:\2008501 - DWG\ELEC\SHEET\20658 - EP-102.dwg, 4/19/2024 5:02:03 PM, Heath Engineering co\CJE

DRAWING NOTES

1. AUTOMATIC TRANSFER SWITCH
2. PLC
3. TRANSFORMER
4. GENERATOR
5. EQUIPMENT ACCESS HATCH
6. THIS UFER GROUND IS ESTABLISHED IN THE LOWER FOOTING. SHOWN HERE FOR REFERENCE. SEE LOWER LEVEL GROUNDING PLAN.
7. SERVICE DISCONNECT
8. TO LIGHTNING PROTECTION OF BOTH BUILDINGS.





1 EP103 MAIN LEVEL GROUNDING PLAN
SCALE: 1/4"=1'-0"
5 0 10
N

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
09/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED RJH	3		·		
DRAFTED KGM	2				
CHECKED RJH	1				
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE ·


SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
TOP FLOOR GROUNDING PLAN

SHEET EP103

126.42.300

I:\2005801 - DWG\ELEC\SHEET\20058 - EP-103.dwg, 4/19/2024 5:02:06 PM, Heath Engineering co/GJE





1 EP104 **ROOF LIGHTNING PROTECTION PLAN**

SCALE: 1/4"= 1'-0"

5 0 10

N

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
04/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED RJH	3		·		
DRAFTED KGM	2				
CHECKED RJH	1				
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE ·

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
LIGHTNING PROTECTION PLANS


SHEET EP104


126.42.300

I:\2005800 - DWG\ELEC\SHEET\20058 - EP-104.dwg, 4/19/2024 5:02:09 PM, Heath Engineering co\GJE

DRAWING NOTES

1. FROM SWITCH AT UPPER LEVEL TOP OF STAIRS.
2. MOUNT AT 8'-0" A.F.F. TYPICAL OF ALL PIT LIGHTS.
3. FROM LIGHTING CIRCUIT ABOVE.
4. MOUNT AT 8'-0" MINIMUM ABOVE STAIR HEIGHT.





1 / EL100 **LOWER LEVEL LIGHTING PLAN**

SCALE: 1/4" = 1'-0"

5 0 10

N

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
04/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED RJH	3				
DRAFTED KGM	2				
CHECKED RJH	1				
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE .

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
LOWER LEVEL LIGHTING PLANS


SHEET EL100

126.42.300

I:\2005801 - SWG\ELEC\SHEET\200558 - EL-100.dwg, 4/19/2024 5:01:48 PM, Heath Engineering cox\GIE

DRAWING NOTES

1. POWER AND SWITCH FOR LOWER LEVEL.
2. CLASSIFIED TRANSITION REQUIRED AT WALL PENETRATION.
3. TO LIGHT FIXTURE BELOW.



1 / EL101 MAIN LEVEL LIGHTING PLAN

SCALE: 1/4"=1'-0"

5 0 10

N

ROBERT J. HILLYER # 11573207-2202 PROFESSIONAL ENGINEER 04/19/2024 STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED RJH	3		·		
DRAFTED KGM	2				
CHECKED RJH	1				
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE ·


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
UPPER FLOOR LIGHTING PLANS

SHEET EL101


126.42.300

I:\26085\01 - DWG\ELEC\SHEET\26058 - EL-101.dwg, 4/19/2024 5:01:52 PM, Heath Engineering co\GJE



UNDERGROUND CONDUIT WALL SEAL OR WASHDOWN FLOOR


SCALE: NONE — 6 / E-501




VERTICAL CONDUIT **HORIZONTAL CONDUIT**

TYPICAL CONDUIT SEAL DAMMING AND POURING

SCALE: NONE — 3 / E-501




SECTION A-A



HOUSEKEEPING CURB REQUIRED AT ALL INTERIOR WALL LOCATIONS FOR SINGLE AND MULTIPLE CONDUIT RISERS. CONDUIT RISERS SHALL BE COUPLED SO THAT SINGLE CONDUITS ARE SIX FEET APART MINIMUM.


CONCRETE HOUSEKEEPING CURB DETAIL

SCALE: NONE — 4 / E-501




DUCT BANK DETAIL

SCALE: NONE — 1 / E-501



FLOW METER GROUND RING CONNECTION DETAIL


SCALE: NONE — 7 / E-501



CONDUIT MARKING SYSTEM


SCALE: NONE — 8 / E-501

TYPICAL OF ALL CONDUITS



ELECTRIC UNIT HEATER CONTROL DIAGRAM

SCALE: NONE — 5 / E-501



EXISTING WALL/DRY FLOOR PENETRATIONS

SCALE: NONE — 2 / E-501

PROFESSIONAL ENGINEER # 11573207-2202 ROBERT J. HILLYER 04/19/2024 STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED RJH	3		·		
DRAFTED KGM	2				
CHECKED RJH	1				
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE ·


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
DETAILS

SHEET E–501

126.42.300

I:\2008501 - DWG\ELEC\SHEET\20658 - E-501.dwg, 4/19/2024 5:00:51 PM, Heath Engineering.ctb/GJE




TOP VIEW

CONDUIT ATTACHMENT TO HANDRAIL

8 / E-502


SCALE: NONE
TYPICAL




CLASSIFIED TRANSITION DETAIL

9 / E-502

SCALE: NONE
TYPICAL



MOUNTING DETAIL




NOTES:
1. ALL HARDWARE STAINLESS STEEL INCLUDING BELLVILLES COAT ALL SURFACE WITH KOPR-SHIELD BEFORE MATING.
2. FOR GROUND BOND TO STEEL ONLY: INSERT A TOOTH WASHER BETWEEN LUG AND STEEL, COAT ALL SURFACES WITH KOPR-SHIELD.
3. ALL HOLES ARE COUNTERSUNK 1/16".

GROUND BAR

6 / E-502


SCALE: NONE



CONDUIT SUPPORT DETAIL

7 / E-502


SCALE: NONE
TYPICAL



WALL HUNG FIXTURE MOUNTING DETAIL

3 / E-502


SCALE: NONE
TYPICAL OF ALL WALL HUNG FIXTURES



FLUSH CONDUIT TERMINATION

4 / E-502


SCALE: NONE
TYPICAL



VFD GROUNDING DIAGRAM

5 / E-502

SCALE: NONE




NOTES:
1. ALL LETTERS TO BE 1/4" UNLESS NOTED OTHERWISE.
2. ALL NAMEPLATES TO BE MOUNTED ON THE VERTICAL CENTERLINE OF THE CUBICAL OR DEVICE.
3. ATTACH ALL NAMEPLATES WITH STAINLESS STEEL SCREWS.
4. PROVIDE BLANK NAMEPLATES FOR ALL SPARE AND FUTURE DEVICES.

NAMEPLATE DETAIL

1 / E-502

SCALE: NONE
TYPICAL OF ALL EQUIPMENT



CONDUIT SUPPORT DETAIL

2 / E-502

SCALE: NONE
TYPICAL

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
04/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS	HEATH Engineering Company	DESIGNED RJH	3				SCALE .
		DRAFTED KGM	2				
		CHECKED RJH	1				
		DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY APVD.	


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
DETAILS


SHEET E-502

126.42.300


I:\2008\801 - DWG\ELEC\SHEET\2008 - E-502.dwg, 4/19/2024 5:00:54 PM, Heath Engineering co\GJE




CONCRETE SLAB



CONCRETE WALL LOCATIONS



SINGLE CONDUIT PENETRATION FOR ABOVE GRADE PENETRATIONS ONLY




CONCRETE SLAB WET LOCATIONS

TYPICAL ABOVE GROUND CONDUIT PENETRATIONS FOR NEW WALLS/FLOORS

3 / E-503


SCALE: NONE



CONDUIT SUPPORT

1 / E-503

SCALE: NONE
TYPICAL




NOTES:

1. PROVIDE LISTED GROUNDING TYPE CONNECTORS WITH LUGS AND EXTERNAL BONDING JUMPER WHEN CIRCUITS ARE RATED 20 AMPS OR MORE FOR 1/2", MORE THAN 60 AMPS FOR 3/4" THROUGH 1-1/4", AND FOR 1-1/2" AND LARGER WERE REQUIRED FOR GROUNDING.
2. INSULATED BUSHING SHALL BE REQUIRED FOR CONDUCTORS #4 OR LARGER.

TYPICAL FLEXIBLE CONDUIT CONNECTION DETAIL

5 / E-503


SCALE: NONE



TYPICAL MOTOR LEAD TERMINATION

4 / E-503

SCALE: NONE
TYPICAL



EQUIPMENT GROUNDING CONNECTION

2 / E-503

SCALE: NONE
TYPICAL

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
04/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company


DESIGNED RJH	3		.			SCALE
DRAFTED KGM	2					.
CHECKED RJH	1					
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.	

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
DETAILS


SHEET
E-503
126.42.300

I:\2005801 - DWG\ELEC\SHEET\2005S - E-503.dwg, 4/19/2024 5:00:57 PM, Heath Engineering csvGJE




GAS SENSOR AND TRANSMITTER DETAIL

NO SCALE — 6 / E-504



CONDUIT PLACEMENT


SCALE: NONE
TYPICAL — 4 / E-504



NOTES:
1. IN CORROSIVE AREAS PROVIDE STAINLESS STEEL U-CHANNEL.
2. OMIT POST BASE WHEN MOUNTING TO SIDE OF ABOVE GRADE STRUCTURE.
3. PROVIDE HARDWARE OF SAME MATERIAL AS U-CHANNEL.


JUNCTION BOX MOUNTING DETAIL

SCALE: NONE — 1 / E-504




MOTOR COMBINATION DISCONNECT STARTER DETAIL

SCALE: NONE — 5 / E-504



BONDING LUG

SCALE: NONE — 2 / E-504



CONDUIT RISER

SCALE: NONE
TYPICAL — 3 / E-504

ROBERT J. HILLYER
11573207-2202
04/19/2024
STATE OF UTAH
PROFESSIONAL ENGINEER

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED RJH	3				
DRAFTED KGM	2				
CHECKED RJH	1				
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.


SCALE: .

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
DETAILS


SHEET
E-504
126.42.300

I:\2005\01 - DWG\ELEC\SHEET\2005S - E-504.dwg, 4/19/2024 5:01:00 PM, Heath Engineering csvGJE




TRENCH DETAIL-ROADWAY RESTORATION

SCALE: NONE — 6 / E-505



HEADWORKS TRANSDUCER MOUNTING DETAIL


SCALE: NONE — 3 / E-505



(1) FOR INSTALLATION OF FLOATS WITHOUT A CONCRETE DECK CONSTRUCT A 3/8"x12"x8" SS PLATE SUPPORT ANCHORED TO WALL AT MINIMUM 4 PLACES. WELD A 3/8"x6"x12" SS GUSSET TO THE BOTTOM OF PLATE SUPPORT.


LEVEL FLOAT MOUNTING DETAIL

SCALE: NONE — 1 / E-505




TRENCH DETAIL-SIDEWALK RESTORATION

SCALE: NONE — 7 / E-505




FLOOD FLOAT SWITCH INSTALLATION

NO SCALE — 4 / E-505




TRENCH DETAIL-ROADWAY RESTORATION

SCALE: NONE — 8 / E-505



ODOR CONTROL UNIT DETAIL

NO SCALE — 5 / E-505



AERIGATOR LEAD MOUNTING DETAIL

SCALE: NONE — 2 / E-505

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
04/01/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS	HEATH Engineering Company	DESIGNED RJH	3		·		
		DRAFTED KGM	2				
		CHECKED RJH	1				
		DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE: ·


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
DETAILS

SHEET E-505

126.42.300


I:\2005801 - DWG\ELEC\SHEET\200505 - E-505.dwg, 4/19/2024 5:01:04 PM, Heath Engineering co\GJE



PRESSURE GAUGE OR PRESSURE SWITCH WITH ANNULAR SEAL

5 E-506


NO SCALE



EQUIPMENT HAND OFF REMOTE SWITCH

6 E-506


NO SCALE OPEN / CLOSE AND POSITION POT SWITCHERS SIMILAR



TERMINAL BLOCK CLEARANCE DETAIL

7 E-506

NO SCALE




NOTE: SEE SPECIFICATION SECTIONS 15183 AND 17100

PRESSURE GAUGE AND PRESSURE SWITCH/PIT

3 E-506


NO SCALE (CLEAN WATER ONLY)



PRESSURE GAUGE AND PRESSURE SWITCH WITH ANNULAR SEAL

4 E-506

NO SCALE




PRESSURE GAUGE OR PRESSURE SWITCH WITH DIAPHRAGM SEAL

1 E-506

NO SCALE

NOTE:
SEE SPECIFICATIONS:



PRESSURE GAUGE AND PRESSURE SWITCH WITH DIAPHRAGM SEAL

2 E-506

NO SCALE

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
04/19/2024
STATE OF UTAH

DESIGNED RJH	3		.			SCALE .
DRAFTED KGM	2					
CHECKED RJH	1					
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.	

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
DETAILS

SHEET E-506


126.42.300

I:\126.42.300\01 - DWG\ELEC\SHEET\126.42.300 - E-506.dwg, 4/19/2024 5:01:07 PM, Heath Engineering co\GJE




MOUNTING HEIGHTS FOR ELECTRICAL DEVICES

SCALE: NONE — 6 / E-507




CABLE TO ROD CONNECTION DETAIL

SCALE: NONE
TYPICAL — 3 / E-507




PUMP MOTOR LEAD MOUNTING DETAIL

SCALE: NONE — 1 / E-507
(MOTOR MONITORING CABLE SIMILAR)




DIN RAIL MOUNTING DETAIL

NO SCALE — 7 / E-507



GROUNDING GRID TIE-IN


SCALE: NONE
TYPICAL — 4 / E-507



NOTE:
BOLTS SHALL BE INSERTED IN BOLT HOLES BEFORE CONNECTOR IS EMBEDDED.

GROUND INSERT DETAIL

SCALE: NONE
TYPICAL OF ALL INTERIOR EQUIPMENT GROUNDING — 5 / E-507



NOTE:
SEE SPECIFICATION SECTIONS 15183 AND 17100

PRESSURE GAUGE OR PRESSURE SWITCH

SCALE: NONE — (CLEAN WATER ONLY) — 2 / E-507

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
04/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED RJH	3					
DRAFTED KGM	2					
CHECKED RJH	1					
DATE MAY 26, 2022	NO.	DATE	REVISIONS		BY	APVD.


SCALE

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
DETAILS


SHEET
E-507
126.42.300

I:\2008\801 - DWG\ELEC\SHEET\20058 - E-507.dwg, 4/19/2024 5:01:10 PM, Heath Engineering co\GJE




7 E-508 **TYPICAL DOWNLEAD DETAIL**
SCALE: NONE

NO. 40-22618BM, BI-METAL
THRU-ROOF/WALL CONNECTOR




5 E-508 **THRU-ROOF/WALL CONNECTOR**
SCALE: NONE

NO. 40-206C, COPPER ONE
BOLT PARALLEL SPLICER




USE TO SPLICE MAIN
SIZE CONDUCTOR TO
MAIN SIZE CONDUCTOR


6 E-508 **CABLE CONNECTOR**
SCALE: NONE



2 E-508 **GROUND ROD DETAIL**
SCALE: NONE



3 E-508 **STACK AIR TERMINAL**
SCALE: NONE




4 E-508 **RIDGE AIR TERMINAL**
SCALE: NONE

NO. 40-208C, COPPER
ONE BOLT PARALLEL SPLICER




USE TO SPLICE MAIN
SIZE CONDUCTOR TO
BONDING CONDUCTOR


NO. 40-216CT,
TIN PLATED BRONZE
BONDING LUG




NO. 40-2316C, COPPER
STRAP TYPE PIPE CLAMP



NO. 40-152C, COPPER
U-BOLT PIPE CLAMP
NO. 40-354C, COPPER
U-BOLT PIPE CLAMP



NO. 40-228G, GALVANIZED
ROOF FLASHING



8 E-508 **MISCELLANEOUS DETAILS**
SCALE: NONE

LEGEND


- AIR TERMINAL AND BASE ASSEMBLY
- MECHANICAL CONNECTION
- THRU-ROOF CONNECTION
- THRU-WALL CONNECTION
- COPPER LIGHTNING PROTECTION CONDUCTOR
- ALUMINUM LIGHTNING PROTECTION CONDUCTOR
- GROUND ROD
- MISCELLANEOUS BOND

GENERAL CONSTRUCTION NOTES

1. THIS DRAWING IS INTENDED FOR USE AS A CONSTRUCTION DOCUMENT. FIELD VERIFY ACTUAL CONDITIONS PRIOR TO CONSTRUCTION. CONTACT ENGINEER TO CLARIFY ANY DISCREPANCIES.

GENERAL BONDING NOTES


1. TYPICAL BODIES OF CONDUCTANCE AS NOTED BELOW. USE FULL SIZE CONDUCTOR AND APPROPRIATE FITTING SHOWN FOR CONNECTION.
2. BONDING CONNECTIONS AND FITTINGS SHOWN ARE TYPICAL EXAMPLES. MAKE ALL CONNECTIONS REQUIRED TO MEET CODES AS NOTED BELOW. ADJUST FITTING TYPE AS REQUIRED TO SUIT FIELD CONDITIONS.
3. TYPICAL BODIES OF INDUCTANCE AS NOTED BELOW. USE SECONDARY SIZE (SMALLER) CONDUCTOR AND APPROPRIATE FITTING SHOWN FOR CONNECTION.
4. (PLUMBING STACK) REQUIRES BONDING WITH MAIN SIZE CABLE ONLY IF WITHIN 6'-0" (1,828mm) OF LIGHTNING PROTECTION SYSTEM.



GENERAL INSTALLATION NOTES

1. LOCATE AIR TERMINALS AS SHOWN. TAKE CARE TO INSURE THAT ALL POINTS ARE WITHIN 2'-0" (609mm) OF OUTSIDE BUILDING EDGE, OUTSIDE CORNERS, RIDGE ENDS, AND THAT MAX SPACING DOES NOT EXCEED 20'-0" (6,096mm), AND THAT MIN PROJECTION ABOVE OBJECT PROTECTED IS 10" (254mm); POINTS PROJECTING 24" (609mm) MAY BE SPACED @ 25'-0" (7,520mm) MAX.
2. MAINTAIN HORIZONTAL OR DOWNWARD COURSING OF MAIN CONDUCTOR. INSURE THAT ALL BENDS HAVE AT LEAST AN 8" (203mm) RADIUS AND DO NOT EXCEED 90 DEGREES.
3. ATTACH ALL EXPOSED ROOF, DOWN LEAD AND BONDING CABLES AT 3'-0" (914mm) ON CENTER MAX. VERIFY COMPATIBILITY OF ADHESIVE ON MEMBRANE ROOF APPLICATIONS PRIOR TO INSTALLATION.
4. GROUND ELECTRODES SHALL BE INSTALLED AS SHOWN, BUT IN NO INSTANCE SHALL THEY BE LESS THAN 1'-0" (304mm) BELOW GRADE AND 2'-0" (609mm) FROM FOUNDATION WALL. DRIVEN RODS SHALL PENETRATE THE EARTH AT LEAST 10'-0" (3,048mm).
5. BOND TO WATER SERVICE AND OTHER PIPING SYSTEMS AS SHOWN AND AS REQUIRED BY CODE.
6. INTERCONNECT LIGHTNING PROTECTION GROUND TO ELECTRIC, TELEPHONE, AND OTHER BUILDING GROUND SYSTEMS AS SHOWN OR AS REQUIRED BY CODE.
7. SYSTEM SHALL BE INSTALLED AS REQUIRED TO INSURE PROPER CODE COMPLIANCE AND SYSTEM CERTIFICATION. ANY MAJOR INSTALLATION VARIANCE SHALL BE RESUBMITTED FOR APPROVAL.
8. RECORD DOCUMENTS SHALL BE SUBMITTED IN ACCORDANCE WITH CERTIFICATION PROCEDURES.
9. ALL MATERIALS TO BE UNDERWRITER'S LABORATORIES APPROVED WITH "A" LABELS ON CONDUCTORS @ 10'-0" (3,048mm) INTERVALS AND "B" LABELS ON ALL AIR TERMINALS.
10. COMPLETED INSTALLATION SHALL BEAR U.L. MASTER LABEL "C" TO BE SECURED BY SYSTEM INSTALLER PER UL96A.
11. INSTALLATION SHALL BE MADE UNDER THE SUPERVISION OF AN L.P.I. CERTIFIED MASTER INSTALLER.

NO. 40-223C, BRONZE
FLANGE BONDING PLATE



1 E-508 **STEEL CONNECTION**
SCALE: NONE

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J.
HILLYER
09/11/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED RJH	3		·			SCALE ·
DRAFTED KGM	2					
CHECKED RJH	1					
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.	

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
DETAILS

SHEET
E-508
126.42.300

I:\2005801 - DWG\ELEC\SHEET\200S8 - E-508.dwg, 4/19/2024 5:01:15 PM, Heath Engineering co\GJE

DRAWING NOTES

1. COMBINATION FUSED SWITCH (30 / 3 / FUSE PER NAMEPLATE / 3R / HD / 600) AND SIZE 00 MAGNETIC STARTER WITH H-O-A, SOLID STATE
2. DISCONNECT AT GRINDER VAULT. 30 / 3 / NF / 3R / 600 / HD.
3. DISCONNECT AT UNIT. 30 / 3 / FUSE PER NAME PLATE / 3R / 600 / HD.
4. DISCONNECT ON BUILDING EXTERIOR WALL IN SIGHT OF ODOR CONTROL UNIT OUT OF CLASSIFIED AREA. 30 / 3 / FUSE PER NAMEPLATE / 3R / 600 / HD.
5. CRANE HOIST DISCONNECT 60 / 3 / FUSE PER NAMEPLATE / 1 / 250 / HD WIRING FOR CRANE HOIST SHALL FOLLOW MANUFACTURER'S RECOMMENDATION.
6. DISCONNECT OUTDOORS OUTSIDE OF CLASSIFIED AREA NEAR ROLL UP DOOR. 30 / 3 / NF / 3R / 600 / HD



ELECTRICAL ONE-LINE DIAGRAM

SCALE: NONE

PROFESSIONAL ENGINEER # 11573207-2202 ROBERT J. HILLYER 04/19/2024 STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS	HEATH Engineering Company	DESIGNED RJH	3				SCALE
		DRAFTED KGM	2				
		CHECKED RJH	1				
		DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY APVD.	


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
ONE-LINE DIAGRAM

SHEET E-601


126.42.300

I:\2005801 - DWG\ELEC\SHEET\2005S - E-601.dwg, 4/19/2024 5:01:31 PM, Heath Engineering co/GJE



HEADWORKS GAS ALARM PANEL CONTROL DIAGARM

SCALE: NONE



PRIMARY SEWAGE PUMPS VFD WIRING DIAGRAM

SCALE: NONE — TYPICAL OF: 5 LIFT PUMPS

GENERAL NOTES

1. PROVIDE AND SIZE OVER CURRENT DEVICES PER THE UTILIZATION EQUIPMENT MANUFACTURERS RECOMMENDATIONS.
2. DIAGRAMS ARE INTENDED TO REFLECT THE GENERAL CONTROL STRATEGY. ACTUAL CIRCUITRY WILL VARY FOR THE SPECIFIC EQUIPMENT SUPPLIED. THE NUMBER AND THE TYPE OF DEVICES SHALL BE FURNISHED AS REQUIRED FOR THE PROPER OPERATION OF THE EQUIPMENT.

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
04/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED RJH	3		.		
DRAFTED KGM	2				
CHECKED RJH	1				
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE: .


SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
CONTROL DIAGRAMS

SHEET E-602


126.42.300

I:\2005801 - DWG\ELEC\SHEET\2005S - E-602.dwg, 4/19/2024 5:01:42 PM, Heath Engineering co/GJE




TYPICAL ANALOG INPUT/OUTPUT DIAGRAM

SCALE: NONE




TYPICAL DISCRETE OUTPUT DIAGRAM


SCALE: NONE



TYPICAL DISCRETE INPUT DIAGRAM

SCALE: NONE





GENERAL NOTES

1. PROVIDE AND SIZE OVER CURRENT DEVICES PER THE UTILIZATION EQUIPMENT MANUFACTURERS RECOMMENDATIONS.
2. DIAGRAMS ARE INTENDED TO REFLECT THE GENERAL WIRING STRATEGY. ACTUAL CIRCUITRY MAY VARY FOR THE SPECIFIC EQUIPMENT SUPPLIED. THE NUMBER AND THE TYPE OF DEVICES SHALL BE FURNISHED AS REQUIRED FOR THE PROPER OPERATION OF THE EQUIPMENT.
3. EACH DC POWER SUPPLY SHALL BE SIZED TO OPERATE AT 60% OF CAPACITY MAXIMUM WHILE CARRYING THE ENTIRE PLC/RTU ENCLOSURE DC LOAD.
4. ADJUST THE DC POWER SUPPLY VOLTAGES FOR REDUNDANT APPLICATION AS RECOMMENDED BY THE MANUFACTURER.
5. SEE SPECIFICATIONS FOR CONTROL NARRATIVE

PLC/RTU ENCLOSURE POWER WIRING DIAGRAM

SCALE: NONE

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
04/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED RJH	3		.		
DRAFTED KGM	2				
CHECKED RJH	1				
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE .

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
CONTROL DIAGRAMS

SHEET E-603

126.42.300

T:\2065\501 - DWG\ELEC\SHEET\2065S - E-603.dwg, 4/19/2024 5:01:45 PM, Heath Engineering cowGJE

PRIMARY ELEMENT SYMBOLS

- PARSHALL FLUME
- ORIFICE PLATE
- FLOW TUBE
- ROTAMETER
- ULTRASONIC FLOWMETER
- ELECTROMAGNETIC FLOWMETER
- PROPELLER METER
- LEVEL (BUBBLE TUBE)
- LEVEL (CONDUCTIVE)
- DM — DENSITY METER
- PRESSURE SENSING ANNULAR RING TYPE SEAL
- AE DO — DO SENSOR
- AE ORP — ORP SENSOR
- AE pH — pH SENSOR
- AIT DO — DO ANALYZER
- AIT ORP — ORP ANALYZER
- AIT pH — pH ANALYZER
- LS — FLOAT SWITCH
- HS HOA — HAND SWITCH
- PRESSURE SENSING DIAPHRAGM SEAL, DISK TYPE
- K BEACON — BEACON
- YL G STOP — INDICATING LIGHT
- FIT — INSERTION TYPE MASS FLOW METER
- FIT MASS — MASS FLOW METER ANNUBAR TYPE
- LE — ULTRASONIC OR RADAR LEVEL TRANSDUCER

VALVE SYMBOLS

- GATE VALVE
- E — MOTOR OPERATED GATE VALVE
- K — KNIFE GATE VALVE
- BUTTERFLY VALVE
- E — MOTOR OPERATED BUTTERFLY VALVE
- GLOBE VALVE
- BALL VALVE
- V — VEE-BALL VALVE
- PLUG VALVE
- E — MOTOR OPERATED PLUG VALVE
- SEAT PORT ECCENTRIC PLUG VALVE
- E — MOTOR OPERATED ECCENTRIC PLUG VALVE
- DIAPHRAGM VALVE
- PINCH VALVE
- E — MOTOR OPERATED PINCH VALVE
- NEEDLE VALVE
- SWING CHECK VALVE
- S — SOLENOID VALVE
- DOUBLE LEAF CHECK VALVE
- RPBP — BACKFLOW PREVENTER (REDUCED PRESSURE ZONE TYPE)
- BALL CHECK VALVE
- MULTI-PORT VALVES (BALL VALVE SHOWN, FOR OTHER VALVE TYPES, APPROPRIATE VALVE SYMBOL SHOWN.) ARROWS INDICATE FLOW PATTERN. SEAT PORTS ARE IMPLIED BY INDICATED FLOW PATTERN.
- TELESCOPING VALVE
- S — SAMPLE TAP
- MUD VALVE
- PRESSURE RELIEF VALVE
- AIR AND/OR VACUUM RELEASE VALVE
- REGULATED SIDE PRESSURE CONTROL VALVE
- AIR RELEASE VALVE (ARV) OR COMBINATION AIR-VACUUM RELIEF VALVE (CAV)
- RUPTURE DISK
- E — MOTOR OPERATED SLEEVE VALVE
- SURGE ANTICIPATOR VALVE
- IPS CORP. STOP
- PVC DIFFUSER W/ IPS CORP. STOP

MISCELLANEOUS MECHANICAL SYMBOLS

- M — FLOCCULATOR OR SUBMERSIBLE MIXER
- M — AERATOR
- M — MOTOR
- DIFFUSERS
- CL2 — CHLORINE TANK
- FILTER
- SILENCER
- INLET SILENCER AND FILTER

P&ID LINE TYPES

- MAJOR PROCESS PIPING OR FLOW CHANNEL
- SECONDARY PROCESS PIPING
- MISCELLANEOUS PIPING
- EXISTING OR FUTURE MAJOR PROCESS PIPING OR FLOW CHANNEL
- EXISTING OR FUTURE SECONDARY PROCESS PIPING
- EXISTING OR FUTURE MISCELLANEOUS PIPING
- PROCESS LINES CROSSING (NOT CONNECTED)
- FLOW ARROW FOR PROCESS PIPING
- EXISTING PIPING OR EQUIPMENT OR FUTURE PIPING OR EQUIPMENT
- ? ? — PROCESS OR SIGNAL LINE GOING TO ANOTHER SHEET
- ? ? — PROCESS OR SIGNAL LINE FROM ANOTHER SHEET (MATCH LETTERS)
- -----L-----L----- HYDRAULIC SIGNAL
- // // PNEUMATIC SIGNAL
- ---------- DISCRETE SIGNAL
- ---------A--------- ANALOG SIGNAL
- ---------P--------- PULSE SIGNAL
- INTERNAL SYSTEM SIGNAL LINK (SOFTWARE OR DATA LINK)
- ELECTRICAL DIRECTION ARROW
- SIGNAL CONNECTION POINT
- PACKAGED SYSTEMS

PUMP AND COMPRESSOR SYMBOLS

- XX — CENTRIFUGAL PUMP (DRY PIT)
- XX — CENTRIFUGAL WET PIT PUMP
- XX — PERISTALTIC CHEMICAL FEED PUMP
- XX — DIAPHRAGM PUMP
- XX — GEAR PUMP OR BLOWER (POSITIVE DISPLACEMENT)
- XX — METERING PUMP WITH MANUAL STROKE CONTROL
- XX — PROGRESSIVE CAVITY PUMP
- XX — AIR OPERATED DOUBLE DIAPHRAGM PUMP
- XX — PISTON PUMP
- XX — GEAR PUMP OR BLOWER
- XX — PROGRESSING CAVITY PUMP
- XX — COMPRESSOR (CENTRIFUGAL)
- XX — COMPRESSOR (PISTON)
- XX — ROTARY LOBE PUMP
- XX — BLOWER OR FAN (CENTRIFUGAL)
- XX — VERTICAL TURBINE PUMP

NOTE: XX:AS ADJUSTABLE SPEED
CS-1 CONSTANT SPEED (SINGLE SPEED)
CS-2 CONSTANT SPEED (TWO SPEED)

PROCESS DEVICE SYMBOLS

- SIGHT GLASS
- PRESSURE REGULATOR
- DIAPHRAGM
- CARTRIDGE FILTER
- AIR FILTER
- DIAPHRAGM WITH POSITIONER
- STRAINER
- PULSATION DAMPENER
- CL2 FLOW METER
- DRAIN
- WATER LEVEL
- SAMPLER
- CAP OR PLUG
- QUICK DISC. COUPLING
- EJECTOR
- BLIND FLANGE
- EXPANSION JOINT
- WEIGHT SCALE

GATE SYMBOLS

- SLIDE GATE
- BUTTERFLY GATE
- SLUICE GATE
- FLAP GATE
- STOP GATE
- WEIR GATE (DOWNWARD OPENING)

ACTUATOR SYMBOLS

- P — PNEUMATIC
- E — ELECTRIC WITH POSITIONER
- S — SOLENOID
- P E — PNEUMATIC WITH POSITIONER
- E — ELECTRIC
- H — HYDRAULIC

NOTE: ON LOSS OF PRIMARY POWER (PNEUMATIC OR ELECTRICAL)
XX — FO = FAIL OPEN; FC = FAIL CLOSED; FLP = FAIL LAST POSITION

MISCELLANEOUS ELECTRICAL SYMBOLS

- 120/1 — VOLTAGE & POWER SUPPLY PHASE(S) AS NOTED
- ISR — INTRINSICALLY SAFE RELAY
- PLUG
- E E — CONVERTER
- S — SMOKE DETECTOR
- DIESEL GENERATOR

PROFESSIONAL ENGINEER # 11573207-2202 ROBERT J. HILLYER 04/19/2024 STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED RJH	3				
DRAFTED KGM	2				
CHECKED RJH	1				
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE .

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
P & ID SYMBOL LEGEND

SHEET I-01

126.42.300


I:\2305801 - DWG\ELEC\SHEET\20058 - I-01.dwg, 4/19/2024 5:02:15 PM, Heath Engineering co\GJE

ISA INSTRUMENT IDENTIFICATION TABLE


	FIRST LETTERS		SUCCEEDING LETTERS		
	MEASURED OR INITIATING VARIABLE	MODIFIER	READOUT OR PASSIVE FUNCTION	OUTPUT FUNCTION	MODIFIER
A	ANALYZER		ALARM		AUTO
B	BURNER, COMBUSTION				
C	CONDUCTIVITY			CONTROL	CLOSED
D	DENSITY	DIFFERENTIAL			
E	VOLTAGE		ELEMENT		
F	FLOW	RATIO			
G	GAUGE		GLASS, VIEWING DEVICE		
H	HAND				HIGH
I	CURRENT		INDICATE		
J	POWER	SCAN			
K	TIME OR TIME SCHEDULE	TIME RATE OF CHANGE		CONTROL STATION	
L	LEVEL		LIGHT		LOW
M	MOTION OR MOISTURE				MIDDLE
N	INTRUSION				NORMAL
O	TORQUE		ORIFICE, RESTRICTION		OPEN
P	PRESSURE		POINT CONNECTION		STOP
Q	QUANTITY	INTEGRATE, TOTALIZE			
R	RADIATION		RECORD OR PRINT	RESET	RUN OR REMOTE
S	SPEED OR FREQUENCY	SAFETY		SWITCH	START
T	TEMPERATURE			TRANSMIT	
U	MULTIVARIABLE		MULTIFUNCTION	MULTIFUNCTION	MULTIFUNCTION
V	VIBRATION			VALVE, LOUVER	
W	WEIGHT OR FORCE		WELL		
X	MOTOR	X–AXIS	UNCLASSIFIED	UNCLASSIFIED	UNCLASSIFIED
Y	EVENT, STATE, OR PRESENCE	Y–AXIS		RELAY, COMPUTE, CONVERT	
Z	POSITION	Z–AXIS		DRIVER, ACTUATOR, FINAL CONTROL ELEMENT	

P&ID INTERFACE SYMBOLS

NOTE:
REFER TO ISA INSTRUMENT IDENTIFICATION TABLE FOR DEFINITION OF LETTERS BBB INSIDE THE BUBBLES. CCC REPRESENTS LOOP ID (IF USED). SEE ABBREVIATIONS LIST FOR SUPERSCRIPT AAA.



TAG NUMBERS AND ADDITIONAL DESIGNATIONS




ABBREVIATIONS

A	AMPERE OR AIR
AC	ALTERNATING CURRENT
AFD	ADJUSTABLE FREQUENCY DRIVE
AI	ANALOG INPUT
AIC	AMPS INTERRUPTING CAPACITY
AM	AUTO–MANUAL
ARV	AIR RELIEF VALVE
AO	ANALOG OUTPUT
AS	AIR SUPPLY
ATS	AUTOMATIC TRANSFER SWITCH
AUTO	AUTOMATIC
BFP	BELT FILTER PRESS
BR	BRINE SOLUTION
BW	BACKWASH
BWL	BOTTOM WATER LEVEL
CB	CIRCUIT BREAKER
CD	CYCLONE DRAIN
CL2	CHLORINE (TYPICAL: USE STANDARD CHEMICAL ELEMENT ABBREVIATION)
CNDT	CONDUCTIVITY
CP–X	CONTROL PANEL NO. X
CPM	CUSTOMER POWER MONITORING UNIT
CON	CONTACTOR
CSI	CYCLONE SEPARATOR INFLUENT
CU	COPPER, BARE
CV	CONTROL VALVE
CW	CYCLONE WASTE
DC	DIRECT CURRENT
DCS	DISTRIBUTED CONTROL SYSTEM
DI	DISCRETE INPUT
DO	DISCRETE OUTPUT OR DISSOLVED OXYGEN
DP	DIFFERENTIAL PRESSURE
DSW	DRUM SCREEN WASTE
DWG	DRAWING
E	VOLTAGE
ETM	ELAPSED TIME METER
ETMf	ELAPSED TIME METER (FAST SPEED)
ETMs	ELAPSED TIME METER (SLOW SPEED)
EOL	ELECTRONIC OVERLOAD
ES	EMERGENCY STOP
EXIST, (E)	EXISTING
FA	FOUL AIR
FC	FAIL CLOSED
FE	FINAL EFFLUENT
FLT	FILTER
FMR	FEEDER MANAGEMENT RELAY
FR	FORWARD–REVERSE
FVNR	FULL VOLTAGE NON–REVERSING
FW	FINISHED WATER
GAL	GALLONS
GCP	GENERATOR CONTROL PANEL
GND	GROUND
GPD	GALLONS PER DAY
GPH	GALLONS PER HOUR
GPM	GALLONS PER MINUTE
H, HI	HIGH
H2S	HYDROGEN SULFIDE
HMI	HUMAN MACHINE INTERFACE
I	CURRENT
ICR	INTERMITTENT CYCLE
IO	REACTOR INPUT/OUTPUT
IOE	INTERNAL – OFF – EXTERNAL
IS	INTERCHANGE SLUDGE
JB	JUNCTION BOX
L, LO	LOW
LAN	LOCAL AREA NETWORK
LC	LOOP CONTROLLER
LCP	LOCAL CONTROL PANEL
LEL	LOWER EXPLOSIVE LIMIT
M	MOTOR
MA	MANUAL/AUTO, MILLIAMPS
MC	MANUFACTURER CABLE
MCC	MOTOR CONTROL CENTER
MCP	MOTOR CIRCUIT PROTECTOR MAIN CONTROL INSTRUMENT PANEL
MFR(S)	MANUFACTURER(S)
MGD	MILLION GALLONS PER DAY
MGL	MILLIGRAMS PER LITER
MH	MANHOLE
ML	MIXED LIQUOR
MLR	MIXED LIQUOR RECYCLE
MLSS	MIXED LIQUOR SUSPENDED SOLIDS
MO	MOISTURE
MOD	MODULATED
MOG	MOTOR OPERATED GATE
MS	MOISTURE SWITCH
MTU	MASTER TELEMETRY UNIT
NADH	NICOTINAMIDE ADENINE DINUCLEOTIDE
NIA	NOT IN AUTO
NPW	NON–POTABLE WATER
NS	NITROGEN SUPPLY
NTU	TURBIDITY
OC	OPEN/CLOSE
OIT	OPERATOR INTERFACE TERMINAL
OL	OVERLOAD
ORP	OXYGEN REDUCTION POTENTIAL
OTA	OVER TORQUE ALARM
OTW	OVER TORQUE WARNING
P	PRESSURE
PD	PLANT DRAIN
PER	PERMISSIVE
PLC	PROGRAMMABLE LOGIC CONTROLLER
PNL	PANEL
PO	PULSE OUTPUT
POS	POSITION
POT	POTENTIOMETER
PPH	POUNDS PER HOUR
PPM	PARTS PER MILLION
PR	PAIR
PRES	PRESSURE
PRV	PRESSURE REDUCING VALVE
PSI	POUNDS PER SQUARE INCH
PV	PROCESS VARIABLE
PWR	POWER
RAS	RETURN ACTIVATED SLUDGE
RAW	RAW WATER
REM	REMOTE
RF	RADIO FREQUENCY
RIO	REMOTE INPUT/OUTPUT
RS	RAW SEWAGE, RUNNING STATUS
RSP	RAW SEWAGE PUMP
RST	RESET
RTU	REMOTE TELEMETRY UNIT
RUNf	RUN (FAST SPEED)
RUNs	RUN (SLOW SPEED)
SB	SLUDGE BLANKET
SCC	SCUM SECONDARY CLARIFIER
SE	SECONDARY EFFLUENT
SEQ	SERVICE ENTRANCE EQUIPMENT
SES	SERVICE ENTRANCE SECTION
SHC	SODIUM HYPOCHLORITE
SLC	SINGLE LOOP CONTROLLER
SLG	SLUICE GATE
SO2	SULFUR DIOXIDE
SOV	SOLENOID OPERATED VALVE
SP	SET POINT
SPC	SET POINT CONTROLLER
SPD	SPEED
SPR	SPARE
SSS	SOLID STATE STARTER (SOFT START)
T/M	TEMPERATURE AND/OR MOISTURE
TEMP	TEMPERATURE
TSS	TOTAL SUSPENDED SOLIDS
TWL	TOP WATER LEVEL
Tu	TURBIDITY
UG	UNDERGROUND
UW	UTILITY WATER
V	VOLT
V*	VENDOR EQUIPMENT
VCP	VENDOR CONTROL PANEL
VFD	VARIABLE FREQUENCY DRIVE
VTP	VERTICAL TURBINE PUMP
VIB	VIBRATION
W	WATT, WIRE
WAS	WASTE ACTIVATED SLUDGE
WS	WASTE SLUDGE

HAND SWITCH DESIGNATIONS

ES	EMERGENCY STOP
HOA	HAND – OFF – AUTO
HOR	HAND – OFF – REMOTE
HORA	HAND – OFF – REMOTE – AUTO
JOA	JOG – OFF – AUTO
JR	JOG REVERSE
LOAR	LOWER – OFF – AUTO – RAISE
LOR	LOCAL – OFF – REMOTE
LOS	LOCKOUT STOP
LR	LOCAL – REMOTE
OC	OPEN – CLOSE
OCA	OPEN – CLOSE – AUTO
OO	ON – OFF
OOA	ON – OFF – AUTO
OSC	OPEN – STOP – CLOSE
SS	START/STOP (MAINTAINED)
USD	UP/STOP/DOWN



HANSEN ALLEN & LUCE, Inc. ENGINEERS

HEATH Engineering Company

DESIGNED	RJH	3			
DRAFTED	KGM	2			
CHECKED	RJH	1			
DATE	MAY 26, 2022	NO.	DATE	REVISIONS	BY / APVD.

SCALE


SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
P & ID SYMBOL LEGEND

SHEET
I–02

126.42.300

I:\20085801 - DWG\ELEC\SHEET\20058 - I-02.dwg, 4/19/2024 5:02:18 PM, Heath Engineering co\GJE





1 / 1-100 LOWER LEVEL CONTROL PLAN

SCALE: 1/4"=1'-0"

5 0 10

N

DRAWING NOTES

1. ACCESS HATCH ABOVE
2. TO FLOW METER
3. TO PLC
4. PRESSURE SWITCH SHUTDOWN
5. TO CORRESPONDING VFD.
6. FLOOD SWITCH
7. SUMP PUMP WITH INTEGRAL FLOAT SWITCH
8. LEVEL TRANSMITTER COMPATIBLE WITH SCREEN MANUFACTURER. SEE SECTION.
9. TO HEADWORKS MOTOR CONTROL PANEL IN PUMP BUILDING VIA CLASSIFIED TRANSITION.
10. GAS DETECTOR. SEE SECTION.
11. TO GAS ALARM PANEL VIA CLASSIFIED TRANSITION
12. FLOOD FLOAT SWITCH
13. GRINDER TEMPERATURE SWITCH
14. TO GRINDER CONTROL PANEL VIA CLASSIFIED TRANSITION

GENERAL NOTES

A. ALL CONDUIT CHANGING CLASSIFIED ZONES REQUIRE A CLASSIFIED TRANSITION. CLASSIFIED TRANSITIONS MAY BE SHARED BY SIGNALS/POWER OF THE SAME TYPE GOING TO THE SAME DESTINATION.

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
09/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED RJH	3				
DRAFTED KGM	2				
CHECKED RJH	1				
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE .

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
DRY PIT CONTROL PLAN

SHEET I-100

126.42.300

I:\2068\01 - DWG\ELEC\SHEET\2068S -1-100.dwg, 4/19/2024 5:02:21 PM, Heath Engineering ca/GJE

GENERAL NOTES

A. ALL CONDUIT CHANGING CLASSIFIED ZONES REQUIRE A CLASSIFIED TRANSITION. CLASSIFIED TRANSITIONS MAY BE SHARED BY SIGNALS/POWER OF THE SAME TYPE GOING TO THE SAME DESTINATION.


B. PROVIDE (1) SPARE 1" CONDUIT BETWEEN EVERY ELECTRICAL DEVICE THAT HAS A CONTROL CONDUIT TO THE PLC. PROVIDE (2) SPARE 2" CONDUIT FROM THE GRINDER CONTROLLER TO SCREEN ROOM FOR ANY GRINDER SIGNALS THAT MAY BE REQUIRED.


DRAWING NOTES


25 PROVIDE PLC 120V POWER FROM NEW PLC CABINET TO SECONDARY INPUT OF DUAL INPUT UPS FOR PLC CABINET IN EXISTING BUILDING TO ENSURE EXISTING PLC HAS POWER ON GENERATOR CIRCUIT. MARK ON EXISTING PLC CABINET "CAUTION! THIS CABINET FED FROM MULTIPLE POWER SOURCES"

26 MODUBS 485 SIGNAL FOR FLOW TOTALIZER AND COMMUNICATIONS.


1 AUTOMATIC TRANSFER SWITCH.
2 MAIN DISTRIBUTION PANEL 'MDP'.
3 VFD
4 NOT USED
5 TO PLC
6 EQUIPMENT ACCESS HATCH.
7 LEVEL METER
8 FLOW METER
9 HEADWORKS SCREEN CONTROL PANEL
10 AERIGATOR
11 AERIGATOR SOFT START. RUN WITH ON / OFF TIMER FROM PLC WITH OPERATOR-SETTABLE TIMER.
12 CLASSIFIED TRANSITION. SEE DETAIL 9 / E-502.
13 MANUFACTURER'S CABLE INCLUDES TEMPERATURE SWITCH SHUTDOWN WIRING.
14 TO HEADWORKS MOTOR CONTROL PANEL IN PUMP BUILDING VIA CLASSIFIED TRANSITION. COMBINE DIGITAL CONTROLS FOR COMMON HOME RUN TO CONTROL PANEL.
15 WASHING PRESS CONSOLE
16 PLC CABINET BY IGOR KOVALENKO SUBCONTRACTED BY GENERAL CONTRACTOR. CABINET, PROGRAMMING, SCADA INTEGRATION BY IGOR. CABINET INSTALLATION AND FIELD WIRING BY ELECTRICAL CONTRACTOR.
17 HEADWORKS VENT FAN CONTROLLER
18 GAS ALARM PANEL
19 TO GAS ALARM PANEL VIA CLASSIFIED TRANSITION
20 GRINDER CONTROL PANEL
21 SEE ALSO POWER PLAN FOR WIRING INSTRUCTIONS.
22 NOT USED
23 TANK LEVEL
24 1-1/4" CONDUIT WITH #14 CONTROL WIRE PAIRS. COORDINATE WITH MANUFACTURER FOR THE FOLLOWING:
-HOPPER SPRAYWASH SOLENOID
-WMP AUGER SPRAYWASH SOLENOID
-SCREEN OVERTORQUE
-SCREEN MOTOR OVERTEMP
-GRINDER MOTOR OVERTEMP
-AUGER MOTOR OVERTEMP
-(2) LOCAL E-STOP
-SCREEN HAND
-SCREEN AUTO
-SCREEN FWD/REV
-GRINDER HAND
-GRINDER AUTO
-GRINDER FWD/REV
-AUGER HAND
-AUGER AUTO
-AUGER FWD/REV
-(3) SPARE PAIRS







1 I-101 MAIN LEVEL CONTROL PLAN
SCALE: 1/4"= 1'-0"



HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED RJH	3				
DRAFTED KGM	2				
CHECKED RJH	1				
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE .

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
TOP FLOOR CONTROL PLAN


SHEET I-101

126.42.300

I:\2005901 - DWG\ELEC\SHEET\20058 - I-101.dwg, 4/19/2024 5:02:25 PM, Heath Engineering cw:GJE

DRAWING NOTES

1. LEVEL TRANSDUCERS
2. TO SCREEN CONTROL
3. TO COMBUSTIBLE GAS ALARM PANEL
4. COMBUSTIBLE GAS DETECTOR
5. TO HEADWORKS CONTROL PANEL VIA CLASSIFIED TRANSITION COMBINED WITH OTHER DIGITAL SIGNALS.
6. FLOOD FLOAT SWITCH
7. GRINDER TEMPERATURE SWITCH



A
I-301
ELECTRICAL SECTION
SCALE: 1/4"=1'-0"

5 0 10

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
04/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS

HEATH Engineering Company

DESIGNED RJH	3		·			SCALE ·
DRAFTED KGM	2					
CHECKED RJH	1					
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.	

SOUTH SALT LAKE


DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
ELECTRICAL CONTROL SECTION

SHEET
I-301
126.42.300

I:\2005801 - DWG\ELEC\SHEET\2005S - I-301.dwg, 4/19/2024 5:02:28 PM, Heath Engineering cox\GJE

GENERAL NOTES

A. SEE SPECIFICATIONS FOR CONTROL NARRATIVE



PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
04/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS	HEATH Engineering Company	DESIGNED RJH	3				
		DRAFTED KGM	2				
		CHECKED RJH	1				
		DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.

SCALE

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
ONE-LINE DIAGRAM

SHEET I-601

126.42.300

I:\26058\01 - DWG\ELEC\SHEET\26058 - I-601.dwg, 4/19/2024 5:02:31 PM, Heath Engineering co\GJE

SCADA

PLC-1

PUMP ROOM HIGH TEMP — TAH 218
PUMP ROOM LOW TEMP — TAL 218
WET WELL PUMP ROOM TEMP — TIR 218 — TI 218
ELEC. ROOM HIGH TEMP — TAH 219
ELEC. ROOM LOW TEMP — TAL 219
ELEC. ROOM TEMP. — TIR 219 — TI 219
DRY PIT HIGH LEVEL — LAH 228 — LAH 228
GRINDER RUNNING — XI -
GRINDER ALARM — XI -
SCREEN RUNNING — XI -
AUGER RUNNING — XI -
MOTOR CONTROL ALARM — YA -
SCREEN ROOM HIGH LEVEL — LAH -
SCREEN INFLUENT LEVEL — LT -
SCREEN EFFLUENT LEVEL — LT -
SCREEN HIGH LEVEL ALARM — LAHH -
FLAMMABLE GAS LEL — AT -
FLAMMABLE GAS ALARM HI — AAH - — 10%
FLAMMABLE GAS ALARM HI-HI — AAHH - — 20%
LOW LOW FUEL LEVEL — LALL 222
LOW FUEL LEVEL — LAL 222
FUEL STORAGE TANK LEVEL — LI 222 — LI 222
FUEL STORAGE TANK LEAK ALARM — YA 223 — YA 223
GEN PR-ALARM — YA1 220
GENERATOR RUNNING — YIR 220
GENERATOR NOT IN AUTO — YA2 220
GENERATOR FAILURE — YA3 220
ATS NORMAL POSITION — YI1 221 — YI1 221
ATS STANDBY POSITION — YI2 221 — YI2 221
ELECTRICAL ROOM DOOR OPEN — YA 230 — ZA 230

COM
COM
NETWORK
C106
C105
HEADWORKS SCREEN CONTROLLER
MULTIPLE SIGNALS. SEE PLANS
C112
LE -
LE -
FROM HEADWORKS
TO SYSTEM
HEADWORKS SCREEN

C100
GRINDER CONTROLLER
HEADWORKS EQUIPMENT

LSH 229
FLOOD SWITCH

C101
R
24V
GAS PANEL
C109
C101
AE

C101
C101

C106
C109

GENERATOR ALARM RELAY CONTACTS
C110
HOA — HS 220
ESTOP — HS 220
RUNNING — YI 220
FAIL — YA 220
IN AUTO — YI 220
FAIL — YI 220
RUN
C100
GENERATOR

LT 223
YA 223
FUEL STORAGE TANK

ATS-1

C100

TIT 218 — PUMP ROOM TEMP.
TIT 219 — ELECTRICAL ROOM TEMP.
LSH 228 — FLOOD SWITCH

DS 230A
DS 230B
C100

PROFESSIONAL ENGINEER
11573207-2202
ROBERT J. HILLYER
09/19/2024
STATE OF UTAH

HANSEN ALLEN & LUCE inc ENGINEERS
HEATH Engineering Company

DESIGNED RJH	3		·			
DRAFTED KGM	2					
CHECKED RJH	1					
DATE MAY 26, 2022	NO.	DATE	REVISIONS	BY	APVD.	

SCALE ·

SOUTH SALT LAKE

DOWNTOWN SEWER IMPROVEMENTS AND PUMP STATION
ELECTRICAL
ONE-LINE DIAGRAM

SHEET I-602
126.42.300

I:\2065\501 - DWG\ELEC\SHEET\2065S - I-602.dwg, 4/19/2024 5:02:34 PM, Heath Engineering csv\GJE